Kennedy/Jenks Consultants

303 Second Street, Suite 300 South San Francisco, California 94107 415-243-2150

Valley Water Management Company Technical Evidence and Edison Oilfield Subsurface Investigations Phase 2 Final Report

30 June 2015



Prepared for

Valley Water Management Company

7510 Meany Avenue Bakersfield, CA

K/J Project No. 1365027*00

Table of Contents

List of Tables			ii
List of Figures			ii
List of Append	lices		ii
Executive Sun	nmary		ES-i
Section 1:	Intro	oduction	1
	1.1	Background	1 2
	1.2	Regulatory History	
Section 2:	Pha	se 1 and Phase 2 Investigations	6
	2.1 2.2 2.3 2.4	Shallow Groundwater Investigations 2.1.1 Fee 34 Facility Field Work and Results 2.1.2 Race Track Hill Field Work and Results Deep Groundwater Investigations Results of Nearby Off-Site Well Sampling Analysis of Historical Flows to the Fee 34 and Race Track Hill	6 7 9
		Facilities	12 12
Section 3:	Ana	lysis and Summary of Investigation Results	15
	3.1 3.2 3.3	Water Quality and Isotopic Evidence of Potential Impacts	16 18 18
References			21

List of Tables

- 1 Shallow Monitoring Well Construction Data
- 2 Shallow Groundwater Level Data
- 3 Groundwater Quality Data for Monitoring Wells and Off-Site Wells
- 4 Deep Monitoring Well Construction Data
- 5 Water Level Data for Deep Monitoring Wells March 17, 2015
- 6 Produced Water Quality: 1961 to 2015
- 7 Produced Water Discharge Flows: 1960 to 2014
- 8 Monthly Precipitation and Evapotranspiration for the Race Track Hill Area

List of Figures

- 1 Locations of Valley Water Management Company Edison Oil Field Facilities
- 2 Fee 34 (C Plant) Produced Water Collection and Treatment Facility
- 3 Race Track Hill Produced Water Discharge Facility
- 4 Fee 34 Boring-1 EC, Soil Moisture, Boron, and Chloride Depth Profiles
- 5 Race Track Hill Borings RTH-1 and RTH-2 EC, Boron and Chloride Depth Profiles
- 6 Shallow Groundwater Level and Direction of Groundwater Flow, December 2014
- 7 Deep Groundwater Level and Direction of Groundwater Flow, March 2015
- 8 Off-Site Well Locations
- 9 Produced Water Discharges and Evaporative Losses at Race Track Hill
- 10 Groundwater Quality Scatter Plots
- 11 Trilinear Diagram for Monitoring wells and Off-Site Wells
- 12 Stable Isotope Analyses of Groundwater at the Fee 34 and Race Track Hill Facilities
- 13 Historical Photographs Race Track Hill
- 14 Historical Photographs Cottonwood Creek

List of Appendices

- A Phase 2 Interim Report
- B Report on Phase 2 Installation of Shallow Monitor Wells at Race Track Hill
- C Report on Installation of Deep Monitor Wells at the Valley Water Management Company Race Track Hill and Plant C Facilities in Kern County
- D Laboratory Reports
- E Monthly Produced Water Flows for 2010 Through 2014
- F Report on Runoff Conditions at the Race Track Hill Facility, Kern County, CA

Executive Summary

This Technical Evidence and Phase 2 Subsurface Investigation Final Report (Report) has been prepared by Kennedy/Jenks Consultants (Kennedy/Jenks) on behalf of Valley Water Management Company (Valley Water). This represents the final report required by a 13267 Order issued to Valley Water on 1 July 2014 as well as Valley Water's evidence to rebut the allegations contained in the proposed Cease and Desist Order (CDO) and the Prosecution Team's Opening Submission of June 12, 2015.

In addition to other information, the findings of two phases of subsurface investigations are presented. Observations regarding the fate and transport of salinity constituents in produced water are developed based on available information including:

- Direct results of the Phase 1 and Phase 2 subsurface investigations of deep and shallow groundwater. Portions of the technical work were conducted by Kenneth D. Schmidt and Associates; Dee Jaspar and Associates; Stuart Childs and Gary Carlton, Kennedy/Jenks; Jim Waldron, Valley Water; and their associates and subcontractors.
- Additional sampling and analysis of groundwater from eight wells installed as part of the investigations
- Sampling and analysis of off-site wells in the vicinity of Race Track Hill
- Review of historical flows discharged to the Fee 34 Facility and Race Track Hill.

Figures 1, 2, and 3 show the locations of the facilities addressed in this report.

Fee 34 Facility

This 3.4 acre Facility is permitted as an oilfield produced water collection and treatment facility near Edison, California. The Facility is located in the active production area of the Edison Oil Field. Produced water from a number of small, independent oil leases in the Edison Oil Field is transported to the facility by pipeline and flows into qunite-lined ponds where crude oil is skimmed from the water. The treated produced water is then pumped to the Race Track Hill Facility and into unlined sumps and onto irrigation areas.

Subsurface investigations included collection and analysis of soil samples to 200 feet below ground surface (bgs); installation and sampling of a groundwater monitoring well screened at a depth of 395 to 435 feet bgs; and leak testing of two of the lined ponds used for produced water treatment.

Soil Boring. A soil boring was advanced at a location 10 feet from an unlined skimmed oil pond and within 30 feet of the produced water treatment ponds. Samples were collected and analyzed for water content, EC, boron, chloride, and Total Petroleum Hydrocarbons as crude oil (TPHc). No perched water was encountered while advancing the boring and none of the measured results for water content gave any indication of accumulation of percolating water or groundwater. TPHc concentrations were not detected at any depth below 5 feet bgs where the concentration was 220 mg/kg, well below the environmental screening level of 500 mg/kg. In addition, no elevated EC levels or concentrations of boron or chloride were observed in the soil boring samples. The result of this evaluation was documentation that neither water nor the constituents commonly found in produced water were encountered at elevated levels in the

unsaturated zone beneath the Fee 34 Facility. This corroborates the finding of a May 1996 soil boring study that also showed no evidence of produced water movement in the unsaturated zone.

Monitoring Well Installation and Sampling. Groundwater monitoring well C-1D was installed adjacent to the produced water treatment and storage ponds and sampled in early 2015. At the time of sampling, the water level was 298.4 feet bgs. Water chemistry of the sample collected documented low levels of boron, chloride, and EC. More detailed analyses of a larger suite of constituents demonstrated that the characteristics of the groundwater have not been influenced by produced water from the Fee 34 Facility.

Leak Testing of Two Produced Water Treatment Ponds. A Spring 2014 initial round of leak testing of the gunite-lined ponds indicated that the estimated range of pond seepage was 0.3 to 3.3 mm/day for the South Pond and 3.3 to 5.5 mm/day for the North Pond. These initial leak tests were undertaken during non-ideal meteorological conditions solely for the purpose of obtaining an indication as to whether any major seepage was occurring from these ponds. As stated in the Phase 1 Report, more precise and accurate results would be obtained by conducting tests during rain-free periods between December and February, when errors due to the measurement of evaporation are minimized. These initial pond seepage values are quite low and, as stated above, there is no indication from the soil boring and groundwater monitoring well datasets that any minor seepage that may have occurred has reached groundwater.

Fee 34 Facility Summary. The most important finding was the water quality analysis of groundwater from monitoring well C-1D that taps first encountered groundwater beneath the Fee 34 Facility. Water quality of this well indicates that groundwater beneath the Facility does not have elevated concentrations that would indicate the influence of produced water. This conclusion is supported by the lack of water or elevated zones of produced water constituents in the unsaturated zone from both the 1996 and 2014 investigations.

Race Track Hill Facility (RTH)

This Facility consists of 240 acres located approximately four miles northeast of the Fee 34 Facility. There are 27 unlined surface impoundments used for produced water percolation and evaporation. Tamarisk trees (also known as Salt Cedar) were planted around the percolation ponds in 1960 to increase evaporative water loss by transpiration. There are approximately 91 acres with sprinkler irrigation systems that are used to apply produced water to salt-tolerant local grasses and some shrubs.

Eight groundwater monitoring wells have been installed and sampled at this Facility. Three wells are completed in deep groundwater and five are completed in shallow groundwater. Four existing off-site wells have also been sampled. Samples from four soil borings have been analyzed for produced water constituents to characterize unsaturated zone conditions. Finally, an evaluation of produced water percolation at RTH has been conducted.

Soil Borings. A dataset of soil EC and concentrations of boron and chloride were collected to determine whether long-term produced water irrigation has affected soil salinity. The results summarized in this report indicate that boron accumulates in the surface three feet of soil under irrigated conditions. There are some apparently random peaks for measured constituents at various depths in the soil profiles, but effects specific to the irrigated area boring other than

boron cannot be identified. There is no indication of salt (EC or chloride) accumulation in the irrigated area at RTH.

Groundwater Flow. Water level measurements for the five shallow groundwater wells show that there is a groundwater flow gradient to the northeast on the east side of RTH. In addition, the water levels in wells on the upper portion of RTH indicate that there may be a groundwater mound in the shallow groundwater.

The deep groundwater flow direction is indicated to be to the north-northwest based on March 2015 measurements. The water level elevations do not indicate a groundwater mound in the deep groundwater.

Groundwater Quality. Groundwater quality information was collected for three sets of wells: shallow groundwater at or near RTH, deep groundwater at RTH, and nearby off-site wells:

- Three of the shallow groundwater wells (RTH-1, 4, and 6) installed near evaporation/percolation ponds have groundwater chemistry that appears to be affected by produced water. A fourth well installed at the eastern base of RTH (RTH-3) has unique water chemistry, primarily due to high sulfate concentration. The fifth shallow well (RTH-5) was installed east of RTH near Cottonwood Creek to determine whether produced water had moved off-site in that direction. Water quality results indicate that this well has not been influenced by produced water.
- Three deep groundwater wells installed on RTH (RTH-7D, 8D, and 9D) represent two types
 of groundwater quality. Water from the well at the base of the northeast corner of RTH
 (RTH-8D) shows groundwater mixed with produced water. The remaining two wells, on the
 western side of the site, (RTH-7D, 9D) have some indication that irrigation with produced
 water has mixed with local groundwater with high sulfate concentrations.
- Four off-site wells near RTH were sampled to assess whether off-site effects of produced water could be documented. Two wells (24J and 12F) were sampled along Cottonwood Creek, one upstream of the location where Breckenridge Road crosses the creek and one downstream. These two wells have water quality very similar to the shallow groundwater monitoring well near Cottonwood Creek (RTH-5) and none of them show any water quality effects related to produced water percolation at RTH. The lack of mixing at the downstream shallow well is an important finding because it documents that, at this location, there is no groundwater impact or imminent threat to groundwater.

One of the remaining two off-site wells is northwest of RTH and the other is southwest of RTH. Neither of these wells has water quality that suggests mixing with produced water. Considering the locations of water supply wells, none are directly downgradient of the Race Track Hill Facility in terms of the direction of deep groundwater flow. This also indicates that there is no imminent threat to groundwater.

Produced Water Flows to Race Track Hill. Records of produced water flows were compiled for 1960 through 2014. This dataset was used to calculate the total volume of produced water pumped to RTH over 54 years of record. A water balance for RTH was developed to determine the amount of produced water evaporated from the evaporation/percolation ponds and lost by evapotranspiration from the Salt Cedar trees and the irrigated areas. The total volume was 8,350 million gallons (MG) and combined evaporative losses were calculated to be between 45 and 49 percent of the total volume: approximately 3,750 – 4,120 MG. Of this total,

approximately 60 percent of total evaporative loss was from evapotranspiration at the irrigated areas. The practice of irrigating salt tolerant grasses and shrubs is an important part of water management at RTH. Aerial photographs of the facility show the beneficial impact on vegetation growth.

The net seepage of produced water to the subsurface at RTH is calculated to be 4,200 – 4,600 MG (12,900 - 14,100 Acre-feet). After accounting for the porosity of the sediments beneath RTH, the total volume needed to store this volume of water would be 43,000 – 47,000 Acre-feet. This amount of sediment would occupy about 200 feet of thickness beneath a 200 acre area.

It should also be noted that the produced water flows from 1960 to 1968, were higher and were applied to a much smaller land area than is used today. The combination of high flows and small land area would result in more percolation. It is likely that produced water reached groundwater during this period prior to the adoption of California's Antidegradation Policy. In fact, it can be presumed that after the initial 8 years of saline produced water discharge via percolation, that by 1968, the underlying ground water reflected mixing with produced water and was not high quality water based on EC or TDS, chloride, or boron concentrations.

Another facet of the produced water flows sent to RTH is the potential for runoff of produced water or produced water constituents deposited in the soil. Valley Water had no evidence of runoff from RTH even from the very large storm event in late December of 2010, so aerial photographs taken between 1992 and 2015 were reviewed for RTH and the Cottonwood Creek area to determine whether signs of erosion or runoff could be documented. The aerial photographs provide evidence that the landscape does not show changes related to erosion and there is no evidence of vegetative growth that would be caused by surface water runoff. In addition, survey work was undertaken at RTH to confirm the adequacy of pond storage and freeboard, drainage ditches and catchment basins to contain produced water and unusual precipitation events on site. During the course of this field work, the trained survey crew has not observed signs of sheet erosion or sediment rills. The existing configuration of ponds, ditches, and catchment basins is adequate to prevent run-off from the Race Track Hill Facility.

Conclusions of the Technical Evidence and Phase 2 Final Report

Valley Water operates an oil field produced water treatment facility and a disposal facility in the Edison Oil Field. Both were evaluated as part of the technical studies reported here:

Fee 34 Facility. The most important finding was the water quality analysis for groundwater underlying the facility. This dataset indicates that underlying groundwater does not have elevated concentrations that would indicate the influence of produced water. This facility has not impacted groundwater; therefore, no further investigations are proposed.

Race Track Hill Facility. At the Race Track Hill Facility, produced water is applied to 27 evaporation/percolation ponds and 91 acres of sprinkler irrigated vegetation. Groundwater studies indicate mixing of produced water and groundwater in the shallow groundwater at the site. There is less mixing of produced water in the deep groundwater at the site. Water quality data collected from four off-site water supply wells and one off-site monitoring well indicate no effect of produced water on groundwater quality.

The final conclusions all reiterate that there is no imminent threat of harm to soil, off-site groundwater users, or surface waters from Valley Water's activities at the Facilities.

Section 1: Introduction

This *Technical Evidence and Phase 2 Subsurface Investigation Final Report* (Report) has been prepared by Kennedy/Jenks Consultants (Kennedy/Jenks) on behalf of Valley Water Management Company (Valley Water). The Report summarizes the Phase 1 and 2 subsurface investigation results for Valley Water's Edison Oil Field Facilities, Race Track Hill and the Fee 34 Facility (also known as the C Plant). The shallow subsurface investigations and reports were conducted by Kennedy/Jenks (Appendix A, Appendix B) and deep subsurface investigations were conducted and reported by Kenneth D. Schmidt and Associates (KDSA, 2015; Appendix C). Research to identify off-site wells was conducted by Dee Jaspar and Associates (DJA). Laboratory results for wells that were sampled are included in Appendix D. Other analysis was provided by Stuart Childs and Gary Carlton of Kennedy/Jenks, Jim Waldron, and other associates and consultants.

This summary report provides a synthesis of the findings of both the Phase 1 and Phase 2 Subsurface Investigations. Phase 1 results have been summarized previously in the *Phase 1 Subsurface Investigation Report* (Kennedy/Jenks, 2014b) and Phase 2 shallow investigations were reported in the *Interim Report on Phase 2 Subsurface Investigations* (Kennedy/Jenks, 2015a; Appendix A) and the well completion report (Kennedy/Jenks 2015b; Appendix B).

Observations regarding the fate and transport of salinity constituents in produced water are developed based on available information including:

- The direct results of the Phase 1 and Phase 2 subsurface investigations
- Additional sampling and analysis of groundwater using the wells installed as part of investigations
- Sampling and analysis of off-site wells in the vicinity of Race Track Hill
- Review of historical flows to the Fee 34 Facility and Race Track Hill as well as an evaluation of percolation and evapotranspiration.

1.1 Background

Valley Water is a non-profit corporation that provides produced water treatment and management services to small independent oil producers in the Edison Oil Field. The Fee 34 and Race Track Hill Facilities are owned and operated by Valley Water (Figure 1).

1.1.1 Description of the Fee 34 Facility

The Fee 34 Facility covers 3.4 acres (Assessor's Parcel Number 388-050-254 in the southwest quarter of the southwest quarter of Section 34, T29S, R29E, MDB&M) and is an oilfield produced water collection, treatment, and shipping facility located approximately one mile northeast of the community of Edison. The Fee 34 Facility operates under California Regional Water Quality Control Board, Central Valley Region (CVRWQCB) Waste Discharge Requirements (WDR) Order No. 92-11037, a Notice of Applicability for General Order No. 92-110. There are six surface impoundments at the facility (Figure 2). Produced water is transported to the facility by pipeline from various small, independent oil leases throughout the

Edison Oil Field. Produced water flows into two gunite-lined ponds where a skimming process is used to remove any remaining crude oil. Water then flows through adjustable weirs into a larger lined pond (the shipping pond) on the west side of the property. The treated produced water is then pumped from the shipping pond to the Race Track Hill Facility for percolation from unlined sumps, irrigation, and evaporation.

1.1.2 The Race Track Hill Facility

The Race Track Hill site consists of 240 acres (Assessor's Parcel Number 387-060-031) in the northwest quarter, and the north half of the southwest quarter of Section 24, T29S, R29E, MDB&M, approximately four miles northeast of the Fee 34 Facility in an area of steep and rolling topography in Kern County (Figure 3). There are 27 unlined surface impoundments used for produced water percolation and evaporation. Tamarisk trees (*Tamarix* spp.), also known as Salt Cedar) were planted around the original 17 percolation ponds in 1960. This facultative phreatophyte species (Zouher, 2003) is capable of extracting considerable water from shallow water tables and can tolerate high salinity levels. This type of vegetation was planted at Race Track Hill to provide additional evapotranspiration of water from the ponds.

The site utilizes approximately 91 acres for irrigation by sprinkler irrigation systems to apply produced water to salt-tolerant local grasses and some shrubs that have been planted in the irrigation areas at Race Track Hill. Produced water flow from the Fee 34 Facility enters Race Track Hill at a netted pond located at a high elevation with respect to the rest of the facility. Gravity is used to distribute produced water to evaporation/percolation ponds and spray irrigation areas to aid in water loss by evapotranspiration. The Race Track Hill Facility operates under WDR Order No. 58-349.

1.1.3 Climate Information

Reference evapotranspiration (ET0) data for the area were collected from the California Irrigation Management Information System (CIMIS) Arvin-Edison Station 125. Annual ET0 totals 61.1 inches with data ranging from an average of 1.4 inches in December and to an average of 9.1 inches in July based on a dataset from 1995 to 2015 (CIMIS, 2015).

Rainfall data for the area were collected from the Western Regional Climate Center (WRCC) database for the Bakersfield Airport WSO, Station 040442. Average annual precipitation at this station is 6.11 inches (WRCC, 2015). The 100-year return annual total precipitation was calculated using the probability distribution of annual precipitation from 1938 to 2014. The 100-year return period annual precipitation is 14.6 inches. The 100-year, 24-hour storm event is 3.00 inches (Appendix F).

A basic hydrologic analysis was performed to determine maximum historic precipitation events that have occurred in the area. Based on data obtained from the Bakersfield Airport WSO station, the maximum 30 day total precipitation on record was 5.98 inches from 5 December 2010 through 3 January 2011 based on a daily period of record from 1938 – 2015. The maximum 7 day total precipitation on record was 4.58 inches from 17 December 2010 through 23 December 2010. Note that the wettest 7 days on record were during the wettest month on record. The maximum one day rainfall on record was 2.29 inches on 9 February 1978.

1.2 Regulatory History

The regulatory history of the Valley Water produced water management areas can be summarized as follows:

- 18 September 1958 Waste Discharge Requirements (WDRs) were issued to Valley Water's Race Track Hill Facility by the Regional Water Board through Res. No. 58-349. (CVRWQCB, 1958).
- 8 April 1991 The Regional Board requested a Technical Report/Report of Waste Discharge for oilfield produced water facilities in the Edison area of Kern County. (CVRWQCB, 1991.)
- 21 June 1991 Valley Water provided the information requested in the Regional Board's 8 April 1991 letter, but informed the Regional Board that the Race Track Facility was covered by WDRs.
- 29 May 1992 WDRs were issued to Valley Water's Fee 34 Facility in the Edison Oil Field through a Notice of Applicability to be covered under General Order No. 92-110. (CVRWQCB, 1992).
- 24 May 1996 Valley Water's predecessor submitted a report in accordance with Order No. 92-110, which required a plan be submitted for achieving compliance with that Order. One compliance pathway was to "demonstrate to the Board in a public hearing that the proposed discharge will not substantially affect water quality or cause a violation of water quality objectives in accordance with Resolution No. 82-136." On this date, a report entitled "Drilling and Data Acquisition Report" was submitted to the Regional Board in order to prove that the Fee 34 facility "does not pose a threat to ground water quality and that no further action should be required for continued operation of the site." In this same submittal, a public hearing was requested, but no hearing was ever granted by the Water Board to allow for this demonstration to be made under the WDRs (Kennedy/Jenks Consultants, 1996).
- 16 August 1996 In a Regional Board inspection report on this date, the Regional Board acknowledged that "Valley Waste Disposal recently submitted a report, *Drilling and Data Acquisition Report*, to demonstrate that the C-Plant (Fee 34) will not affect water quality. The report is currently being reviewed."
- 20 June 2012 The first inspection reports to indicate any violations. Valley Water implemented modifications to the facilities (e.g., netting of ponds) to address several of the issues.
- 28 June 2012 First Notice alleging violation at the Fee 34 Facility since 1992 related to sumps not being netted to exclude wildlife. A similar notice was sent to the Race Track Hill Facility on July 10, 2012.

- 23 July 2013 CVRWQCB letter to Valley Water stating its intention to update the WDRs for all surface water impoundments for oil field produced water. This notice also requested specific information about the facilities and discharges. (CVRWQCB, 2013a)
- 9 October 2013 Valley Water and Kennedy/Jenks met with CVRWQCB staff and a representative of the State Water Quality Control Board legal staff.
- 10 October 2013 Valley Water was issued a Notice of Violation (NOV) for the Race Track Hill Facility claiming that the irrigation water being applied to land violated the WDRs, even though previous inspection reports had never deemed this activity to be a violation and it does not violate the plain terms of the permit. (CVRWQCB, 2013b). A NOV for the Fee 34 Facility was also issued on this date claiming insufficient freeboard in the ponds and alleging for the first time that high salinity wastewater poses a threat to groundwater (CVRQCB, 2013c).
- 8 November 2013 Valley Water provided responses to both of the October 2013 NOVs (Valley Water, 2013).
- 14 January 2014 At Valley Water's request, CVRWQCB staff met with Valley Water and their consultants to discuss the voluntary Phase 1 Subsurface Investigation at both facilities proposed by Valley Water.
- 5 February 2014 Draft Cleanup and Abatement Orders (CAOs) for each of the facilities were sent to Valley Water for review and comment (CVRWQCB, 2014a).
- 13 March 2014 Phase 1 Work Plan for Subsurface Investigations at the Fee 34 Facility and Race Track Hill Area was submitted to the CVRWQCB (Kennedy/Jenks, 2014a). Phase 1 investigations were developed based on requirements in the Draft CAOs and the intent was to characterize vadose zone and groundwater conditions beneath the Race Track Hill and Fee 34 Facilities and to provide an initial assessment of potential impacts of oil field produced water storage and discharge on underlying groundwater and soil. The Phase 1 investigations were conducted on a voluntary basis but under the guidance of the CVRWQCB.
- 4 April 2014. CVRWQCB email response to the Work Plan stating that the scope of the Phase I Work Plan seemed adequate.
- 1 July 2014 A 13267 Order was issued to Valley Water in lieu of the draft CAOs (CVRWQCB, 2014b). The Order required that all additional field investigations be completed by 15 January 2015.
- 31 July 2014 Valley Water appealed the terms of the July 2014 13267 letter to the State Water Board due to the unreasonable timeframes that could not be reasonably met. No response to this petition for review was received, except an acknowledgement of filing.

- 1 August 2014 Phase 1 Subsurface Investigation Report at the Fee 34 Facility and Race Track Hill Area submitted to CVRWQCB (Kennedy/Jenks, 2014b). This included a proposal for Phase 2 investigations.
- 2 October 2014 At Valley Water's request, Valley Water met with CVRWQCB to discuss the Phase 1 report and propose Phase 2 investigations.
- 10 November 2014 Phase 2 Investigation Work Plans were submitted to the CVRWQCB (Kennedy/Jenks, 2014c; KDSA, 2014).
- 15 January 2015 Interim Report on Phase 2 Subsurface Investigations was submitted to the CVRWQCB (Kennedy/Jenks, 2015a). This report included preliminary results for the shallow aquifer investigations.
- 1 April 2015 The Regional Board issued a Water Code section 13267 Order requiring collection and analysis of wastewater samples from each of the ponds listed, including those at the Fee 34 and Race Track Hill Facilities (CVRWQCB, 2015a).
- 30 April 2015 A draft Cease and Desist Order (CDO) was provided to Valley Water for comment. Valley Water provided detailed comments on May 11, 2015, and respectfully requested that the CVRWQCB defer issuance of any further enforcement orders until the results of the Phase II Workplan were submitted in the near future.
- 1 May 2015 Valley Water receives NOV in response to the Phase 2 results included in the Interim Report submitted 15 January 2015 (CVRWQCB, 2015b).
- 18 May 2015 Tentative CDO was issued for the Race Track Hill Facility and Fee 34 Facility (CVRWQCB, 2015c).
- 15 June 2015 Valley Water submitted technical information requested in the April 1, 2015 13267 Order (Valley Water, 2015).
- 30 June 2015 Evidence submitted to CVRWQCB in preparation for hearing on 31 July 2015 (Downey Brand, 2015).

Section 2: Phase 1 and Phase 2 Investigations

This section provides a summary of all investigations at the site. In Section 3, further analysis is provided to combine available information for the sites.

During conversations among Valley Water, its consultants, and CVRWQCB staff and managers in 2013 and 2014, it was agreed that the investigations at both sites would be undertaken using a phased approach. A phased approach is most efficient for site investigations such as those conducted because results of one phase can be used to allow informed decisions regarding the next phases of investigations. Approval of and support for the phased approach are documented in submitted work plans and reports as well as in draft and final regulatory orders from CVRWQCB.

2.1 Shallow Groundwater Investigations

The Phase 1 shallow investigations were conducted to provide an initial assessment of the potential influence of oilfield produced water on underlying soil and shallow groundwater (Kennedy/Jenks, 2014b). The Phase 1 investigations at the Fee 34 Facility included: a) a deep soil boring to determine subsurface lithology, presence of moisture, and depth profiles of key constituents of produced water; and b) leak testing of the lined ponds. At the Race Track Hill Facility, four soil borings were advanced and monitoring wells were installed and sampled at three of the boring locations (Figure 3).

Phase 2 shallow groundwater investigations were conducted based on the results of Phase 1 to provide further assessment of shallow groundwater conditions at the Race Track Hill Facility (Kennedy/Jenks, 2014c). The investigations at the Race Track Hill Facility included installation and sampling of two additional shallow monitoring wells (RTH-5 and RTH-6) in assumed downgradient locations (Figure 3) to augment the three shallow monitoring wells installed during Phase 1.

Results for the Phase 1 shallow investigations were submitted to the CVRWQCB on 1 August 2014 (Kennedy/Jenks, 2014b). Preliminary results for the Phase 2 shallow groundwater investigations (Interim Report) were submitted to the CVRWQCB on 15 January 2015 and are included in this report as Appendix A (Kennedy/Jenks, 2015a; Appendix A). The Shallow Monitoring Well Installation Report is included as Appendix B of this report (Kennedy/Jenks, 2015b; Appendix B).

2.1.1 Fee 34 Facility Field Work and Results

At the Fee 34 Facility, a soil boring was advanced to 200 feet below ground surface (bgs) at a location 10 feet from the unlined skimmed oil ponds and within 30 feet of the produced water treatment ponds (Figure 2). Samples were collected at 5 foot depth increments to 50 feet below ground surface (bgs) and then every 10 feet to 200 feet. The boring log (Kennedy/Jenks, 2014b) shows that the dominant texture of the subsurface material was well graded sand with granitic gravel, with a smaller portion composed of silty sand. No distinct clay layers were observed, but silt to sandy silt was encountered from 48.5 to 56 feet bgs, and from 88 to 90 feet bgs. No perched water was encountered while advancing the boring. The measured results give no

indication of accumulations of percolating water and no groundwater was encountered in the 200 foot boring.

At all depths between 10 and 200 feet, Total Petroleum Hydrocarbons as crude oil (TPHc) concentrations were below the detection limit, 20 mg/kg. The sample collected at 5 feet bgs had a TPHc concentration of 220 mg/kg, well below the environmental screening level of 500 mg/kg (San Francisco Bay Regional Water Quality Control Board, 2013).

No high EC levels or concentrations of boron or chloride were observed in the soil boring (Figure 4). As stated previously, no perched water was encountered while advancing the boring. Soil materials were observed to be dry in the sandy material above these finer-grained layers giving no indication of subsurface movement of water in the unsaturated zone beneath the facility. This is consistent with the results of soil borings taken beneath the Fee 34 Facility nearly 20 years ago in 1996 (Kennedy/Jenks, 1996).

Leak tests were conducted for two of the three lined ponds (North Pond and South Pond) at the Fee 34 Facility to evaluate whether produced water may be seeping through the gunite-lined ponds. The procedure used, based on the techniques of Luhdorff and Scalmanini (2012) and Ham and Baum (2002, 2009), made use of precision monitoring of pond water levels and monitoring of microclimate variables required to calculate pond evaporation rate. These initial tests were conducted during the warm season, late April and May, when errors that are part of measuring the microclimate variables (air temperature, relative humidity, pond surface temperature, and wind speed) are largest. Therefore, it is recommended practice to make leak test measurements during the winter months when evaporation is lowest to get the best accuracy. The initial tests were conducted recognizing that the results might not be sufficiently accurate to precisely assess the low levels of seepage anticipated.

The results of these tests show that the apparent seepage rates of the North Pond and the South Pond average 4.4 millimeters per day (mm/day) and 1.8 mm/day, respectively. The range of uncertainty around these average values was evaluated using two standard deviations based on the 15 minute readings. Using the measured uncertainty for the South Pond, the result of the test ranges from 0.3 to 3.3 mm/day. The uncertainty for the North Pond ranges from 3.3 to 5.5 mm/day. The North Pond test was expected to have additional error associated with the results due to the precipitation events that occurred during the test period and the uncertain accuracy of the precipitation gauge. The average seepage rates measured for the North Pond (approximately 500 gallons per day), range from 380 to 620 gallons per day. The range in uncertainty around the average value of approximately 200 gallons per day from the South Pond is 30 to 370 gallons per day. These initial estimates of seepage indicate that there are not large water losses from the ponds, but the overall accuracy does not allow a final determination of seepage rate.

2.1.2 Race Track Hill Field Work and Results

Soil Borings. As part of the Phase 1 investigations, four soil borings were advanced at the Race Track Hill Facility in April 2014 (Kennedy/Jenks, 2014b). Two of the borings were in the central swale adjacent to the percolation ponds (Figure 3). RTH-1 was in an irrigated area and RTH-2 was in an adjacent unirrigated area. Two more borings were advanced at the base of the swale on the east side of Race Track Hill adjacent to Breckenridge Road. RTH-3 was in a south to north trending dry swale along Breckenridge Road just downstream (north) of the central

swale and RTH-4 was located in the northern swale below the percolation ponds. RTH-3 and RTH-4 were located in order to provide representative groundwater monitoring wells. Both are in areas with no irrigation and in swales where surface water may occasionally flow.

The boring logs completed at Race Track Hill indicated that much of the lithology consists of silty sand, silty clayey sands, well-graded sands, and poorly graded sands (Kennedy/Jenks, 2014b). The proportions of these materials differed among the borings but, except for RTH-3, the surface materials were silty sands. Some thin, partially consolidated or cemented layers were observed in RTH-1, RTH-2, and RTH-3 but not in RTH-4. At RTH-4, drilling was difficult near the bottom of the boring, likely due to the presence of cobbles. These cobbles may indicate that stream channel deposits are present in the subsurface of the swale where RTH-4 is located. In all borings, there was little moisture noted in the subsurface. Some moisture increase was observed in occasional finer textured layers, but there were no cases in which free water was observed above first encountered groundwater.

EC, chloride, and boron profiles for the four borings are shown in Figure 5. Considerable variability exists in EC versus depth for each boring as well as among the four borings. Three of the borings show zones with higher EC than the average EC. The EC peak for RTH-4 is at 15 feet bgs; EC peaks in RTH-1 between 30 and 40 feet bgs, and RTH-3 peaks at 90 to 100 feet bgs. Each of these zones is in finer textured zones and RTH-3 is in the saturated zone. The boron soil profiles do not show peak concentrations at the same depths as EC. The only elevated boron zone occurs in RTH-1 in the surface 3 feet of soil. RTH-1 also has a chloride increase in a finer textured layer at 30 to 35 feet.

The soil boring results for Race Track Hill demonstrate the variability of EC, boron, and chloride in sediments between ground surface and groundwater. Figure 5 characterizes the variability of constituent concentrations in the soil by plotting the mean of all measured values shown as a vertical black line. The shaded areas on either side of the mean are one standard deviation in width. This figure shows that there are few values outside of the range shown. EC profiles show the most variability and boron has the lowest variability. The boron concentration increase near the soil surface of the irrigated area (RTH-1) reflects the adsorptive forces that bind boron to soil. No increases in chloride or EC in the shallow soil are observed in the dataset. At all depths below 40 feet, the natural variability of EC, boron, and chloride profiles among the borings indicates that produced water has not influenced constituent levels in the subsurface.

Shallow Monitoring Wells. Shallow monitoring wells (RTH-1, 3 and 4) were installed and sampled at three of the boring locations completed in Phase 1 (Figure 3). In December 2014, two additional shallow monitoring wells were installed as part of the Phase 2 investigations: RTH-5 was installed northeast of the Race Track Hill Facility near Cottonwood Creek and shallow monitoring well RTH-6 was installed on the southwest side of the southernmost surface impoundment at Race Track Hill (Figure 3). Table 1 provides information on shallow well completions at Race Track Hill (see also Appendix A and Appendix B).

Groundwater levels were measured in April and December 2014 at RTH-1, 3 and 4 and in December 2014 at RTH-5 and 6 (Table 2). Depth to groundwater at the Race Track Hill Facility occurs at depths ranging from 33 to 120 feet bgs. Shallow groundwater mounding was observed beneath the Race Track Hill Facility as indicated in Figure 6 for the December 2014 monitoring event, but not in the deep groundwater

The results of April 2014 and December 2014 groundwater sampling are shown in Table 3. Shallow groundwater beneath the Race Track Hill Facility has been influenced by the produced water that has percolated through the ponds and irrigation areas since 1958 at three locations: RTH-1, RTH-4, and RTH-6. The concentrations of boron and chloride in these limited locations can be explained by percolation of produced water at the Race Track Hill Facility. RTH-3 is at the base of Race Track Hill and, based on the high sulfate concentration, has likely been affected by more than one water source. Water chemistry at RTH-5 is much different than that of the other wells, and does not indicate any effect from the produced water percolation at Race Track Hill.

Total petroleum hydrocarbon-diesel (TPHd) concentrations ranged from less than non-detect to 240 μ g/l, well below environmental screening level for groundwater of 500 μ g/l for TPHd (San Francisco Bay Regional Water Quality Control Board, 2013). The only detectable TPHd concentration was in RTH-4.

EC and boron are highest at well RTH-1 and slightly lower at RTH-4 and RTH-6. These constituent levels are lowest at wells RTH-3 and RTH-5. RTH-5 is much lower in EC and B than all other wells, likely because it is furthest from Race Track Hill and has not been influenced by water from the Race Track Hill ponds. Wells RTH-3 and RTH-5 also have the lowest concentrations of TDS, calcium, chloride, and sodium.

2.2 Deep Groundwater Investigations

The Phase 1 investigations for the deep groundwater in the Race Track Hill and Fee 34 Facility areas consisted of the review of geologic and hydrogeologic information, and construction of a geologic cross section. This information was reported in the Phase 2 Work Plan for deep well installation submitted to the CVRWQCB in October 2014 (KDSA, 2014).

The Phase 2 subsurface investigations for the deep groundwater at the two Valley Water facilities consisted of installation, logging, sampling, and analysis of four monitoring wells (KDSA, 2015, Appendix C). The wells were installed and developed during January and February, 2015, and the initial monitoring was completed in March 2015.

Three deep monitoring wells (RTH-7D, 8D and 9D) were installed, developed, and sampled at the Race Track Hill Facility. Each well is located near produced water ponds and adjacent to a shallow monitoring well (Figure 3). One deep monitoring well (Well C-1D) was installed at the Fee 34 Facility and is located southwest of the large shipping pond (Figure 2). The well installed at the Fee 34 Facility taps the shallowest groundwater beneath the site.

Well Installation. Bradley & Sons of Del Rey, CA installed the deep monitoring wells by the direct rotary method during January 26 - February 24, 2015. An electric log and sonic log were run in the hole for each new monitoring well. A geologic log and well completion diagram for each monitoring well was also prepared (KDSA, 2015; Appendix C).

At the Race Track Hill Facility, saturated deposits at the time of drilling were indicated below depths ranging from about 70 to 155 feet. At the Fee 34 Facility, saturated deposits were indicated below a depth of 270 feet. Deposits opposite the perforated intervals of the new wells were primarily alternating layers of sand, gravel, and sandy clay. A five-inch diameter Schedule 40 PVC casing was installed in a twelve-inch diameter hole for each deep well at the Race

Track Hill Facility. At the Fee 34 Facility, a five-inch diameter Schedule 80 PVC casing was installed in a twelve-inch diameter hole. Flush joints and threaded ends were used and all joints for the casing were made using clean couplings. No glue or solvents were used in connecting the casing joints. Machine-cut 0.03-inch slot factory perforated was used for the perforated sections. Table 4 shows construction information for the deep monitoring wells.

Subsurface Geologic Conditions. A subsurface geologic cross section was previously developed that extended through the western and northern parts of the facility (KDSA, 2014). The shallowest deposits beneath the facility are part of the Kern River-Chanac Formation and are generally unconsolidated. These alluvial deposits dip to the southwest beneath the facility. These deposits pinch out east of the facility and are indicated to be about 700 feet thick near the west edge of the facility. The next deep deposits beneath the facility are the marine Santa Margarita Formation. These deposits are indicated to extend to a depth of about 800 feet near the northeast corner of the facility and to a depth of about 1,500 feet near the west edge of the facility. Beneath the Santa Margarita Formation is the Edison Shale, which is of low permeability and forms the base of the aquifer in the Race Track Hill area. Comparison of the logs for the deep monitoring wells with the cross section indicates that RTH-8D likely encountered the top of the Santa Margarita Formation at a depth of about 140 feet. The other two deep monitoring wells at the Race Track Hill Facility only encountered deposits of the Kern River-Chanac Formation.

At the Fee 34 Facility, the top of the Santa Margarita Formation is more than 1,200 feet deep. Water supply wells in this area and deep monitoring well C-1D tap deposits of the overlying Kern River-Chanac Formation (KDSA, 2014).

Groundwater Levels. Table 5 provides water-level data for the deep monitoring wells on March 17, 2015. The water-level elevation in C-1D at the Fee 34 Facility was 337.1 feet above mean sea level (AMSL).

Depth to water in the deep monitoring wells at Race Track Hill Facility ranged from 86.9 feet below the measuring point at RTH-8D to 225.3 feet at RTH-9D. Depth to water in C-1D at the Fee 34 Facility was 298.4 feet below the measuring point. Considering the depths where saturated deposits were indicated during drilling, the water levels in the completed wells indicate that the groundwater tapped by the wells is under a confining pressure. Dee Jaspar and Associates, Inc. of Bakersfield surveyed the elevations of the measuring points for the new wells. Water-level elevations for the monitoring wells at the Race Track Hill Facility ranged from 854.3 feet above mean sea level at RTH-7D to 787.8 feet at RTH-8D. Figure 7 shows water-level elevations and the direction of groundwater flow for the deep monitoring wells at the Race Track Hill Facility on March 17, 2015. A north-northwest direction of groundwater flow was indicated. This suggests that pumping of wells north-northwest of the facility has influenced the direction of groundwater flow. The water-level slope averaged about 130 feet per mile beneath the facility. To our knowledge, this is the first time that groundwater gradients in this area have been mapped.

Groundwater Quality. The four deep monitoring wells were sampled between March 11 and March 17, 2015. Three well volumes were removed by pumping from each well prior to the collection of water samples for laboratory analyses. The samples were preserved and shipped to FGL Environmental in Santa Paula for determination of inorganic chemical constituents and

total organic carbon (TOC), to APPL, Inc. in Clovis for total petroleum hydrocarbons-diesel (TPH-d), and to the University of Arizona Environmental Isotope Laboratory, Tucson, Arizona for the analysis of stable isotopes of water.

Table 3 summarizes the results of the laboratory analyses of water from the deep monitor wells, shallow monitoring wells, and nearby off-site wells. Total dissolved solids (TDS) concentrations in the water samples from the deep monitoring wells at Race Track Hill ranged from 2,960 to 4,180 mg/l. The lowest TDS concentration was at RTH-9D (2,960 mg/l), and the highest concentrations (3,900 to 4,180 mg/l) were in water from RTH-7D and RTH-8D. Chloride concentrations in water from these wells ranged from 820 to 2,060 mg/l. The chloride concentration was highest in water from RTH-8D and was lowest in water from RTH-9D. Boron concentrations in water from these wells ranged from 0.2 to 9.1 mg/l. The lowest boron concentrations (0.2 to 0.5 mg/l) were in water from wells RTH-7D and RTH-9D, and the highest concentration was in water from RTH-8D. Sulfate concentrations in water from these wells ranged from 23 to 910 mg/l. The lowest sulfate concentration was for RTH-8D and the highest concentrations (860 to 910 mg/l) were in water from RTH-7D and RTH-9D. Sulfate type groundwater was previously found at RTH-3, a shallow monitor well south of RTH-8D. TPHd concentrations ranged from less than 50 µg/l to 280 µg/l, well below environmental screening level for groundwater of 500 ug/l for TPHd (San Francisco Bay Regional Water Quality Control Board, 2013). The only detectable TPHd concentration was in RTH-8D.

2.3 Results of Nearby Off-Site Well Sampling

Four off-site wells were sampled to assess whether local area wells showed impacts related to produced water from Race Track Hill. Well locations are shown Figure 8. Figure 8 and the table below show the status of the wells identified in well records received from DWR. Wells 26B and 16H are downgradient of Race Track Hill. Wells 13A and 13B are located along Cottonwood Creek east of Race Track Hill. Well 24J is upgradient and likely represents background groundwater in the area of Cottonwood Creek. Well 12F is located along Cottonwood Creek, downstream from Breckenridge Road and just south of Highway 178.

Well Number	Depth, feet	Status/Comments
13A	80	Unused Industrial Well (Gravel Plant)
13B	60	Unused Industrial Well (Gravel Plant)
16H	741	Active Irrigation Well - Sampled
24J	360	Active Domestic Well - Sampled
24M	460	Unused Domestic Well, Corroded Casing, Well Cannot
24101	460	Be Sampled
26B	800	Active Domestic Well - Sampled
		Domestic Well -Not Found in the Field, May Have
26C	455	Been Destroyed – 1.05 miles West Southwest of Race
		Track Hill
26N	680	Unused Domestic Well – 1.6 miles Southwest of Race
ZUIN		Track Hill
12F	70	Unused Shallow Well - Sampled
·	·	

Water quality data for the wells sampled are shown in Table 3. EC and concentrations of TDS, boron, chloride, sodium, and calcium, are all low. These sample results indicate no influence on

water quality caused by produced water from the Race Track Hill Facility. Well 12F is located in the floodplain of Cottonwood Creek, and potentially downgradient of Race Track Hill, in terms of shallow groundwater. Results of this well sample provide evidence that groundwater beneath Cottonwood Creek has not been mixed with produced water. There are no other active supply wells indicated that are exactly downgradient of the Race Track Hill Facility, in terms of the deep groundwater. No imminent threat to groundwater supplies or to the Kern River was identified at this location.

2.4 Analysis of Historical Flows to the Fee 34 and Race Track Hill Facilities

The record of annual flows to Race Track Hill was compiled from Valley Water's records. In addition, the chronology of development of evaporation/percolation ponds and irrigated areas was also determined. This information was used to determine the total flow volume to Race Track Hill and the amount of water loss due to evaporation from the ponds and evapotranspiration from the irrigation areas. These two analyses allow calculation of the volume of produced water percolated to the subsurface and land applied at the Race Track Hill Facility.

2.4.1 Produced Water Quality for Valley Water Facilities

Table 6 shows available historical water quality data for produced water sent to Race Track Hill from 1960 through 2015. During this time period, EC ranged from 4,630 µmhos/cm to 7,400 µmhos/cm with a median value of 6,190 µmhos/cm. Median chloride concentration is 1,988 mg/l and the median boron concentration is 14 mg/l. The produced water concentrations have generally been lower in samples collected after 2000.

2.4.2 Flows from Valley Water Facilities from 1960 - 2014

Valley Water's records of produced water flows to Race Track Hill start in 1960 and continue to present. Annual produced water volume records for 1960 through 2014 are shown in Table 7. (As requested in the draft Cease and Desist Order (CDO) monthly flows for the period 1 January 2010 through 31 December 2014 are included in Appendix E). The total volume from 1960 to 2014 was approximately 198,730,000 barrels (8,350 MG; 25,600 Ac-ft). Average annual volume based on this dataset is approximately 3,613,000 barrels per year (152 MGY; 466 Ac-ft/vr).

In 1960, the Race Track Hill Facility consisted of 17 evaporation/percolation ponds and approximately 30 acres of sprinkler irrigation area. The pond surface area at that time was 14.8 acres. The margins of all ponds below the initial ponds were planted with cuttings of Salt Cedar (Tamarisk) in 1960 to enhance water loss by evapotranspiration and salt uptake. At the same time, the irrigation areas were seeded with salt tolerant grasses.

Records for 1976 show that the evaporation/percolation pond system was expanded to 27 ponds with approximately 19.8 acres of evaporative surface area and the irrigation area covered 66 acres. Records indicate that the Salt Cedar canopy had grown to an average height of 40 feet by 1976. In 1978, an additional 25 acres of irrigated area were added to reach the current 91 acres. The 91 acre area is divided into four main irrigation zones with a number of irrigation laterals to allow control of the distribution of irrigation. Much of the irrigation occurs in an area along the southeast portion of Race Track Hill along Breckenridge Road (Figure 3), but irrigated

areas also cover slopes adjacent to the evaporation/percolation ponds along the central and northern swales at the site.

2.4.3 Precipitation and Evapotranspiration at Race Track Hill

Precipitation information for the Race Track Hill Facility was obtained from the WRCC Bakersfield WSO (Station 040442) using records from 1938 to 2014 (WRCC, 2015). Evaporation and evapotranspiration information was taken from the CIMIS weather station at Arvin-Edison Station 125 (CIMIS, 2015). Average monthly values for precipitation and potential evaporation are shown in Table 8, with precipitation just 10% of total evapotranspiration levels (6.1 inches of precipitation versus 61.1 inches of evapotranspiration).

Calculations of pond evaporation and evapotranspiration from vegetation were made using average annual values for the period of 1960 to 2014. Crop coefficients for both bare soil and sparse crops with a winter-spring growing season were used. Figure 9 shows the produced water discharge and evaporative losses from the ponds and irrigated areas.

During the initial years, flows to Race Track Hill were the highest recorded and evaporative losses were low because the irrigated area was much smaller and the Salt Cedar canopy had not yet grown to maturity. Thus, more produced water was percolating. Flows to the facility decreased over the years according to oil production trends and availability of other disposal alternatives, but the flows stabilized in the early 1990s. The evaporative loss for the ponds and irrigation areas also stabilized in approximately 1980 when the irrigation area expanded to 91 acres and crops were well established. Figure 9 shows that there has been a good balance between flows to the facility and evaporative losses since the early 1990s. During most years, evaporative losses almost equal the produced water flow.

The 54 year record of flows and evaporative loss information was used to estimate the amount of produced water that percolated to the subsurface at Race Track Hill. To account for varying crop conditions in the irrigated area, bare soil and sparse grass canopy conditions were both considered. These calculations are summarized in the table below:

		Sparse
	Bare Soil	Canopy
Total Water Volume Pumped to Race Track Hill ^(a) , MG:		8,350
Pond and Irrigation Evapotranspiration ^(b) ,% of Produced		
Water Volume:	45%	49%
Total Evaporative Water Loss, MG:	3,760	4,120
Net Produced Water Percolation at Race Track Hill, MG:	4,600	4,200
Ac-ft:	14,100	12,900
Porosity:	30%	30%
Volume of Deposits Required to Store Water, Ac-ft:	47,000	43,000

Notes:

These estimates indicate that between approximately 12,900 and 14,100 Ac-ft of produced water may have percolated to the subsurface at Race Track Hill over 54 years. The total sediment volume required to store this water in the pore space is also estimated based on an assumed porosity for the soils and sediments beneath the site, 0.3. As an example of the

⁽a) Source: Valley Water Records 1960-2014.

⁽b) Based on water balance calculations.

Kennedy/Jenks Consultants

potential area this storage volume could occupy, the area beneath Race Track Hill that could store groundwater is estimated to be between 150 and 200 acres. The approximate thickness of sediments required to store the produced water volumes calculated above would range from 190 feet beneath the 200 acre area to 290 feet beneath the 150 acre area.

Section 3: Analysis and Summary of Investigation Results

In this section, the water level and water quality data for Phase 1 and 2 subsurface investigations are combined so that overall evaluations can be made of the following:

- Evaluation of groundwater quality for shallow monitoring wells, deep monitoring wells, and off-site wells
- Groundwater flow direction and mounding at Race Track Hill
- The volume of water in the subsurface at Race Track Hill
- Potential influences on groundwater

3.1 Water Quality and Isotopic Evidence of Potential Impacts

Figure 10 shows summary results of recent groundwater monitoring for wells at the Fee 34 Facility, Race Track Hill Facility, and off-site wells in the vicinity of Race Track Hill. Individual graphs for boron, chloride, sulfate and EC show the general trends of the dataset for 13 wells. The data are also presented in Table 3.

Samples collected from off-site wells (26B, 16H, 24J, and 12F) all have low levels of EC, boron, and chloride. Samples from well C-1D (at the Fee 34 Facility within the Edison Oil Field Producing area) and RTH-5 (in the Cottonwood Creek floodplain east of Race Track Hill) also have low levels of these constituents. None of these wells appear to have been affected by produced water.

The water sample for monitoring well RTH-3 also has low concentrations of boron and chloride, but the sulfate concentration and EC are higher than the unaffected wells. This groundwater quality appears to not be due to seepage of produced water, but may be related to irrigation practices.

Figure 11 is a trilinear diagram for water from the monitoring wells and off-site wells included in Table 3. In this diagram, concentrations are expressed as milliequivalents per liter, rather than milligrams per liter. The anion part of the diagram is used for much of the interpretation because the anion concentrations (chloride, sulfate, and bicarbonate) are less affected by exchange processes that are known to affect cations. Based on the distribution of water sample chemistry shown in Figure 11, several different water types can be observed on the anion trilinear plot in the lower left corner as well as the quadrilateral section of the figure. The following types of water were observed:

- Type 1. Greater than 80 percent chloride equivalents are present in RTH-1, 4, 6, and 8D. The produced water also falls into this water type. The monitoring wells with this type of water are near evaporation/percolation ponds (see Figure 3). These well samples also have high boron concentrations (Table 3).
- Type 2. Sulfate percentage of approximately 80 (RTH-3). RTH-3 taps shallow groundwater along the drainage on the east side of Race Track Hill. The RTH-3 water chemistry is

unique in comparison to all other shallow wells because it has low bicarbonate and low chloride percentages. In addition, this sample has lower boron, EC, TDS, and sodium than the wells in Type 1 above. The high sulfate and low chloride concentrations of the RTH-3 sample make this water chemistry different from the wells with high chloride concentrations (Type 1).

- Type 3. Chloride percentages ranging from about 50 to 60 with low bicarbonate and significant sulfate (RTH-7D and 9D). These deep groundwater monitoring wells are located along the western part of the facility. Water from these wells appears to be a mixture of the Type 2 high sulfate percentage groundwater and Type 1 high chloride percentage groundwater or produced water. These wells also have lower boron concentrations than the wells in Type 1 above.
- Type 4. Wells with bicarbonate greater than 30 percent. This group consists of C-1D, RTH-5, and the four off-site wells. These wells all have low TDS and boron concentrations, but fall into separate sub-categories:
 - Chloride percentage less than 20 and sulfate percentage less than 40 (RTH-5, 24J, 12F). These three wells tap the shallow groundwater along Cottonwood Creek and none of these samples has been influenced by produced water. Off-site well 24J is located upstream of Breckenridge Road along Cottonwood Creek and off-site well 12F is downstream of Breckenridge Road. These wells have a composition that is natural in origin.
 - The sample for well 26B appears to be a mixture of high sulfate groundwater and the high bicarbonate groundwater described just above.
 - Samples for monitoring well C-1D and well 16H are similar in having less than 20 percent sulfate and 40 to 50 percent chloride. These samples differ from the Cottonwood Creek well samples due to higher chloride percentage, and differ from the Race Track Hill wells due to higher bicarbonate and lower TDS.

Figure 12 shows a comparison of the stable isotope ratios of hydrogen and oxygen for the monitoring wells installed in the Phase 1 and Phase 2 investigations. Stable isotopes of water samples indicate that the isotopically heaviest water (which plots to the right along the x axis) was found in samples collected from RTH-7D and RTH-8D. The isotopically lightest water samples on the left side of the figure came from C-1D and RTH-5, wells, which are clearly not affected by produced water. The remaining wells, all on Race Track Hill, have lower oxygen isotope values. The three pairs of shallow and deep wells each have heavier water in the shallow well. This effect could be related to effects of pond evaporation and evapotranspiration in the irrigated areas, which act to concentrate the percolating water.

3.2 Fee 34 Facility

The Phase 1 and Phase 2 subsurface investigations included collection of soil boring samples in the unsaturated zone; installation, logging, and sampling of a groundwater monitoring well; and leak testing of two of the lined ponds used for treatment of produced water.

Soil Boring Investigations. The results of soil boring investigations are summarized below:

- As part of Phase 1 investigations, a soil boring was advanced to 200 feet bgs at a location 10 feet from the unlined skimmed oil ponds and within 30 feet of the produced water treatment ponds (Figure 2). Samples were collected and analyzed for water content, EC, boron, chloride, and TPHc. The boring log documented varying layers of well graded sand and silty sand. No perched water was encountered during advancement of the boring and none of the measured results for water content gave any indication of accumulations of percolating water or groundwater.
- TPHc concentrations were not detected at any depth below 5 feet bgs. The TPHc concentration at 5 feet was 220 mg/kg, well below the shallow soil environmental screening level of 500 mg/kg (San Francisco Bay Regional Water Quality Control Board, 2013).
- No elevated EC levels or elevated concentrations of boron or chloride were observed in the soil boring samples (Figure 4).
- The findings summarized above are consistent with and confirm the results of soil borings taken beneath the Fee 34 Facility in 1996 (Kennedy/Jenks, 1996). Three 80-foot slant borings were advanced beneath the ponds; the depth below ground surface reached 70 feet. Samples were collected and analyzed for boron, chloride, EC and TPHc. The results did not identify movement of produced water or evidence of constituents in the unsaturated zone.

Monitor Well Installation and Sampling. A groundwater monitoring well was installed and sampled in early 2015. The drilled depth was 460 feet bgs and the perforated interval was 395 to 435 feet bgs (Table 4). At the time of sampling, the water level was 298.4 feet bgs (Table 5) indicating that the groundwater tapped by the well is confined. Water chemistry of the sample collected on 11 March 2015 is reported in Table 3 and discussed in Section 3.1 above. The low levels of boron, chloride, and EC indicate no effects of percolation of produced water from the Fee 34 Facility.

Leak Testing of Two Fee 34 Produced Water Treatment Ponds. An initial round of leak testing of the gunite-lined ponds was conducted in Spring 2014 (see Section 2.1.1). The results indicated that the likely range of pond seepage for the South Pond was 0.3 to 3.3 mm/day. The likely range in seepage for the North Pond was 3.3 to 5.5 mm/day. The test results incorporated significant measurement uncertainty because: a) the tests were conducted during a period of high evaporation when measurement errors are proportionately larger for the four sensors used in the measurement; b) there was a rainfall event during one of the tests that introduced another uncertainty associated with the measurement of precipitation; and c) the sensors used to measure pond water level are operating at the limits of their resolution. It should also be noted that the results of unsaturated zone testing and sampling of monitoring well C-1D indicate that seepage has not been significant.

Summary. No evidence of produced water impacts to the unsaturated zone or groundwater were documented in Phase 1 and Phase 2 results. An important finding was the water quality analysis of groundwater from monitoring well C-1D that taps first encountered groundwater beneath the Fee 34 Facility. Water quality of the sample collected from this well indicates that groundwater beneath the Facility does not have elevated concentrations that would indicate the presence of produced water. Thus, operation of the Fee 34 Facility does not represent an imminent threat to local groundwater.

3.3 Race Track Hill

Phase 1 and Phase 2 investigations for the Race Track Hill Facility have been completed. The resulting dataset provides valuable information to characterize groundwater flow and water quality at this site. In addition, several other evaluations have been performed: water quality sampling for off-site wells in the vicinity of Race Track Hill, preparation of a water balance for the produced water flows at this site, and an evaluation of the potential for runoff from the ponds and irrigated areas offsite to Cottonwood Creek, the nearest surface water.

3.3.1 Groundwater Conditions

Groundwater Flow. Figure 7 shows the groundwater flow direction for the deep groundwater. The deep groundwater flow direction in March 2015 was approximately north-northwest at a gradient of 130 feet/mile. Based on the three water level measurements shown on Figure 7, mounding does not occur in the deep aquifer beneath Race Track Hill. Well RTH-7D, the southernmost deep well, had the highest water level elevation and water levels for wells RTH-8D and RTH-9D were at least 50 feet lower in elevation.

Figure 6 shows the groundwater flow direction for the shallow groundwater. The flow direction of shallow groundwater in late December 2014 was to the northeast at approximately 50 feet/mile. This flow path and gradient were calculated using the three wells to the east of Race Track Hill. The ground surface for the two wells on Race Track Hill, RTH-1 and RTH-6, are approximately 150 feet higher in elevation than wells RTH-3 and RTH-4 and water levels at RTH-1 and RTH-6 are over 100 feet higher than those at RTH-3 and RTH-4. RTH-1 and RTH-6 are also directly adjacent to active evaporation/percolation ponds. The water levels indicate that a groundwater mound is present in the shallow groundwater but there is not currently enough data to fully characterize the extent.

Water Quality. A detailed discussion of groundwater quality is provided in Section 3.1 above. Results indicate that the wells along Cottonwood Creek (24J, RTH-5, 12F) do not show impacts or any imminent threat from produced water. Some effect of produced water on groundwater quality has occurred on-site at wells RTH-1, RTH-4, RTH-6, and RTH-8D. These wells are all near evaporation/percolation ponds. The effects on these shallow monitoring wells appear to be associated with the percolation ponds and not due to effects of irrigation practices. Well RTH-3 is the closest well to the irrigation area in the southeast part of Race Track Hill and water quality at this location is different from that of wells RTH-1, RTH-4, RTH-6, and RTH-8D. Wells RTH-7D and RTH-9D are apparently a blend of high chloride produced water and high sulfate groundwater. These waters are indicated to be a mixture of produced water and native groundwater. Boron concentrations are low in each of these wells. The sulfate concentrations in these wells are higher than the levels found in the Cottonwood Creek wells.

3.3.2 Water Balance for Discharges at Race Track Hill

A water balance of produced water flows and site evaporative losses was presented in Section 2.4. Figure 9 shows the 1960 to 2014 annual produced water flows to Race Track Hill and the amount of water lost to pond evaporation and evapotranspiration from the irrigated areas. Of the total 8,350 MG volume of produced water from 1960 through 2014, between 45 and 49 percent was lost to evaporative processes. Evapotranspiration from the irrigated areas comprises 58 to 62 percent of the total water losses.

The difference between produced water flows and evaporative losses is 4,200 to 4,600 MG (12,900 to 14,100 Ac-ft). This volume is assumed to have entered the subsurface at Race Track Hill over a 54 year time period. Using an estimated average porosity of the sediments at the site, the volume of sediments required to hold this water is between 43,000 and 47,000 Ac-ft. This volume can be visualized as an area of 150 acres and thickness of 290 feet or an area of 200 acres with a thickness of 190 feet.

Flows at Race Track Hill between 1960 and 1968. The water balance for Race Track Hill shows that the annual flows to Race Track Hill were largest during the 1960s (Table 7, Figure 9). During the period from 1960 through 1968 before California's Antidegradation Policy was adopted (SWRCB, 1968), the total produced water flow is estimated to be 6,175 Ac-ft and water losses by evaporation and evapotranspiration totaled 1,175 Ac-ft. The evaporative losses were lower during this time period because, in 1960, the irrigation area was only 30 acres and the Salt Cedar and grasses had not yet reached maturity. The difference between produced water flow and evaporative loss, 5,000 Ac-ft, was applied to the initial, smaller pond surface area and irrigated acreage. As a result, the hydraulic loading was higher than in later years. During this period, produced water would have moved through the unsaturated zone towards the shallow groundwater beneath Race Track Hill. The seepage for large flows applied to smaller land areas was likely greater than the seepage in later years when the produced water flows were lower and were only slightly greater than pond evaporation and evapotranspiration from the irrigation areas. Between 1960 and 1968, four produced water samples were collected and analyzed for water quality constituents (Table 6). The average salinity values from these samples were 6,950 μmhos/cm EC, 2,220 mg/l Chloride, and 12 mg/l Boron. Although there are no groundwater samples available for this time period, it can be presumed from later sampling that the shallow groundwater would reflect similar values.

Potential for Runoff from the Race Track Hill Facility. Management of the ponds and irrigated areas at Race Track Hill has been developed to maximize evaporative losses, maintain pond freeboard, and minimize runoff and erosion in the irrigated areas. As part of a review of Facility management practices and in order to rebut allegations in the CDO that the Facility presents an imminent threat to Cottonwood Creek and the downstream Kern River, an evaluation of the potential for runoff and erosion was initiated during Spring 2015:

- Aerial photographs taken between September 1992 and March 2015 were reviewed to identify any signs of surface water flow in the roadside drainage along Breckenridge Road. Figure 13 shows fourteen aerial photographs of Race Track Hill and Breckenridge Road to the east. Figure 14 shows fourteen aerial photographs of the location where Breckenridge Road reaches Cottonwood Creek just east of Race Track Hill (see Figure 8). Each aerial photograph was evaluated using higher resolution images than those in the Figures. This evaluation helped to distinguish shadows from changes in vegetation.
 - Figure 13 shows the vegetation growth at Race Track Hill and no signs of vegetation growth caused by water in the draw between Breckenridge Road on the east and the adjacent irrigated area on Race Track Hill (Breckenridge Road is elevated above the swale in this area). There are ditches along the base of the irrigated area that collect infrequent flows, primarily from rainfall events, and route any flow to collection sumps. Water in these sumps is pumped back to the upper ponds to maintain adequate freeboard in the collection sumps. The Race Track Hill photographs do not show signs of

- ongoing erosion in the irrigated areas and the irrigated areas do not appear to have changed substantially since 2002.
- The photographs of Cottonwood Creek (Figure 14) show that there is riparian vegetation along the creek bed. In contrast, there is very little vegetation along the swale adjacent to Breckenridge Road and downgradient from Race Track Hill (the dark areas shown in the figure were confirmed to be shadows when higher resolution images were evaluated). Flows along Cottonwood Creek have been documented, but flows from the west (near Race Track Hill) have not been recorded and are not evident in the photographs.
 - The largest 30-day precipitation (5.98 inches) and largest 7-day precipitation (4.58 inches) recorded at the Bakersfield WSO station occurred in December 2010 (see Section 1.1.3). In the April 2011 photograph, vegetation is lush along Cottonwood Creek, but there is no observable difference in vegetation in the drainage along Breckenridge Road.
- Valley Water has initiated a survey of Race Track Hill to assess the adequacy of on-site storage for produced water and the occasional precipitation events (Appendix F; C. Zimmerman, personal communication, 2015). The field survey crew has observed the existing water management features including evaporation/percolation ponds, drainage ditches, catchment basins, swales, and detention basins that can provide temporary retention of precipitation. They report no evidence of erosion or sediment rills that would indicate either sheet flow or channelized run-off of on-site water.
- Dee Jaspar and Associates made a preliminary evaluation of runoff conditions at Race Track Hill. The preliminary report is included as Appendix F. The evaluation makes use of methods outlined in the Kern County Hydrology Manual, tools available on the County website, and a 100 year return period 24-hour precipitation of 3.00 inches along with other maximum precipitation conditions discussed above. A number of the drainage basins on Race Track Hill have pond capacity to maintain runoff from the design storm. Basins with less pond storage capacity are served by a network of drainage ditches, and catchment basins that are used to retain water to be pumped up slope to other ponds on Race Track Hill. Facility operators state that, during large storm events, a booster pump and movable above-ground pipelines are used to intercept water flowing on the west side of Breckenridge Road and pump the water upslope to ponds with available capacity. The runoff infrastructure and operational management practices, including adjusting freeboard levels prior to the wet season or storm events, appear to be adequate to prevent run-off from the Race Track Hill Facility even during the largest precipitation events discussed above.

References

- California Irrigation Management Information System (CIMIS). 2015. Average Monthly Reference Evapotranspiration. Accessed via the internet (http://www.cimis.water.ca.gov/cimis/) on 5 June 2015.
- Central Valley Regional Water Quality Control Board (CVRWQCB). 1958. Waste Discharge Requirements, Race Track Hill Area, Edison Oil Field, Kern County. Resolution No. 58-349. 18 September 1958.
- Central Valley Regional Water Quality Control Board. 1991. CWRQCB Request for a Technical Report/Report of Waste Discharge for Oilfield Produced Water Facilities in the Edison Area of Kern County. 8 April 1991.
- Central Valley Regional Water Quality Control Board. 1992. Order No. 92-11037. *Notice for Applicability for Valley Waste Disposal Company, Fee 34 Facility, Edison Oil Field, Kern County*. 29 May 1992.
- Central Valley Regional Water Quality Control Board. 2013a. Letter from CVRWQB to Valley Water. 23 July 2013.
- Central Valley Regional Water Quality Control Board. 2013b. *Notice of Violation for Race Track Hill Facility*. 9 October 2013.
- Central Valley Regional Water Quality Control Board. 2013c. *Notice of Violation for Fee 34 Facility*. 23 October 2013.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2014a). *Draft Cleanup and Abatement Orders (CAOs) for Edison Oilfield Facilities*. 5 February 2014.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2014b). California Water Code Directive Pursuant to Section 13267 Valley Water Management Company. Fee 34 Facility and Race Track Hill Area, Edison Oil Field, Kern County. 1 July 2014.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2015a). Water Code 13267 Order for Fee 34 and Race Track Hill Facilities. 1 April 2015.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2015b). *Notice of Violation.* Report Review, Phase 2 Subsurface Investigation, Valley Water Management Company, Race Track Hill, Edison Oil Field, Kern County. 1 May 2015.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2015c). Tentative Cease and Desist Order for Valley Water Management Company, Race Track Hill Facility and Fee 34 Facility, Edison, Kern County. 18 May 2015.

- Craig, H. 1961. Standard for Reporting Concentrations of Deuterium and Oxygen-18 in Natural Waters. Science, 133, p. 1833-1834.
- Downey Brand LLP, 2015. Valley Water Management Company's Submission of Evidence and Policy Statements and Designation of Witnesses. 30 June 2015.
- Ham, J.M. 2002. Uncertainty Analysis of the Water Balance Technique for measuring Seepage from Animal Waste Lagoons. J. Environ. Qual. 31:1370-1379.
- Ham, J.M. and K.A. Baum. 2009. Measuring Seepage from Waste Lagoons and Earthen Basins with an Overnight Water Balance Test. Trans. ASABE: 52(3):835-844).
- Luhdorff and Scalmanini. 2012. Technical Field Guide: Measuring Dairy Lagoon Seepage Using the Water Balance Method. Prepared for Western United Dairymen in cooperation with USDA-NRCS).
- Kendall, C., Coplen, T.B. 2001. Distribution of Oxygen-18 and Deuterium in River Waters Across the United States. Hydrological Processes, 15, p. 1363-1393.
- Kennedy/Jenks Consultants. 1996. Drilling and Data Acquisition Report, Race Track Hill District, Edison Oil Field, Kern County, California. Report submitted by Valley Waste Management Company to the CVRWQCB, 22 May 1996.
- Kennedy/Jenks Consultants. 2014a. Phase 1 Work Plan for Subsurface Investigations. Submitted to CVRWQCB, Fresno, CA. 13 March 2014.
- Kennedy/Jenks Consultants. 2014b. Phase 1 Subsurface Investigation Report for the Fee 34 Facility and Race Track Hill Area. Submitted to CVRWQCB, Fresno, CA. 1 August 2014.
- Kennedy/Jenks Consultants. 2014c. Phase 2 Investigation Work Plan. Submitted to CVRWQCB, Fresno, CA. 10 November 2014.
- Kennedy/Jenks Consultants. 2015a. Interim Report on Phase 2 Subsurface Investigations. Submitted to CVRWQCB, Fresno, CA. 15 January 2015.
- Kennedy/Jenks Consultants. 2015b. Phase 2 Subsurface Investigation Final Report. 30 June 2015.
- Kenneth D. Schmidt and Associates (KDSA). 2014. Workplan for Deep Monitor Wells at Valley Water Management Company Race Track Hill and Plant-C Facilities in Kern County. October 2014.
- Kenneth D. Schmidt and Associates (KDSA). 2015. Report on Installation of Deep Monitor Wells at Valley Water Management Company Race Track Hill and Plant-C Facilities in Kern County. June 2015.

- San Francisco Bay Regional Water Quality Control Board (2013). ESL Environmental Screening Level Workbook. Accessed via the internet http://www.waterboards.ca.gov/sanfranciscobay/water_issues/programs/esl.shtml. December 2013.
- State Water Resources Control Board (SWRCB). 1968. Statement of Policy with Respect to Maintaining High Quality of Waters in California. Resolution 68-16. 28 October 1968. Sacramento, CA.
- Valley Water Management Company. 2013. Letter From Valley Water to CVRWQCB. 8 November 2013.
- Valley Water Management Company. 2015. Valley Water Submission of Technical Information Requested in 1 April 2015 13267 Order. 15 June 2015.
- Western Regional Climate Center. 2015. Long Term Precipitation Records. Accessed via the internet (http://wrcc.dri.edu/) on 5 June 2015.
- Zouhar, K. 2003. Tamarix spp. In: Fire Effects Information System, [Online]. U.S. Department of Agriculture, Forest Service, Rocky Mountain Research Station, Fire Sciences Laboratory (Producer). Available: http://www.fs.fed.us/database/feis/ [2015, June 19].

Tables

Table 1: Shallow Monitoring Well Construction Data

					Well Screen		Sand Pack		Bentonite Seal		Grout Seal	
Well ID	Completion Date	Well Diameter (inches)	Top of Casing Elevation (ft AMSL) ^(a)	Drilled Depth (ft bgs) ^(b)	Top (ft bgs)	Bottom (ft bgs)						
Shallow Moni	toring Wells											
RTH-1	04/11/2014	4	1,025.85	70.5	50	70	48	70.5	45	48	1.5	45.0
RTH-3	04/22/2014	4	879.39	105.1	84.6	104.6	82	105.1	76.2	82	1	76.2
RTH-4	04/17/2014	4	871.02	150	80	100	78	104	72	78	5	72
RTH-5	12/11/2014	4	810.80	57.4	27	57	24.5	57.4	22.5	24.5	3	22.5
RTH-6	12/10/2014	4	1,059.82	145.0	113.5	143.5	111	145.0	107.8	111.0	1	107.8

Notes:

⁽a) "ft AMSL" denotes feet above mean sea level, NAVD88. RTH-1 through RTH-4 surveyed in June 2014 and RTH-5 and RTH-6 surveyed in December 2014 by Dee Jaspar and Associates.

⁽b) "ft bgs" denotes feet below ground surface.

Table 2: Shallow Groundwater Level Data

Monitoring Well	Measuring Point ^(a) Elevation (ft AMSL) ^(b)	Date	Depth to Groundwater (ft TOC) ^(c)	Groundwater Elevation (ft AMSL)
RTH-1	1025.85	4/30/2014	47.91	977.94
RTH-1	1025.85	12/22/2014	48.15	977.70
RTH-3	879.39	4/29/2014	80.83	798.56
RTH-3	879.39	12/22/2014	87.31	792.08
RTH-4	871.02	4/29/2014	78.45	792.57
RTH-4	871.02	12/22/2014	84.41	786.61
RTH-5	810.80	12/21/2014	33.45	777.35
RTH-6	1059.82	12/22/2014	120.31	939.51

Notes:

⁽a) Top of PVC Well Casing

⁽b) ft AMSL = feet above mean sea level, to NAVD88 datum. RTH-1 through RTH-4 surveyed in June 2014 and RTH-5 and RTH-6 were surveyed in December 2014 by Dee Jaspar & Associates.

⁽c) ft TOC = feet below top of casing

Table 3: Groundwater Quality Data for Monitoring Wells and Off-Site Wells

Race Track Hill Shallow Wells RTH-1 4/30/2014 8,690 6,600 2,900 16 560 44 RTH-1 12/22/2014 8,650 7,000 2,900 16 550 45	1,100 1,300	8.9		μg/l ^(f)	μg/l										
	,	8.9													
RTH-1 12/22/2014 8,650 7,000 2,900 16 550 45	1,300	0.0	42	1,300	<200										
		9.0	42	<500 ^(g)	-										
RTH-3 4/29/2014 2,810 1,900 510 4.1 200 93	280	25	680	<500	<200										
RTH-3 12/23/2014 1,920 1,500 130 0.65 170 81	180	22	800	<500	-										
RTH-4 4/29/2014 5,900 4,400 1,700 6.9 450 170	580	22	510	<500	240										
RTH-4 12/22/2014 6,540 5,100 2,000 5.4 490 180	680	23	370	<500	-										
RTH-5 12/21/2014 624 450 26 0.066 64 23	51	6.4	92	<500	-										
RTH-6 12/23/2014 4,680 3,500 1,300 3.0 400 48	570	22	290	<500	-										
Deep Wells (Race Track Hill and Fee 34)															
RTH-7D 3/11/2015 5,420 3,900 1,250 0.5 535 104	411	35	910	-	<50										
RTH-8D 3/11/2015 6,490 4,180 2,060 9.1 514 161	376	14	23	-	280										
RTH-9D 3/11/2015 4,000 2,960 820 0.2 464 26	321	17	860	-	<50										
C-1D 3/11/2015 1,400 800 229 0.2 101 18	130	4	110	-	<50										
Offsite Wells															
16H 4/11/2015 570 390 75 0.2 25 1	99	2	18	-	<50										
26B 4/20/2015 750 503 35 0.1 29 <1	114	4	191	-	100										
24J 4/21/2015 667 526 20 < 0.10 71 24	35	5	95	-	<50										
12F 6/9/2015 977 680 42 0.13 120 33	68	9.2	200	<500	-										

Table 3: Groundwater Quality Data for Monitoring Wells and Off-Site Wells

Monitoring Well	Sample Date	pH pH Units	Arsenic μg/l	Bicarbonate (HCO ₃) ⁽ⁱ⁾ mg/L	Carbonate (CO ₃) ^(j) mg/L	Total Organic Carbon mg/L	Nitrate as N mg/L	Nitrate mg/L	lron mg/L	Mn ^(k) mg/L	Zinc mg/L
Race Track Hi			н ул	mg/L	mg/L	mg/L	IIIg/L	mg/L	mg/L	mg/L	mg/L
RTH-1	4/30/2014	7.31		293	< 4.9	_	7.1	_	_	_	_
RTH-1	12/22/2014	7.26		268	< 4.9	_	14	-	-	-	_
	12,22,2011	7.20		200	1.0						
RTH-3	4/29/2014	6.86	_	146	< 4.9	-	0.7	-	-	-	-
RTH-3	12/23/2014	6.91	-	122	< 4.9	-	0.16	-	-	-	-
RTH-4	4/29/2014	7.52	-	256	< 4.9	-	8.3	-	-	-	-
RTH-4	12/22/2014	7.38	-	256	< 4.9	-	3.4	-	-	-	-
RTH-5	12/21/2014	7.69	-	268	< 2.5	-	0.57	-	-	-	-
RTH-6	12/23/2014	7.34	-	232	< 4.9	-	23	-	-	-	-
Deep Wells (R											
RTH-7D	3/11/2015	6.6	-	320	< 10	0.5	-	0.4	0.54	1.13	-
RTH-8D	3/11/2015	6.6	-	310	< 10	8.0	=	2.7	<0.05	0.11	-
RTH-9D	0/44/0045	7.0		040	40	0.5		4.0	0.05	0.70	
KIN-9D	3/11/2015	7.0	-	210	< 10	0.5	-	1.0	<0.05	0.79	-
C-1D	3/11/2015	7.2		280	< 10	0.9		<0.5	<0.05	0.88	_
Offsite Wells	0/11/2010	7.2		200	V 10	0.0		٧٥.٥	٧٥.٥٥	0.00	
16H	4/11/2015	7.5	4	170	< 10	0.8	<0.1	<0.5	0.19	0.29	0.09
1011	1/11/2010	7.0	•		110	0.0	10.1	10.0	0.10	0.20	0.00
26B	4/20/2015	7.7	_	130	< 10	<0.7	<0.1	<0.5	<0.030	0.02	<0.020
	= 5, = 5 . 0										
24J	4/21/2015	7.4	-	260	< 10	<0.7	3.5	15.6	<0.030	<0.010	<0.020
12F	6/9/2015	7.47	8.7	354	< 2.5	-	0.51	-	-	-	-

Table 3: Groundwater Quality Data for Monitoring Wells and Off-Site Wells

Notes:

- (a) EC = Electrical Conductivity
- (b) µmhos/cm = micromhos per centimeter
- (c) TDS = Total Dissolved Solids
- (d) mg/l = milligrams per liter
- (e) TPH = Total Petroleum Hydrocarbons
- (f) μ g/l = micrograms per liter
- (g) "<500"= not detected above the practical quantitation limit
- (h) Ca, Mg, Na, K, As, B samples are "Total Recoverable"
- (i) Bicarbonate data for the shallow well and Well 12F were converted from Bicarbonate as CaCO3 to Bicarbonate (HCO3).
- (j) Carbonate data for the shallow well and Well 12F were converted from Carbonate as CaCO3 to Carbonate (CO3).
- (k) Mn = Manganese

Table 4: Deep Monitoring Well Construction Data

Well ID	Date Completed	Drilled Depth (ft) ^(a)	Cased Depth (ft)	Perforated Interval (ft)	Gravel Pack (ft)	Annular Seal (ft)
RTH-7D	2/11/2015	360 ^(b)	330	282-330	223-340	0-223
RTH-8D	1/28/2015	260	210	191-210	168-210	0-168
RTH-9D	2/17/2015	360	350	312-350	289-360	0-289
C-1D	2/24/2015	460	435	395-435	381-455	0-381

Source: Kenneth D. Schmidt & Associates, Deep Well Report, June 2015.

Monitor Wells were constructed by Bradley & Sons of Del Rey and have 5-inch diameter PVC casings.

Schedule 40 was used for the first three wells, and Schedule 80 for C-1D.

- (a) ft= feet
- (b) Depth from surface

Table 5: Water Level Data For Deep Monitoring Wells - March 17, 2015

Well ID	Measuring Point Elevation (ft)	Depth to Water (ft) ^(a)	Water-Level Elevation (ft)
RTH-7D	1061.8	207.5 ^(b)	854.3
RTH-8D	874.7	86.9	787.8
RTH-9D	1025.2	225.3	799.9
C-1D	635.5	298.4	337.1

Source: Kenneth D. Schmidt & Associates, Deep Well Report, June 2015. Water levels were measured by KDSA. Measuring point elevations were surveyed

by Dee Jasper and Associates, Inc., of Bakersfield on March 20, 2015.

- (a) ft = feet
- (b) Measured from surface

Table 6: Produced Water Quality, 1961 - 2015

Sample Date	Electrical Conductivity μmhos/cm ^(a)	Chloride mg/l ^(b)	Boron mg/l	TDS ^(c) mg/l	Calcium mg/l	Mg ^(d) mg/l	Na ^(e) mg/l	K ^(f) mg/l	Sulfate mg/l	Nitrate(NO₃) mg/l	pН	TPH - Diesel ^(g) μg/l ^(h)	Lab Sheet Number (Appendix D)
1/20/1960	6,550	1,975	17.1	3,700	-	-	1200	-	-	-	-	-	1
1/3/1961 ⁽ⁱ⁾	4,906	1,631	2.0	2,826	476	73	465	20	96	-	7.7	-	2
1/18/1963	8,775	2,709	17	5,095	=	-	-	-	-	-	-	-	3
12/18/1964	7,577	2,553	11	4,399	-	-	-	-	-	-	-	-	4
10/23/1979	6,050	2,410	6	4,250	201	10	1,395	4.9	< 5.0	58	7.6	-	5
9/28/1984	5,600	1,855	20	3,399	125	8.0	1,150	-	<5.0	<0.4	7.7	-	6
4/22/1992	7,100	2,010	=	3,750	188	9.0	1,290	17	< 5.0	<0.4	7.6	-	7
5/28/1993	7,400	2,250	16	-	-	-	-	-	-	-	-	-	8
7/1/1993	6,190	1,830	14	3,570	160	8.4	1,180	14	5.3	<1.0	8.0	-	9
10/2/1995	6,870	2,000	13	3,900	170	13	1,300	16	< 5.0	<1.0	8.2	-	10
7/13/1997	6,640	2,000	15	3,800	180	11	1,300	14	6	<1.0	7.9	-	11
7/18/2013	5,700	1,800	14	-	-	-	-	-	-	-	=	-	12
10/24/2014	5,700	1,500	13	3,000	100	10	1,300	12	18	-	7.49	-	13
1/6/2015	5,600	1,700	14	3,100	100	9.6	1,600	-	< 0.50	<2.00	7.33	-	14
4/20/2015	4,630	1,370	12.6	2,830	88	11	923	17	3	<0.4	7.4	5,000	15A & 15B

- (a) µmhos/cm = micromhos per centimeter
- (b) mg/l = milligrams per liter
- (c) TDS = Total Dissolved Solids
- (d) Mg = Magnesium
- (e) Na = Sodium
- (f) K = Potassium
- (g) TPH-Diesel = Total Petroleum Hydrocarbons Diesel
- (h) $\mu g/l = micrograms per liter$
- (i) Sample was filtered
- (j) Highlighted cell means the value was calculated based on an average TDS/EC ratio of (0.58).

Table 7: Produced Water Discharge Flows: 1960 - 2014

Year ^(a)	Barrels Per Year	Milion Gallons Per Year	Average Barrels Per Day	Average Million Gallons Per Day
1958	0	0	0	0.00
1959	0	0	0	0.00
1960	6,995,600	294	19,166	0.80
1963	5,945,900	250	16,290	0.68
1964	4,836,600	203	13,251	0.56
1965	4,769,100	200	13,066	0.55
1966	4,751,900	200	13,019	0.55
1968	3,505,460	147	9,604	0.40
1969	3,078,800	129	8,435	0.35
1971	2,142,900	90	5,871	0.25
1972	2,805,800	118	7,687	0.32
1973	4,769,100	200	13,066	0.55
1981	4,825,652	203	13,221	0.56
1982	3,992,100	168	10,937	0.46
1983	4,180,100	176	11,452	0.48
1984	4,462,100	187	12,225	0.51
1985	3,801,000	160	10,414	0.44
1986	3,369,200	142	9,231	0.39
1987	2,921,000	123	8,003	0.34
1988	3,066,800	129	8,402	0.35
1989	2,126,500	89	5,826	0.24
1990	1,799,200	76	4,929	0.21
1991	1,585,000	67	4,342	0.18
1992	2,516,900	106	6,896	0.29
1993	2,818,900	118	7,723	0.32
1994	2,277,900	96	6,241	0.26
1995	2,336,330	98	6,401	0.27
1996	2,404,100	101	6,587	0.28
1997	3,409,000	143	9,340	0.39
2001	2,725,900	114	7,468	0.31
2007	2,630,000	110	7,205	0.30
2008	3,152,000	132	8,636	0.36
2009	2,618,000	110	7,173	0.30
2010	2,568,000	108	7,036	0.30
2011	2,568,000	108	7,036	0.30
2012	3,177,000	133	8,704	0.37
2013	3,839,000	161	10,518	0.44
2014	4,104,000	172	11,244	0.47

(a) Data not available for: 1961-1962, 1967, 1970, 1974-1980, 1998-2000, 2002-2006.

Table 8: Monthly Precipitation and Evapotranspiration for the Race Track Hill Area

	Average Precipitation ^(a)	Evapotranspiration(b)(c)
Month	(Inches)	(Inches)
January	1.0	1.5
February	1.1	2.3
March	1.1	4.1
April	0.7	5.6
May	0.2	7.7
June	0.1	8.7
July	0.0	9.1
August	0.0	8.5
September	0.1	6.1
October	0.3	4.1
November	0.6	2.1
December	0.9	1.4
Annual Total:	6.1	61.1

- (a) Western Regional Climate Center (WRCC) Station 040442 Bakersfield WSO (1938-2012).
- (b) Reference evapotranspiration (ET0) from the CIMIS Station Arvin/Edison (#125) 1995 2015.
- (c) Pond evaporation plus Salt Cedar water use is assumed to equal ET0.

 Bare soil evapotranspiration uses a crop coefficient of 0.35.

 Sparse canopy evapotranspiration uses a crop coefficient of 0.35 for May through November and 0.6 for the remaining months.

N

2,250

Feet

4,500

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Locations of the Valley Water Management Company Edison Oil Field Facilities


> K/J 1365027*00 June 2015



- Approximate Soil Boring Location
- Deep Monitoring Well Location (C-1D)

Notes:

1. Fee 34 Facility Located at SW1/4 Section 34 T29S R29E WDB&M



Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Fee 34 (C Plant) Produced Water Collection and Treatment Facility

K/J 1365027*00 June 2015






Deep Monitoring Well Location



Shallow Monitoring Well Location




Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Race Track Hill Produced Water Discharge Facility

K/J 1365027*00 June 2015




- 1. EC = Electrical Conductivity
- 2. µmho/cm = micromhos per centimeter

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Fee 34 Boring-1 EC, Soil Moisture, Boron and Chloride Depth Profiles

> K/J 1365027.00 June 2015



- → RTH-1 Irrigated
- ---- RTH-2 Unirrigated
- --- RTH-3
- → RTH-4

—Average

- A RTH-1 Approximate Depth to First-Encountered Groundwater
- RTH-2 Approximate Depth to First-Encountered Groundwater
- + RTH-3 Approximate Depth to First-Encountered Groundwater
- △ RTH-4 Approximate Depth to First-Encountered Groundwater

Notes:

- 1. EC = Electrical Conductivity
- 2. µmho/cm = micromhos per centimeter
- 3. RTH-1 sample depths corrected to depth below original ground surface (1025.85 ft amsl)
- 4. Samples where Boron was reported as <5 mg/kg are plotted at 5 mg/kg

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Race Track Hill Borings RTH-1 and RTH-2 EC, Boron and Chloride Depth Profiles

K/J 1365027.00 June 2015






Shallow Monitoring Well Location

Water Level Elevation (AMSL)



Groundwater Elevation Contour




Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Shallow Groundwater Level and Direction of Groundwater Flow, December 2014

K/J 1365027*00 June 2015





Deep Monitoring Well Location

Water Level Elevation (AMSL)

~

Groundwater Elevation Contour

0 300 600 Feet


Note: Groundwater Elevations Measured on 17 March 2015. Source: Kenneth D. Schmidt & Associates. Deep Well Investigation Report, June 2015.

Kennedy/Jenks Consultants


Valley Water Management Company Bakersfield, California

Deep Groundwater Level and Direction of Groundwater Flow, March 2015

K/J 1365027*00 June 2015



Produced Water Discharges and Evaporative Losses at Race Track Hill - Sparse Canopy Condition





Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Produced Water Discharges and Evaporative Losses at Race Track Hill

> K/J 1365027*00 June 2015






Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Water Quality Scatter Plots

K/J 1365027*00 June 2015




Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Trilinear Diagram for Monitoring Wells and Off-Site Wells

K/J 1365027*00 June 2015




- (a) Metoric water line: δ^2 H=8.13* δ^{18} O+10.0: Craig, H. 1961. *Isotopic variations in meteoric waters*. Science, 133, 1702-1703, <u>in</u> http://cierzo.sahra.arizona.edu/programs/isotopes/oxygen.html#5
- (b) $\delta^{18}O$ = delta Oxygen-18 ($\delta^{18}O$ = 1000*[(^{18}O / ^{16}O sample ^{18}O / ^{16}O reference) / ^{18}O / ^{16}O reference])
- (c) $\delta^2 H$ = delta Deuterium ($\delta^2 H$ = 1000*[($^2 H$ / $^1 H$ sample $^2 H$ / $^1 H$ reference) / $^2 H$ / $^1 H$ reference])
- (d) Sources: Craig, 1961 and Kendall, 2001.


Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Stable Isotope Analyses of Groundwater at the Fee 34 and Race Track Hill Facilities

> K/J 1365027*00 June 2015





Appendix A

Phase 2 Interim Report

Kennedy/Jenks Consultants

Engineers & Scientists

200 S.W. Market Street, Suite 500 Portland, Oregon 97201 503-423-4000 FAX: 503-295-4901

15 January 2015

Mr. Dane Johnson Senior Engineering Geologist Central Valley Regional Water Quality Control Board 1685 E Street Fresno, California 93706

Subject: Interim Report on Phase 2 Subsurface Investigations at the Valley Water

Management Company Edison Oil Field Fee 34 Facility and Race Track Hill

K/J 1365027*00

Dear Mr. Johnson:

This interim report on the Phase 2 Subsurface Investigations: Valley Water Management Company Edison Oil Field, Fee 34 Facility and Race Track Hill is submitted in compliance with the 13267 Order issued to Valley Water Management Company (VWMC) on 1 July 2014. A Work Plan describing the proposed investigations was submitted for Central Valley Regional Water Quality Control Board (Regional Board) approval on 14 November 2014 and reviewed with the Regional Board during a meeting on 2 October 2014. During that meeting, the Regional Board gave conceptual approval to the Phase 2 investigations plan.

Background. VWMC received the 13267 Order on 7 July 2014, and responded to the Regional Board on 29 July 2014 (Letter from Larry Bright, VWMC, to Clay Rodgers, Regional Board, dated 29 July 2014). The purpose of the letter was to once again reiterate the impossibility VWMC faces in complying with the requirement to complete all the work described in the 13267 Order by the final completion date of 15 January 2015 established in the Order.

The basis for our concerns with the schedule contained in the 13267 Order is summarized as follows. The work required to be performed by VWMC in the Order consists of three basic tasks:

- 1. Conduct investigations and studies necessary to determine whether potential adverse impacts on soil and groundwater quality have occurred.
- 2. Characterize the nature and extent of release, if any, from the subject facilities.
- Once the characterization is complete, conduct studies to evaluate what corrective measures, if any, need to be taken to protect existing and potential future uses of impacted soils and groundwater.

Step 2 cannot be undertaken until Step 1 is completed and Step 3 cannot be completed without first completing Step 2. VWMC has worked collaboratively with Regional Board staff to this point and agree that a phased approach is the best approach to conducting the evaluation for VWMC's Edison Oil Field sites, as mentioned in the 13267 Order. VWMC submitted a Work Plan for proposed Phase 2 work and contracted with a drilling company for Phase 2 well installation. Two additional shallow monitoring wells have been installed at Race Track Hill and 4 deep wells will be installed later this month (drillers in the area have been extremely busy so this was the earliest time we could contract for the drill rig specified for the deep wells). Drilling, well construction, development, sampling, and water quality analyses are expected to take 4-6 weeks to complete.

If the Phase 2 investigations do, in fact, result in defining the nature and extent of the release, if any, VWMC will then require a minimum of an additional six months to conduct the evaluation of what, if anything, need be done in response to the release. Alternatively, if the Phase 2 investigations do not adequately define the nature and extent of the release, a third phase of characterization will be required before the evaluation of need for corrective action can commence.

VWMC pursued Phase 1 investigations at Race Track Hill and the Fee 34 Facility in a voluntary manner prior to receiving a 13267 Order in order to hasten the investigations. VWMC intends to continue investigations diligently. Yet in spite of our commitment to continue in this manner, it is not possible for us to comply with the schedule set forth in the Order. The Interim report on subsurface investigations presented in this letter is intended to report our findings to date and our continued diligence in pursuing necessary investigations, in accordance with our Work Plans for drilling and the technical elements of the 13267 Order.

Technical Summary of Subsurface Investigations

Phase 2 Subsurface Investigations at the Valley Water Management Company Edison Oil Field Sites consist of two drilling and monitoring well construction programs. One investigation focuses on the deep aquifers that underlie the Fee 34 Facility and Racetrack Hill. Three wells will be completed at Racetrack Hill and one well will be completed at the Fee 34 Facility (Figure 1). This investigation has not been completed and, therefore, is not discussed in this interim report. The following paragraphs provide a summary of the second subsurface investigation which addresses shallow subsurface stratigraphy and shallow monitoring well construction at the Racetrack Hill Facility. VWMC also identified wells within one mile of the VWMC sites, as required in the 13267 Order. A report on the wells identified was submitted to the Regional Board on 21 August 2014. This report also included a cross section for the Racetrack Hill Area based on local area well logs.

The objective of the Phase 2 shallow groundwater investigation is to provide a further assessment of shallow groundwater conditions down gradient of the Racetrack Hill Site (Figure 1). Two additional shallow groundwater monitoring wells were installed, developed, and surveyed to augment the three monitoring wells installed during Phase 1. New monitoring well RTH#5 was installed northeast of the Site near Cottonwood Creek, and new monitoring well

RTH#6 was installed on the southwest side of the southernmost surface impoundment in the southern drainage (Figure 2). All five shallow monitoring wells were sampled and analyzed in December 2014 for inorganic constituents, Total Petroleum Hydrocarbons as crude oil (TPHc), and isotopic analysis of O¹⁸ and deuterium.

Results. Boring Logs for the new wells (Attachment A) indicate that RTH#5 is completed in recent alluvium. This alluvium is in a drainage way that trends west to east losing approximately 80 feet elevation between the base of Racetrack Hill and Cottonwood Creek. The boring, which extended to 57 feet below ground surface (bgs), had an initial static water level at 33 feet bgs. The hollow stem auger could not advance past 57 feet bgs so the depth of the recent alluvium overlying the Santa Margarita Formation could not be determined.

Boring RTH#6 was advanced to 144 feet bgs with an initial static water level in the borehole at 120 feet bgs. Based on our boring logs, the sediments encountered are those of the Santa Margarita Formation. No evidence of moisture related to the adjacent produced water percolation was observed in the near surface core samples; no perched water or indication of horizontal movement were observed.

Wells were constructed in borings RTH#5 and RTH#6. Table 1 summarizes well construction details for all shallow wells at Racetrack Hill. The top of casing elevation for RTH#5 is at the lowest elevation of the wells and RTH#6 is at the highest elevation.

Groundwater elevation data for both April 2014 and December 2014 monitoring well sampling events are included in Table 2. Three wells have been sampled twice. Of these, RTH#1 has approximately the same water level in April and December. This is likely due to its location adjacent to an active percolation-evaporation pond that maintains water levels in the area. The two wells at the base of Race Track Hill, RTH#3 and RTH#4, both have static water levels approximately 6 feet lower in December than in April.

Figure 3 shows water level elevations for the December 2014 sampling event. No attempt was made to provide water level contours because there are undefined variables that affect groundwater flow in the area. This includes percolation discharge volume from the 21 ponds at Racetrack Hill, a large elevation change between wells on Racetrack Hill and those in the valley east of Racetrack Hill, and marked differences in subsurface conditions among the well locations.

An important objective of the Phase 2 Work Plan was to determine the flow direction of first-encountered ground water east of Racetrack Hill. Based on December 2014 results from RTH#3, RTH#4, and RTH#5, the apparent flow direction is to the northeast along the same path as the surface drainage way just north of Breckenridge Road. This assumes that groundwater encountered at RTH#5 is hydraulically connected to the groundwater in RTH#3 and RTH#4. This is discussed in the next section.

Water Quality Monitoring Dataset. The results of April 2014 and December 2014 groundwater sampling are shown in Tables 3 and 4. For this interim report, the results of the December 2014

samples will be discussed here. Monitoring wells RTH#1 and RTH#6 are located directly adjacent to produced water percolation-evaporation ponds on Racetrack Hill. Water quality of these wells is expected to be related to the chemistry of produced water. RTH#3 and RTH#4 are at the base of Racetrack Hill and may have water quality affected by more than one water source. The same is true for RTH#5 but this well is much further from Racetrack Hill.

Electrical conductivity (EC) and boron (B) are highest at well RTH#1 and slightly lower at RTH#4 and RTH#6. These parameters are lowest at wells RTH#3 and RTH#5. RTH#5 is much lower in EC and B than all other wells, likely because it is furthest from Racetrack Hill and may not have been influenced by water from the Racetrack Hill ponds. This comparative trend among wells is consistent for a number of constituents including sodium (Na) and chloride (CI) which are characteristically high in produced water. Calcium and total dissolved solids (TDS) also follow this trend. Nitrate nitrogen, sulfate (SO₄), magnesium (Mg), potassium (K), and alkalinity (HCO₃) all have different trends for the wells completed in first encountered groundwater. SO₄, Mg, K, and HCO₃ all have concentrations equal to or greater than those at RTH#1. This suggests that there are other sources of groundwater that contribute salt ions, particularly at RTH#4.

The relationships among salt ions can be evaluated using a trilinear geochemical analysis (Figure 4). This figure shows that the wells on Racetrack Hill, RTH#1 and RTH#6, consistently plot near each other, because they are chemically similar. Wells RTH#3 and RTH#5 consistently plot at one end of the group of five wells because their geochemistry is markedly different. In addition, RTH#3 and RTH#5 are different from each other because RTH#5 has a geochemical make-up that is distinctly different from all other wells. EC, B, and Cl are much lower than the other wells and indicates that groundwater at this well location comes primarily from sources other than produced water discharge at Racetrack Hill. Well RTH#4 generally falls between the geochemistry of RTH#1/RTH#6 and RTH#3/RTH#5. This well also has higher Mg and SO_4 concentrations than are present in the produced water or at RTH#1.

The sampling plan for the December 2014 sampling event also included TPHc and isotopes of oxygen and hydrogen. TPHc was not detected in any sample above the method reporting limit, $500 \mu g/l$ (Table 4).

The preliminary analysis of wells at the Racetrack Hill site indicate that wells located on Racetrack Hill (RTH#1, RTH#6) have characteristics similar to produced water but generally at somewhat lower concentrations. The other wells have chemical differences from produced water that suggest that other groundwater sources are present at these wells. RTH#4 may have another source with elevated K, Mg, and SO₄. RTH#3 may have similar effects but the concentrations of B, CI, and EC are lower than at RTH#4. This may be due to the distance of RTH#3 from the nearest percolation-evaporation ponds. As mentioned above, RTH#5 has very different water quality than that of the other four wells at Racetrack Hill.

Isotope analyses have not yet been completed by the specialty laboratory. Since isotopic analysis is a key part of evaluating potential component sources of groundwater, any further

evaluation of sources of shallow groundwater at and near the Racetrack Hill site will be conducted when the laboratory dataset is complete in early February 2015.

Evaluation of Alternative Discharge Methods

Two discharge alternatives to the Racetrack Hill discharge are under consideration and evaluation by VWMC. We continue to evaluate potential alternatives but, at this time, these have not been demonstrated to be viable.

- 1. Produced Water Injection into an Exempt Aquifer. As a contingency to the potential future loss of the VWMC disposal facility at Racetrack Hill, VWMC has made a decision to attempt to try and permit a Class II UIC disposal well, through DOGGR, at their Section 34 "C Plant" fee property. The purpose of this UIC project is to dispose of water produced from leases in the Edison Oil Field that are a part of the VWMC Racetrack Hill water disposal district. Injection will be into the Santa Margarita formation, which is an exempted aquifer in this portion of the Edison Oil Field. The injection facility would be on VWMC's "C Plant" property located near the southwest corner of Section 34, T29S/R29E, MDBM, Kern County, California. The proposal is to drill one new well initially, "Fee 34-1", into the Santa Margarita for testing of the proposed injection zone. VWMC may propose supplemental wells in the future if produced water volumes increase and/or the formation can accept an increase in injected produced water volumes. VWMC estimates that it will take up to two years to permit and drill this proposed disposal well. VWMC has conducted background research on properties and has completed the geological portion of the permit application.
- 2. **Discharge of Produced Water to an Irrigation District.** VWMC is in discussions with the Arvin-Edison Water Storage District regarding providing them with produced water to augment their irrigation water supply. The blended concentrations are being evaluated to assess agricultural suitability and the mechanics of piping the produced water to Arvin-Edison's canal system are under review.

Please contact Gary Carlton, Larry Bright, or me if you wish to discuss any aspect of this interim report. VWMC plans to submit a final report on the Phase 2 subsurface characterization activities when the investigations have been completed. We anticipate the report will be submitted between mid-March and early April 2015.

Very truly yours,

KENNEDY/JENKS CONSULTANTS

Stat w Childs

Stuart W. Childs, PhD

Senior Scientist

Tables:

Table 1: Monitoring Well Completion Details

Table 2: Summary of Groundwater Elevation Data

Table 3: Summary of Monitoring Well Sample Data – Inorganic Analytes

Table 4: Summary of Monitoring Well Sample Data – TPH as Crude Oil Attachments:

Attachment A: RTH # 5 and RTH #6 Boring Logs

Figures:

Figure 1: Site Location Map

Figure 2: Race Track Hill Boring and Well Locations

Figure 3: Groundwater Elevations – December 2014

Figure 4: Geotechnical Analysis of Race Track Hill Groundwater Samples - December 2014

Attachment A: RTH # 5 and RTH #6 Boring Logs

cc: Clay Rodgers, CVRWQCB

Larry Bright, Valley Water Management Company Jim Waldron, Valley Water Management Company

Gary Carlton, Kennedy/Jenks Consultants

Tables

Table 1: Monitoring Well Completion Details

				<u>.</u>	Well Screen Sand Pac		Pack ^(d)	Bentonite Seal		Grout Seal		
Well ID	Completion Date	Well Diameter (inches)	Top of Casing Elevation (ft AMSL) ^(a)	Drilled Depth (ft bgs) ^(b)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)
RTH#1	04/11/2014	4	1025.85	70.5	50	70	48	70.5	45	48	1.5	45.0
RTH#3	04/22/2014	4	879.39	105.1	84.6	104.6	82	105.1	76.2	82	1	76.2
RTH#4	04/17/2014	4	871.02	150	80	100	78	104	72	78	5	72
RTH#5	12/11/2014	4	810.8	57.4	27	57	24.5	57.4	22.5	24.5	3	22.5
RTH#6	12/10/2014	4	1059.82	145.0	113.5	143.5	111	145.0	107.8	111.0	1	107.8

⁽a) "ft AMSL" denotes feet above mean sea level, NAVD88. RTH#1 through RTH#4 surveyed in June 2014 and RTH#5 and RTH#6 surveyed in December 2014 by Dee Jaspar and Associates.

⁽b) "ft bgs" denotes feet below ground surface.

Table 2: Summary of Groundwater Elevation Data

Monitoring Well	Measuring Point ^(a) Elevation (ft AMSL) ^(b)	Date	Depth to Groundwater (ft TOC) ^(c)	Groundwater Elevation (ft AMSL)
RTH #1	1025.85	4/30/2014	47.91	977.94
RTH #1	1025.85	12/22/2014	48.15	977.70
RTH #3	879.39	4/29/2014	80.83	798.56
RTH #3	879.39	12/22/2014	87.31	792.08
RTH #4	871.02	4/29/2014	78.45	792.57
RTH #4	871.02	12/22/2014	84.41	786.61
RTH#5	810.80	12/21/2014	33.45	777.35
RTH#6	1059.82	12/22/2014	120.31	939.51

⁽a) Top of PVC Well Casing

⁽b) ft AMSL = feet above mean sea level, to NAVD88 datum. RTH#1 through RTH#4 surveyed in June 2014 and RTH#5 and RTH#6 were surveyed in December 2014 by Dee Jaspar & Associates.

⁽c) ft TOC = feet below top of casing

Table 3: Summary of Monitoring Well Sample Data - Inorganic Analytes

Monitoring Well	Sample Date	Sample Name	рН	Electrical Conductivity @ 25°C	Total Dissolved Solids @ 180°C	Calcium	Magnesium	Sodium	Potassium	Boron	Bicarbonate Alkalinity as CaCO ₃	Carbonate Alkalinity as CaCO ₃	Chloride	Nitrate as N	Sulfate
			pH Units	µmhos/cm ^(a)	mg/L ^(b)	mg/L	mg/L	mg/L	mg/L	mg/l	mg/L	mg/L	mg/L	mg/L	mg/L
Produced Water	10/24/2014 I	RTH Discharge Water	7.49	5700	3000	100	10	1300	12	13	290	<10 ^(c)	1500	-	18
RTH #1	4/30/2014	RTH-1-140430	7.31	8,690	6,600	560	44	1,100	8.9	16	240	<8.2 ^(c)	2,900	7.1	42
RTH #1	12/22/2014	RTH #1 - 122214	7.26	8,650	7,000	550	45	1,300	9.0	16	220	<8.2	2,900	14	42
RTH #1	12/22/2014	QCFD-01-141222	7.24	8,700	7,000	560	45	1,300	9.0	16	220	<8.2	2,900	11	40
RTH #3	4/29/2014	RTH-3-140429	6.86	2,810	1,900	200	93	280	25	4.1	120	<8.2	510	0.7	680
RTH #3	12/23/2014	RTH#3-122314	6.91	1,920	1,500	170	81	180	22	0.65	100	<8.2	130	0.16	800
RTH #4	4/29/2014	RTH-4-010429	7.52	5,900	4,400	450	170	580	22	6.9	210	<8.2	1,700	8.3	510
RTH #4	4/29/2014	QCFD-01-140429	7.53	5,900	4,100	430	160	560	22	6.8	220	<8.2	1,700	8.4	510
RTH #4	12/22/2014	RTH #4 - 122214	7.38	6,540	5,100	490	180	680	23	5.4	210	<8.2	2,000	3.4	370
RTH #5	12/21/2014	RTH #5 - 122114	7.69	624	450	64	23	51	6.4	0.066	220	<4.1	26	0.57	92
RTH #6	12/23/2014	RTH #6 - 122314	7.34	4,680	3,500	400	48	570	22	3.0	190	<8.2	1,300	23	290

⁽a) µmhos/cm = micromhos per centimeter

⁽b) mg/l = milligrams per liter

⁽c) "<10", "<8.2" = not detected above the practical quantitation limit

Table 4: Summary of Monitoring Well Sample Data - TPH as Crude Oil

Monitoring Well	Sample Date	Sample Name	TPH - Crude Oil μg/l ^(a)
RTH #1	4/30/2014	RTH-1-140430	1,300
RTH #1	12/22/2014	RTH #1 - 122214	<500
RTH #1	12/22/2014	QCFD-01-141222	<500
RTH #3	4/29/2014	RTH-3-140429	<500
RTH #3	12/23/2014	RTH#3-122314	<500
RTH #4	4/29/2014	RTH-4-010429	<500
RTH #4	4/29/2014	QCFD-01-140429	<500
RTH #4	12/22/2014	RTH #4 - 122214	<500
RTH #5	12/21/2014	RTH #5 - 122114	<500
	•		
RTH #6	12/21/2014	RTH #6 - 122114	<500

(a) µg/l = micrograms per liter


0 2,250 4,500 Feet

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Site Location Map

K/J 1365027*00 January 2015




Existing Soil Boring Location

Existing Shallow Monitoring Well Location

Proposed Deep Monitoring Well Location (to be installed by others)

Note:

1). Race Track Hill Area is located at W1/2 Section 24 T27S R29E WDB&M.



Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

bakersheid, Californi

Race Track Hill Boring and Well Locations

K/J 1365027*00 January 2015



•


Shallow Monitoring Well Location

RTH #1 (977.70)

Groundwater Elevation (FT AMSL)

Note:

1). Race Track Hill Area is located at W1/2 Section 24 T27S R29E WDB&M.




Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Groundwater Elevations

December 2014

K/J 1365027*00 January 2015



Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Geochemical Analysis of Racetrack Hill Groundwater Samples – December 2014

K/J 1365027*00 January 2015

Attachment A

RTH #5 and RTH #6 Boring Logs

RILLIN		DRING LOCATION Breckenridge Road									Well NameRTH#5			
	G COMPA		aa Dri	lling and Testing		, uu	DRIL		fuente	e				
RILLIN	G METHO	D(S)					DRIL	L BIT(S) S	IZE		4005007.00			
SOLATI	ON CASIN		w Ster	m Auger - CME 9	15		FROM	Reamed with 10-in. augers FROM TO FT.			Project Number	1365027.00		
LANK (CASING			n/a			FROM	<u>n/a</u> и	TO TO	/a FT.	TOC: 810.80 ft. AMS	L 57.4 ft. bgs		
LOTTE	D CASING		4-inch	SCH 40 PVC			FROM	0.5	27	'.0 FT.	DATE STARTED 12/11/14	DATE COMPLETED 12/11/14		
4-inch SCH 40 PVC 0.010-inch slotted IZE AND TYPE OF FILTER PACK						27.0	57	'.0	STATIC WATER ELEVATION 777.35 ft. AMSL	NORTH 2332160.899				
	D TYPE O	FFILIER		mex #2/12			FROM	24.5		'.4	LOGGED BY M. McLeod	EAST 6319525.753		
EAL		Wyo-	Ben M	edium Bent. Chip	os		FROM	^M 22.5	то 2 4	FT. I.5	SAMPLING METHODS	WELL COMPLETION		
ROUT		3% E	Benton	ite Cement Grou	ıt		FROM	м 3	то 22	FT. 2.5	Continuous coring	SURFACE HOUSING STAND PIPE		
	SAMPLES	Penetr.	Drill Depth	WELL CONSTI	RUCTION		USCS	Lithology	Color		SAMPLE DESCRIPTION a			
Type & No.	Recovery (Feet)	Resist. Blows/6"	(Feet)	well enclosure	i		Log	Littlology	00101					
	5		5-				SW	/.0	10YR 7/4	OVEF	<u>- GRADED SAND (SW)</u> \ RALL, <~5% GRAVEL, ~1), ~20% MEDIUM GRAINI NED SAND, DRY	0% COARSE GRAINED		
	2		10-	Bentonite- — Cement Grout			SW		(10YR 6/3 10YR 8/1	- BROV GRAV MEDI	/EL, ~20% COARSE GRA	INDANT WHITE, ~10-20% AINED SAND, ~23-30 0% FINE GRAINED SAND,		
	2		- - -	RI LO :			SW		10YR 6/4	- BROV), ~10-20% MEDIUM GRA	IGHT YELLOWISH 10% COARSE GRAINED AINED SAND, ~70% FINE E AND CONSOLIDATED,		
	No		15 - - -	Blank Casing —			GW			- VIOLE WITH		STRING RATTLES VEL IN CUTTINGS. DRILL ROCKY TO 17 FT. AND LESS		
	Core 2		20-				-			OVEF GRAN MEDI SAND	_ GRADED SAND (SW) \\ RALL WITH BROWNISH \\ /EL, <~10% COARSE GR\\ UM GRAINED SAND, ~10\\), VERY DENSE AND CO\\ HORIZONTAL BROWNISH	YELLOW STREAKS, TRACE RAINED SAND, ~60-70% 0-20% FINE GRAINED NSOLIDATED, DRY,		
	No Core		- - 25 -	Bentonite Seal —			-		10YR 7/3-7/4	- - -				
	1		-	Filter Pack —			SW		10YR 6/8		/EL INCREASES TO ~10- ETER	-20%, UP TO 2.5-INCHES		
	1.5		30 -	Slotted Screen — DTW:33.45 ft. =	7		-			- - -				

	Name	V	alley V	Vater Management Co.	_ Pı	oject N	lumber		1365027.00 Well NameRTH#5
ype No.	Recovery (Feet)	Penetr. Resist. Blows/6"	Drill Depth (Feet)	WELL CONSTRUCTION		USCS Log	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
	2		_	First Encountered	-				GRAVELLY WELL GRADED SAND (SW) YELLOW OVERALL WITH BROWNISH YELLOW STREAKS, ~20% GRAVEL TO 2-INCHES, ~10%20% COARSE GRAINED
	No Core		- - 40 <i>-</i>	Water	- - -				SAND, ~70% FINE GRAINED SAND, VERY DENSE, MOIST, ABUNDANT COARSE FELDSPAR AND QUARTZ
	1		- -		- : : -			10YR	41 FT. MATERIAL IS WET. WATER LEVEL MEASURED A APPX. 37 FT.
_	No Core		- - 45 -	Filter Pack	- - - -			7/6 10YR 6/8	MATERIAL IS DENSE AND GRAVELLY-CANNOT PENETRATE WITH SAMPLE BARREL SO START ALTERNATING CORING/NON CORING RUNS
	No Core		-	Clatted Course		SW			-
	1.5		50 - -	Slotted Screen	- -				50 FT. COLOR CHANGES TO BROWNISH YELLOW
_	No Core		- - 55 -					10YR 6/8	
	No Core		_ _		- -				57 FT. AUGER REFUSAL

NOTES

- 1. ALL CONTACTS APPROXIMATE
- 2. BGS: BELOW GROUND SURFACE
- 3. COLOR DESIGNATION IN ACCORDANCE WITH THE MUNSELL SOIL COLOR CHARTS (KOLLMORGEN INSTRUMENTS CORPORATION, 1990)
- 4. SOIL CLASSIFIED IN ACCORDANCE WITH THE UNIFIED SOIL CLASSIFICATION SYSTEM, ASTM D-2488-93

BORING & WELL CONSTRUCTION 1365027.00.GPJ KENNEDY JENKS.GDT 1/7/15

Ch SC FILTER	4-inch S GCH 40 P ER PACK Cem D-Ben Me	n/a SCH 40 PVC VC 0.010-inch sleex #2/12 dium Bent. Chip	otted	F	Rea FROM FROM FROM	n/a	LE 10-in. auge TO n/a TO 1113.	FT.	Project Name Valley	1365027.00
Ch SC FILTER Wyo-l 3% E	4-inch \$ 6CH 40 P 6CH 40 P Cem Cem 6-Ben Me	n/a SCH 40 PVC VC 0.010-inch sleex #2/12 dium Bent. Chip te Cement Grout	otted	F	FROM FROM FROM T	n/a +2.1	то n/a	FT.		
Ch SC FILTER Wyo- 3% E	CER PACK Cem Cem Bentonit	SCH 40 PVC VC 0.010-inch sleex #2/12 dium Bent. Chip te Cement Grout		F	ROM ROM	n/a ⊦2.1	n/a			TOTAL DEPTH
Penetr. Resist.	CER PACK Cem Cem Bentonit	VC 0.010-inch sl nex #2/12 dium Bent. Chip te Cement Grout		F	ROM 1	+2.1			ELEVATION AND DATUM TOC: 1059.82 ft. AMSL	145.0 ft. bgs
Penetr. Resist.	CER PACK Cem Cem Bentonit	VC 0.010-inch sl nex #2/12 dium Bent. Chip te Cement Grout		F	ROM 1	-		FT. 5	DATE STARTED	DATE COMPLETED
Nyo-	Cem D-Ben Me	nex #2/12 dium Bent. Chip te Cement Grout					ТО	FT.	12/8/14 STATIC WATER ELEVATION	12/8/14 NORTH
3% E	Bentonit	dium Bent. Chip	os	F		13.5	143.	FT.	939.51 ft. AMSL	2328430.428
3% E	Bentonit	te Cement Grout	s		TROM	11.0	145.	0 FT.	LOGGED BY M. McLeod	6316629.347
Penetr. Resist.	Drill				1	07.8	111.	0	SAMPLING METHODS Continuous coring	WELL COMPLETION SURFACE HOUSING
Resist.		WELL CONCED	t	F	ROM	1	то 107.	FT.	Communication of the second	STAND PIPE3
Resist.		Stand pipe ——			SCS I in	hology	Color		SAMPLE DESCRIPTION and	
	(Feet)	Well cap	-	Lo	og Litt	Hology	Coloi		SAMPLE DESCRIPTION and	JRILLING REWARKS
	- - - - 5-			- - - SI	M		10YR - 5/4	COAR	<u>' SAND (SM)</u> YELLOWISH B RSE GRAINED SAND, ~10-2 I, ~60-70% FINE GRAINED PLASTIC FINES, DRY	20% MEDIUM GRAINED
	10-			- S'	! :	-	10YR 7/3	OVER MEDII	_ GRADED SAND (SW) VEF tALL, ~10-20% COARSE GF UM GRAINED SAND, ~70% DENSE AND CONSOLIDA	RAINED SAND, ~20% FINE GRAINED SAND,
				M	1L		2.5Y - 6/3 -	OVER NON-I FRIAE	Y SILT (ML) LIGHT YELLO PALL, ~20-30% FINE GRAIN PLASTIC FINES, CEMENTE BLE; BREAKS INTO SUBHO	NED SAND, ~70% ED, BRITTLE, AND PRIZONTAL CHIPS
	15-	Bentonite- — Cement Grout			1L ()	` . ·	2.5Y 5/4 0YR 8/1	~40% SAND OLIVE	Y SILT (ML) LIGHT OLIVE COARSE GRAINED SAND WHITE FELDSPAR AND G BROWN SILT MATRIX, VE TICITY, DRY	TO MEDIUM GRAINÉD QUARTZ; ~60% LIGHT
	20-	Blank Casing —		- - - -	\		10YR _	BROV ~20% WHIT SOME	<u>. GRADED SAND WITH GR</u> VN OVERALL WITH YELLO GRAVEL, ~20% COARSE (E FELDSPAR), ~30% MEDI E MICAS), ~30% FINE GRAI E AND CONSOLIDATED	WISH BROWN STREAKS GRAINED SAND (MAINLY UM GRAINED SAND (INC
	25-				W		6/3 10YR 5/8	23 FT	. SOME SUBHORIZONTAL	COLOR BANDING
	-			 	- —); M			YELLO	OWISH BROWN BANDING,	,~80% FINE GRAINED
	30-				- — • • • • • • • • • • • • • • • • • •		10YR 6/3 10YR 5/8	BROV ~20% WHIT SOME	VN OVERALL WITH YELLO GRAVEL, ~20% COARSE (E FELDSPAR), ~30% MEDI E MICAS), ~30% FINE GRAI	WISH BROWN STREAKS GRAINED SAND (MAINLY UM GRAINED SAND (INC
		-	30-	30-	30- - - - - - - - - - - - - - - - - - -	30 - SW	30 - SW	25	23 FT 25	25 - 23 FT. SOME SUBHORIZONTAL 25 - 25 FT. SOME SUBHORIZONTAL 25 SM SILTY SAND (SM) LIGHT YELLO' YELLOWISH BROWN BANDING, SAND INC. MICAS, ~20% NON-P WELL GRADED SAND WITH GR BROWN OVERALL WITH YELLO ~20% GRAVEL, ~20% COARSE (WHITE FELDSPAR), ~30% MEDI SOME MICAS), ~30% FINE GRAI DENSE AND CONSOLIDATED

F-40.1 (6-87) (3-88) (8-90)

oject I	Name	v	alley W	ater Management Co.	P	roject N	lumber		1365027.00 Well NameRTH#6
	MPLES Recovery	Penetr. Resist.	Drill Depth (Feet)	WELL CONSTRUCTION	l	USCS	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
No.	(Feet)	Blows/6"			-	SM		2.5Y 6/3	SILTY SAND (SM) LIGHT YELLOWISH BROWN AND WHITE, ~15% WHITE MEDIUM GRAINED SAND FELDSPAR, ~70% LIGHT YELLOWISH BROWN FINE GRAINED SAND, ~15% NON-PLASTIC FINES, MOIST?
	5		40-		-	SW		10YR 6/3 10YR 5/8	WELL GRADED SAND WITH GRAVEL (SW) PALE BROWN OVERALL WITH YELLOWISH BROWN STREAK: ~20% GRAVEL, ~20% COARSE GRAINED SAND (MAINL) WHITE FELDSPAR), ~30% MEDIUM GRAINED SAND (INC SOME MICAS), ~30% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
			45-		-	SM		2.5Y 6/3 2.5Y	SILTY SAND OR SILTY SAND WITH CLAY (SM) LIGHT YELLOWISH BROWN OVERALL, ~80% FINE GRAINED SAND INC. MICA, ~20% SILT AND SOME CLAY, VERY \STIFF/DENSE, NO TO LOW PLASTICITY
	5				-	SM ——— ML		5/3 	SILTY SAND (SM) LIGHT OLIVE BROWN AND WHITE, ~80% FINE GRAINED SAND INC. MICA, ~20% \ NON-PLASTIC FINES, BRITTLE AND BREAKS INTO \SUBHORIZONTAL CHIPS
			50-		-			2.5Y 5/3	SANDY SILT (ML) LIGHT YELLOWISH BROWN OVERALL, ~10% SCATTERED WHITE MEDIUM GRAINEI SAND, ~20-30% SCATTERED FINE GRAINED SAND, ~60% NON-PLASTIC FINES AND POSS. CLAY, VERY
	4.5				-	ML		2.5Y6/8	\STIFF, NO PLASTICITY, DRY SILT TO SANDY SILT (ML) LIGHT OLIVE BROWN OVERALL, ~5-10% FINE GRAINED SAND, ~80-90% SILT VERY STIFF AND BRITTLE
			55 -	Bentonite- Cement Grout	-	ML		2.5Y 6/3 	52 FT 54 FT. COLOR INCLUDES OLIVE YELLOW SANDY SILT (ML) LIGHT YELLOWISH BROWN OVERALL, ~10-20% SCATTERED WHITE AND BLACK MEDIUM GRAINED SAND, ~80% NON-PLASTIC FINES,
	4.5		-		-	SM		2.5Y 7/2 — — — 2.5Y	VERY STIFF, NO PLASTICITY SILTY SAND (SM) LIGHT BROWNISH GRAY TO LIGHT BROWN, ~60% FINE GRAINED SAND INC. MICAS, ~40-20% NON-PLASTIC FINES, MOIST TO DRY
			60 -	Blank Casing	-	SW		6/2	- <u>WELL GRADED SAND (SW)</u> LIGHT BROWNISH GRAY OVERALL, ~20% COARSE GRAINED SAND, ~40% □ MEDIUM GRAINED SAND, ~40% FINE GRAINED SAND, \VERY DENSE, DRY
	4		65 -		-	SM		2.5Y 5/3	SILTY SAND (SM) LIGHT OLIVE BROWN AND WHITE, ~40% WHITE COARSE GRAINED SAND - MEDIUM GRAINED SAND FELSPAR AND QUARTZ; ~60% LIGHT OLIVE BROWN FINE GRAINED SAND AND NON-PLASTI FINES
	3.5		-		-			2.5Y 7/2	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH OLIVE YELLOW STAINS AND BLACK AND WHITE GRAINS, ~10% GRAVEL, ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
	3.5		70 - - -		-	SW		2.5Y 5/8 10YR 8/1	- - -
	5		75 - -		-	SM		2.5Y 6/3 2.5Y 6/8	SILTY SAND (SM) LIGHT YELLOWISH BROWN OVERALL WITH SOME SUBHORIZONTAL BANDING AND OLIVE YELLOW STAINING, ~80-90% FINE GRAINED SAND, ~10-20% NON-PLASTIC FINES
			80		-	SM		 2.5Y 5/3	SILTY SAND (SM) LIGHT OLIVE BROWN AND WHITE,

oject	Name	V	alley V	Nater Management Co	О Р	roject l	Number		1365027.00 Well NameRTH#6
<u> </u>	AMPLES Recovery (Feet)	Penetr. Resist.	Drill Depth (Feet)	WELL CONSTRUCTION		USCS Log	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
x NO.	(Feet)	Blows/6"			-				 ~40% WHITE COARSE GRAINED SAND - MEDIUM - GRAINED SAND FELDSPAR AND QUARTZ; ~60% LIGHT OLIVE BROWN FINE GRAINED SAND AND NON-PLASTIC
	4		- - 85 -		-	sw		2.5Y 7/2 2.5Y 5/8	FINES WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH OLIVE YELLOW STAINS AND BLACK AND WHITE GRAINS, ~10% GRAVEL, ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND
	3		- -		-	SM		10YR 8/1 ———————————————————————————————————	SILTY SAND (SM) GRAYISH BROWN AND WHITE, ~20% WHITE COARSE GRAINED SAND - MEDIUM GRAINED SAND FELDSPAR AND QUARTZ; ~40-60% GB FINE
	4		90 -	Bentonite- Cement Grout	- -	-		2.5Y	GRAINED SAND AND ~40% GB NON-PLASTIC FINES WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, ~10% GRAVEI ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
			95 -	Blank Casing	-	SW		7/2 10YR 8/1	
	4.5		- - -		-	SM		2.5Y 5/2	SILTY SAND (SM) GRAYISH BROWN OVERALL, TRACE COARSE GRAINED SAND, ~10-20% MEDIUM GRAINED SAND, ~70% FINE GRAINED SAND, ~20% NON-PLASTIC
	4		100-		-	- - -			FINES, VERY DENSE, DRY WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, <10% GRAVEI ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
	4		105 - - - - 110 -	Bentonite Seal —	-	SW		2.5Y 7/2 10YR 8/1	
	3		-	Filter Pack ——		_			
	3		115 - - -	Slotted Screen	-	SW		 2.5Y 6/2 	WELL GRADED SAND WITH SILT (SW) LIGHT BROWNISH GRAY OVERALL, TRACE GRAVEL, TRACE COARSE GRAINED SAND, ~10-20 MEDIUM GRAINED SAND, ~70% FINE GRAINED SAND, ~10% NON-PLASTIC
ŀ	1		120 - -	DTW: 120.31 ft. ▼ TOC, 12/22/14 First Encountered ▼	-	SW		2.5Y 7/2 10YR 8/1	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, ~10% GRAVE ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED 120-125 FT. DRILL WITHOUT SAMPLING DUE TO
			- 125 -	Water					DENSITY AND GRAVEL BLOCKAGE 125 FT. AFTER LUNCH BREAK SOUND WATER LEVEL A 123 FT. BGS

Project	Name	v	alley W	/ater Management Co.	Proje	ect N	umber .		1365027.00 Well Name RTH#6
Type & No.	Recovery (Feet)	Penetr. Resist. Blows/6"	Drill Depth (Feet)	WELL CONSTRUCTION	US	SCS Log	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
-			-		-				WELL GRADED SAND WITH GRAVEL CONT'D
- - [3		-		_				125-130 FT. SAMPLER BARREL IS WET
- 			130		-			2.5Y	- -
- - -	3		-					7/2 10YR 8/1	- - -
- ■			135	Filter Pack	_ s	SW			135-140 FT. DRILL WITHOUT SAMPLING DUE TO DENSITY AND GRAVEL BLOCKAGE
- -	No core		-		_				- -
 			140-	Slotted Screen	-			2.5Y 6/2	140 FT. COLOR CHANGES TO LIGHT BROWNISH GRAY WITH WHITE AND BLACK GRAINS
- -	3		-					10YR 8/1	- -

NOTES

- 1. ALL CONTACTS APPROXIMATE
- 2. BGS: BELOW GROUND SURFACE
- 3. COLOR DESIGNATION IN ACCORDANCE WITH THE MUNSELL SOIL COLOR CHARTS (KOLLMORGEN INSTRUMENTS CORPORATION, 1990)
- 4. SOIL CLASSIFIED IN ACCORDANCE WITH THE UNIFIED SOIL CLASSIFICATION SYSTEM, ASTM D-2488-93

BORING & WELL CONSTRUCTION 1365027.00.GPJ KENNEDY JENKS.GDT 1/7/15

Appendix B

Report on Phase 2 Installation of Shallow Monitor Wells at Race Track Hill

Kennedy/Jenks Consultants

303 Second Street, Suite 300 South San Francisco, California 94107 415-243-2150 FAX: 415-896-0999

Shallow Monitoring Well Installation Report Race Track Hill Area, Edison Oil Field California

30 June 2015

Prepared for

Valley Water Management Company

7500 Meany Avenue Bakersfield, California 93308

K/J Project No. 1365027*00

Table of Contents

List of Tables.		i
List of Figures	S	i
List of Append	dices	i
Section 1:	Introduction	1
Section 2:	Site Descriptions and Field Investigations	2
	Race Track Hill Site Shallow Groundwater Phase 2 Field Investigations	
Section 3:	Field Activities	3
	3.1 Pre-Field Activities	3 4 4 4
Section 4:	Findings of the Field Investigations	6
	4.1 Soil Stratigraphy at Race Track Hill	7 7
	4.3 Isotopic Analysis	7 7
Section 5:	Conclusions	9
Section 6:	Recommendations	10
References		11

List of Tables

- B-1 Monitoring Well Completion Details
- B-2Summary of Shallow Groundwater Elevation Data
- B-3Summary of Shallow Monitoring Well Sample Data Inorganic Analytes
- B-4Summary of Shallow Monitoring Well Sample Data TPH as Crude Oil
- B-5Summary of Shallow Monitoring Well Sample Data Oxygen and Hydrogen Isotopes

List of Figures

- **B-1 Site Location Map**
- B-2Race Track Hill Produced Water Discharge Facility
- B-3Race Track Hill Groundwater Elevations December 2014
- B-4Isotope Diagram of Race Track Hill Shallow Well Groundwater Samples December 2014

List of Appendices

- B-1 Permits and Boring and Well Construction Logs
- B-2 Monitoring Well Development Logs
- B-3 Survey Report
- B-4 Monitoring Well Purge Forms
- B-5 Monitoring Well Sample Laboratory Reports

Section 1: Introduction

This Shallow Monitoring Well Installation Report (Report) has been prepared by Kennedy/Jenks Consultants (Kennedy/Jenks) for the Race Track Hill Facility, one of the two Valley Water Management Company (VWMC) sites that serve the Edison Oilfield east of Bakersfield, California (Figure B-1).

The Race Track Hill location is shown on Figure B-1. It is located approximately four miles northeast of the Fee 34 Facility, from which it receives treated oilfield produced water, and discharges the treated water to surface impoundments where the water is distributed to percolation/evaporation ponds or spray irrigation areas for evapotranspiration. The Race Track Hill Facility is regulated by Central Valley Regional Water Quality Control Board (RWQCB) Resolution No. 58-349.

On 1 July 2014, the RWQCB issued a California Water Code Directive pursuant to Section 13267 (13267 Order) (CVRWQCB 2014) to VWMC. This 13267 Order required that VWMC develop a Work Plan for additional investigations at the Fee 34 and Race Track Hill facilities. Prior to the 13267 Order, VWMC had been conducting investigations on a voluntary basis but with the input of RWQCB staff and management. The 13267 Order also required that investigations and reporting be completed by 15 January 2015.

The initial investigations (the Phase 1 investigation) conducted at the site provided an assessment of potential soil and groundwater impacts caused by site operations. The Phase 1 investigation results were presented in the *Phase 1 Subsurface Investigation Report at the Fee 34 Facility and Race Track Hill Area, Edison Oil Field, California* dated 1 August 2014 (Kennedy/Jenks 2014a).

The Phase 1 report recommended additional groundwater investigation. The shallow groundwater investigation was described in the *Phase 2 Investigation Work Plan* (Work Plan) dated 10 November 2014 (Kennedy/Jenks 2014b). Phase 2 included installation and sampling of shallow monitoring wells (discussed in this Report), and a separate program of deep monitoring well installation (in preparation by others).

This Report discusses the installation, development, surveying, and initial sampling of the shallow monitoring wells. Synthesis of the findings of the shallow and deep monitoring wells will be prepared in a separate report.

Section 2: Site Descriptions and Field Investigations

2.1 Race Track Hill Site

The Race Track Hill site consists of 338.4 acres (Assessor's Parcel Number 387-060-031) in the western half of Section 24, T29S, R29E, MDB&M. The Race Track Hill Facility is in an area of steep and rolling topography (Figure B-2). Produced water flow from the Fee 34 site enters Race Track Hill at a netted pond at a higher elevation than the highest point where water can be applied on the site. As a result, distribution of all discharges on the site can be conducted via gravity.

There are 27 unlined surface impoundments used for produced water percolation and evaporation. The ponds lie along several existing drainageways that are usually dry except for the percolation ponds. In addition, there are 94 acres with sprinkler irrigation systems that are also used for land application. Salt-tolerant local grasses and some shrubs take up water from the soil to meet their evapotranspiration needs.

2.2 Shallow Groundwater Phase 2 Field Investigations

The objective of the shallow groundwater Phase 2 investigation was to further assessment of shallow groundwater downgradient of the Site. Two new shallow groundwater monitoring wells were installed, developed, and surveyed; and all shallow monitoring wells were sampled. Samples were analyzed for inorganic constituents, Total Petroleum Hydrocarbons as crude oil (TPHc), and isotopic analysis of O¹⁸ and deuterium. New monitoring well RTH#5 was installed north of the Site near Cottonwood Creek, and new monitoring well RTH#6 was installed on the southwest side of the southernmost surface impoundment in the southern drainage (Figure B-2).

Well construction details are summarized in Table B-1.

Section 3: Field Activities

Details of the completed field investigations are presented in this section. In addition, sampling procedures and analytical methods are discussed.

3.1 Pre-Field Activities

Kennedy/Jenks performed the following activities prior to commencing fieldwork.

- Updated the site-specific Health and Safety Plan.
- Well installation permits (Appendix B-1) were obtained from Kern County.
- The boring locations were checked for potential location conflicts with subsurface utilities by performing a utility clearance check at each location prior to drilling. The survey was done by contacting USA Alert and a private subsurface utility locating service.
- Subcontracted with Gregg Drilling and Testing Inc. (Gregg Drilling) of Signal Hill,
 California to perform the boring and well construction fieldwork.
- Arranged with ELAP-certified BC Laboratories, Inc. (BC Laboratories) of Bakersfield to provide laboratory analytical services for water samples.
- Arranged with the University of Arizona Environmental Isotope Laboratory to analyze samples for oxygen and hydrogen isotopes.

3.2 Soil Borings and Well Construction Methods

3.2.1 Soil Boring Drilling and Sampling

Gregg Drilling advanced the borings using a CME-95 drill rig and 8-inch diameter hollow stem augers. The soil was cored with a 5-foot long CME core barrel. The core at each boring was laid on plastic sheeting for logging and a small portion was placed in a sealed plastic bag. The borings were reamed with 10-inch diameter augers after the coring was completed. Boring and well construction logs are included in Appendix B-1.

3.2.2 Well Installation

Each well was constructed with new, 4-inch diameter SCH 40 PVC. Each well screen was 20 feet in length, and the annular space around the well screen was filled with clean, graded Cemex #2/12 filter pack sand up to 1-2 feet above the well screen. Well RTH#1 had 0.020-inch slots and the others had 0.010-inch slots. Each filter pack interval was overlain with three to four feet of bentonite pellets or chips, which were allowed to hydrate prior to pouring the sanitary seal. The sanitary seal was composed of 3-5% bentonite-cement grout, which was installed using a tremie pipe. Well RTH#6 was completed with an above-ground steel standpipe and RTH#5 was completed with a traffic-rated flush monument. Each well was surged using a swab

tool sized for the well casing diameter after the filter pack was installed and prior to the bentonite seal installation.

3.2.3 Well Development

The wells were developed on 23 and 24 April 2014. Gregg developed each monitoring well by bailing, surging, and pumping until the water turbidity was less than five nephelometric turbidity units (NTU). The pH, temperature, conductivity, and dissolved oxygen were recorded. The development logs are included in Appendix B-2.

3.2.4 Surveying

The location and well casing elevations of the new monitoring wells were horizontally and vertically surveyed by a licensed land surveyor (Dee Jaspar and Associates, Bakersfield, California). The ground surface and top of well casing elevation were surveyed to the nearest 0.01 foot relative to mean sea level. The ground surface and top of casing were surveyed to the North American Vertical Datum (NAVD) 1988, relative to the nearest benchmark for the Site. The horizontal location of each new well was surveyed relative to the California Coordinate system to 0.1 foot precision. Appendix B-3 presents the elevations measured by the surveyor.

3.2.5 Monitoring Well Groundwater Sampling and Analysis

Kennedy/Jenks collected samples from all of the site wells on 21 through 23 December 2014 in accordance with the Work Plan. At least three casing volumes were removed from each well with a Grundfos Redi-flo submersible pump.

The field parameters, pH, temperature, electrical conductivity, dissolved oxygen, and oxidation-reduction potential, were monitored during purging to document stabilization. The documentation is included in Appendix B-4. Laboratory reports are included in Appendix B-5.

3.2.6 Residuals Management

Residuals generated as a result of these activities included soil cuttings and core, decontamination water, and development and purge water from the monitoring wells.

Cuttings were piled up near each drill site for onsite distribution by VWMC. Drilling and sampling equipment was decontaminated near the ponds at Race Track Hill and overspray drained to the ponds. Development and purge water was temporarily contained at each well site then transported to a nearby percolation pond and discharged.

3.2.7 Quality Assurance/Quality Control Procedures

The laboratory followed their standard internal QA/QC procedures during sample analysis, including elements such as analyzing method blanks and control spikes, where appropriate.

All reported results were acceptable. In some cases, practical quantitation limits or method detection limits were raised due to sample dilution or matrix interference. Boron recovery in the

Kennedy/Jenks Consultants

matrix spike (MS) and matrix spike duplicates (MSD) was estimated. Evaluation of calcium and sodium the matrix spike/matrix spike duplicate samples could not be performed because the constituent was present in the sample at more than four times the spike concentration.

Findings of the Field Investigations Section 4:

This section presents the findings of the shallow well installation and sampling.

4.1 Soil Stratigraphy at Race Track Hill

Two soil borings were drilled and converted to monitoring wells. Well RTH#5 was located in the Kern County right-of-way on the north side of Breckinridge Road approximately 0.5 miles northeast of the northeasternmost pond of the Race Track Hill facility. The well is located at ground elevation is 811 feet above mean sea level (AMSL), as Breckenridge Road makes a gradual descent from the Race Track Hill Facility along a drainage toward the Cottonwood Creek valley.

Well RTH#6 was located at the west side of the berm of the southernmost pond of the southern drainage. It was sited to assess local groundwater quality in the vicinity of the pond.

RTH#5. The subsurface at RTH#5 consisted of sand and gravel mixtures. Recovered gravels measured up to 2.5-inches diameter and larger gravels and cobbles were probably present, based upon the resistance met by the drill rig. The materials observed in this boring are consistent with alluvial sediment derived from the nearby Santa Margarita Formation.

Water was first encountered at 41 feet below ground surface (bgs) and later measured at 37 feet bgs. The drill was unable to penetrate deeper than 57 feet bgs due to the gravelly and cobbly subsurface so the well screen was set from 27 feet bgs to 57 feet bgs.

RTH#6. RTH#6 was drilled approximately 50 feet southwest of the southernmost percolation pond of the southern valley at a ground surface elevation of 1,057 feet AMSL. At this location, groundwater was encountered at 123 feet bgs and the boring was advanced to 145 feet bgs.

Near the surface the material was mainly silty sand to 17 feet bgs, and composed mainly of well graded sand from 17 to 43 feet bgs. Between 43 feet bgs and 65 feet bgs, the material was a mix of silt/fine sand mixtures. The material was very dense, very stiff, and in some cases broke into brittle thin layers. Abundant weathered feldspar was present.

Below 65 feet the material was mainly well graded sand with gravel some silty sand layers. The material was very dense and consolidated, keeping the 'core' shape after removal from the core

Water was encountered at 123 feet bgs and the well was screened from 113.5 feet bgs to 143.5 feet bgs.

4.2 Groundwater Sampling Results

4.2.1 Groundwater Elevation

Groundwater elevation data for both April 2014 and December 2014 monitoring well sampling events are included in Table B-2. Three wells have been sampled twice. Of these RTH#1 has approximately the same water level in April and December, likely due to its location adjacent to an active percolation pond that maintains water levels in the area. The two wells at the base of Race Track Hill, RTH#3 and RTH#4, both have static water levels approximately 6 feet lower in December than in April.

Figure B-3 shows water level elevations for the December 2014 sampling event. No attempt was made to provide water level contours because there are too many variables that affect groundwater flow in the area: a large percolation volume in the 21 ponds at Race Track Hill, a large elevation change between wells on Race Track Hill and those in the valley east of Race Track Hill, and marked differences in subsurface conditions among the well locations.

4.2.2 Groundwater Sample Analytical Results

The results of April 2014 and December 2014 groundwater sampling are shown in Table B-3 and Table B-4.

EC and TDS are highest at well RTH#1 and slightly lower at RTH#4 and RTH#6. These parameters are lowest at wells RTH#3 and RTH#5. RTH#5 is much lower in EC and TDS than all other wells, likely because it is furthest from Race Track Hill and influenced by water from other sources. This comparative trend among wells is consistent for a number of constituents including boron and chloride. Calcium and sodium also follow this trend. Nitrate nitrogen, sulfate, magnesium, potassium, and alkalinity all have different trends.

4.3 Isotopic Analysis

4.3.1 Introduction

Isotopic composition is determined by measuring the atom ratio of a minor abundance isotope to a major abundance isotope. For oxygen, the ratio measured is ¹⁸O/¹⁶O, i.e. the atom ratio of Oxygen-18 to Oxygen-16 (Singleton et al. 2013). For hydrogen, the ratio measured is ²H/¹H, i.e. the atom ratio of hydrogen-2 to hydrogen-1. Hydrogen-2 is also referred to as deuterium (D).

Isotope ratios are reported in the standard delta (δ) notation as parts per thousand (per mil or ‰) variations relative to a reference material of known composition. For oxygen and hydrogen in water, the Vienna Standard Mean Ocean Water (VSMOW; Craig, 1961) is used as a reference (Singleton et al. 2013).

4.3.2 Results from Race Track Hill

The isotopic data from shallow monitoring wells at Race Track Hill is summarized in Table B-5 and graphed on Figure 6. Figure 6 also shows the Global Meteoric Water Line (GMWL) (Craig,

1961). The $\delta^{18}O$ in groundwater samples ranged from -5.6 ‰ in RTH#6 to -8.8 ‰ in RTH#5. The δ^2H ranged from -54 in RTH#1 to -64 in RTH#5. Isotopes were not analyzed in the produced water sample.

Section 5: Conclusions

The following conclusions are based upon the findings of this investigation:

- Two additional shallow monitoring wells (RTH#5 and RTH#6) were installed in the shallow aguifer at Race Track Hill.
- A total of four shallow monitoring wells are present onsite and one is located offsite.
- The groundwater quality in the RTH#5 is unlike the quality of the onsite wells and RTH#3.
- The groundwater quality in RTH#6 is more similar to RTH#1.

Section 6: Recommendations

The following recommendations are based upon the results presented above:

- Continue groundwater monitoring.
- Evaluate the produced water quality in the ponds.
- Submit a report evaluating shallow groundwater, deep groundwater, offsite groundwater, and produced water quality, and their relation to each other.

A detailed work plan should be prepared prior to conducting any further subsurface investigations.

References

- Craig, H. 1961. Standard for Reporting Concentrations of Deuterium and Oxygen-18 in Natural Waters. Science, 133, p. 1833-1834.
- Central Valley Regional Water Quality Control Board (CVRWQCB, 2014). California Water Code Directive Pursuant to Section 13267 Valley Water Management Company. Fee 34 Facility and Race Track Hill Area, Edison Oil Field, Kern County. 1 July 2014.
- Kendall, C., Coplen, T.B. 2001. Distribution of Oxygen-18 and Deuterium in River Waters Across the United States. Hydrological Processes, 15, p. 1363-1393.
- Kennedy/Jenks Consultants. 2014a. Phase 1 Subsurface Investigation Report at the Fee 34 Facility and Race Track Hill Area, Edison Oil Field, California. 1 August 2014.
- Kennedy/Jenks Consultants. 2014b. Phase 2 Investigation Work Plan. 10 November 2014.
- Singleton, M.J., Roberts, S.K., Moran, J.E., Esser, B.K. 2013. California GAMA Domestic Wells: Nitrate and Water Isotopic Data for Tulare County. Lawrence Livermore National Laboratory. January 2011 Revised August 2013.

Tables

Table B-1: Monitoring Well Completion Details

					Well S	Screen	Sand	Sand Pack ^(d)		(d) Bentonite Seal		Grout Seal	
Well ID	Completion Date	Well Diameter (inches)	Top of Casing Elevation (ft AMSL) ^(a)	Drilled Depth (ft bgs) ^(b)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)	Top (ft bgs)	Bottom (ft bgs)	
RTH#1	04/11/2014	4	1025.85	70.5	50	70	48	70.5	45	48	1.5	45.0	
RTH#3	04/22/2014	4	879.39	105.1	84.6	104.6	82	105.1	76.2	82	1	76.2	
RTH#4	04/17/2014	4	871.02	150	80	100	78	104	72	78	5	72	
RTH#5	12/11/2014	4	810.8	57.4	27	57	24.5	57.4	22.5	24.5	3	22.5	
RTH#6	12/10/2014	4	1059.82	145.0	113.5	143.5	111	145.0	107.8	111.0	1	107.8	

⁽a) "ft AMSL" denotes feet above mean sea level, NAVD88. RTH#1 through RTH#4 surveyed in June 2014 and RTH#5 and RTH#6 surveyed in December 2014 by Dee Jaspar and Associates.

⁽b) "ft bgs" denotes feet below ground surface.

Table B-2: Summary of Shallow Groundwater Elevation Data

Monitoring Well	Measuring Point ^(a) Elevation (ft AMSL) ^(b)	Date	Depth to Groundwater (ft TOC) ^(c)	Groundwater Elevation (ft AMSL)
RTH #1	1025.85	4/30/2014	47.91	977.94
RTH #1	1025.85	12/22/2014	48.15	977.70
RTH #3	879.39	4/29/2014	80.83	798.56
RTH #3	879.39	12/22/2014	87.31	792.08
RTH #4	871.02	4/29/2014	78.45	792.57
RTH #4	871.02	12/22/2014	84.41	786.61
RTH#5	810.80	12/21/2014	33.45	777.35
DTILLIC	1050.00	12/22/2014	120.21	020 F1
RTH#6	1059.82	12/22/2014	120.31	939.51

⁽a) Top of PVC Well Casing

⁽b) ft AMSL = feet above mean sea level, to NAVD88 datum. RTH#1 through RTH#4 surveyed in June 2014 and RTH#5 and RTH#6 were surveyed in December 2014 by Dee Jaspar & Associates.

⁽c) ft TOC = feet below top of casing

Table B-3: Summary of Shallow Monitoring Well Sample Data - Inorganic Analytes

Monitoring Well	Sample Date	Sample Name	рН	Electrical Conductivity @ 25°C	Total Dissolved Solids @ 180°C	Calcium	Magnesium	Sodium	Potassium	Boron	Bicarbonate Alkalinity as CaCO ₃	Carbonate Alkalinity as CaCO ₃	Chloride	Nitrate as N	Sulfate
			pH Units	µmhos/cm ^(a)	mg/L ^(b)	mg/L	mg/L	mg/L	mg/L	mg/l	mg/L	mg/L	mg/L	mg/L	mg/L
RTH #1	4/30/2014	RTH-1-140430	7.31	8,690	6,600	560	44	1,100	8.9	16	240	<8.2 ^(c)	2,900	7.1	42
RTH #1	12/22/2014	RTH #1 - 122214	7.26	8,650	7,000	550	45	1,300	9.0	16	220	<8.2	2,900	14	42
RTH #1	12/22/2014	QCFD-01-141222	7.24	8,700	7,000	560	45	1,300	9.0	16	220	<8.2	2,900	11	40
RTH #3	4/29/2014	RTH-3-140429	6.86	2,810	1,900	200	93	280	25	4.1	120	<8.2	510	0.7	680
RTH #3	12/23/2014	RTH#3-122314	6.91	1,920	1,500	170	81	180	22	0.65	100	<8.2	130	0.16	800
RTH #4	4/29/2014	RTH-4-010429	7.52	5,900	4,400	450	170	580	22	6.9	210	<8.2	1,700	8.3	510
RTH #4	4/29/2014	QCFD-01-140429	7.53	5,900	4,100	430	160	560	22	6.8	220	<8.2	1,700	8.4	510
RTH #4	12/22/2014	RTH #4 - 122214	7.38	6,540	5,100	490	180	680	23	5.4	210	<8.2	2,000	3.4	370
RTH #5	12/21/2014	RTH #5 - 122114	7.69	624	450	64	23	51	6.4	0.066	220	<4.1	26	0.57	92
RTH #5	6/8/2015	RTH#5-150608									-			-	
RTH #6	12/23/2014	RTH #6 - 122314	7.34	4,680	3,500	400	48	570	22	3.0	190	<8.2	1,300	23	290

⁽a) µmhos/cm = micromhos per centimeter

⁽b) mg/l = milligrams per liter

⁽c) "<8.2"= not detected above the practical quantitation limit

Table B-4: Summary of Shallow Monitoring Well Sample TPH as Crude Oil

TPH - Crude Oil

Monitoring Well	Sample Date	Sample Name	μg/l ^(a)
RTH #1	4/30/2014	RTH-1-140430	1,300
RTH #1	12/22/2014	RTH #1 - 122214	<500
RTH #1	12/22/2014	QCFD-01-141222	<500
RTH #3	4/29/2014	RTH-3-140429	<500
RTH #3	12/23/2014	RTH#3-122314	<500
RTH #4	4/29/2014	RTH-4-010429	<500
RTH #4	4/29/2014	QCFD-01-140429	<500
RTH #4	12/22/2014	RTH #4 - 122214	<500
RTH #5	12/21/2014	RTH #5 - 122114	<500
RTH #6	12/21/2014	RTH #6 - 122114	<500

Note:

(a) µg/l = micrograms per liter

Table B-5: Summary of Shallow Monitoring Well Sample Data - Oxygen and Hydrogen Isotopes

			$\delta^{18}O^{\;(a)}$	$\delta^2 H^{(b)}$
Monitoring Well	Sample Date	Sample Name	‰ ^(c)	‰
RTH #1	12/22/2014	RTH #1 - 122214	-6.2	-54
RTH #3	12/23/2014	RTH#3-122314	-6.7	-60
RTH #4	12/22/2014	RTH #4 - 122214	-6.8	-58
RTH #5	12/21/2014	RTH #5 - 122114	-8.8	-64
RTH #6	12/21/2014	RTH #6 - 122114	-5.8	-56

⁽a) δ^{18} O = delta Oxygen-18 (δ^{18} O = 1000*[(18 O/ 16 O sample - 18 O/ 16 O reference) / 18 O/ 16 O reference])

⁽b) $\delta^2 H$ = delta Deuterium ($\delta^2 H$ = 1000*[($^2 H$ / $^1 H$ sample - $^2 H$ / $^1 H$ reference)/ $^2 H$ / $^1 H$ reference])

⁽c) ‰ = per mil

⁽d) Sources: Craig, 1961 and Vienna Standard Mean Ocean Water

Figures

Ν

2,250

Feet

4,500

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Locations of the Valley Water Management Company Edison Oil Field Facilities

> K/J 1365027*00 June 2015



Note:

RTH #7D

RTH #1

1). Race Track Hill Area is located at W1/2 Section 24 T27S R29E WDB&M.

Shallow Monitoring Well Location

400

Valley Water Management Company Bakersfield, California

> Race Track Hill Produced **Water Discharge Facility**

> > K/J 1365027*00 June 2015



Legend:



Shallow Monitoring Well Location Water Level Elevation (AMSL)


0 300 600 Feet

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Shallow Groundwater Elevations December 2014

K/J 1365027*00 June 2015



Notes:

- 1. Metoric water line: δ2H=8.13*δ18O+10.0: Craig, H. 1961. Isotopic variations in meteoric waters. Science, 133, 1702-1703, in http://cierzo.sahra.arizona.edu/programs/isotopes/oxygen.html#5
- 2. $\delta^{18}O$ = delta Oxygen-18 ($\delta^{18}O$ = 1000*[(^{18}O / ^{16}O sample ^{18}O / ^{16}O reference) / ^{18}O / ^{16}O reference])
- 3. $\delta^2 H = delta Deuterium (\delta^2 H = 1000*[(^2H/^1H sample ^2H/^1H reference) / ^2H/^1H reference])$
- 4. ‰ = per mil

Kennedy/Jenks Consultants

Valley Water Management Company Bakersfield, California

Isotopic Analysis of Groundwater at Fee 34
Facility and Race Track Hill

K/J 1365027*00 June 2015

Appendix B-1

Permits and Well Construction Logs



MATTHEW CONSTANTINE DIRECTOR

2700 M STREET, SUITE 300

BAKERSFIELD, CALIFORNIA 93301-2370

VOICE: 661-862-8740

FAX: 661-862-8701

WWW.CO.KERN.CA.US/EH

Starting Date: 12/10/14

	nstruct/Modify
	of Well
□ Domestic/Private (1) □ Agricultural □ Domestic (2-4 connections) □ Test Hole □ Domestic (5 or more connections) x Monitoring	Cathodic Protection Vadose Other: PARTY RESPONSIBLE FOR PAYMENT OF FEES
OWNER'S INFORMATION	PROPERTY/FACILITY INFORMATION
Name Valley Water Management Co.	Name Kern County ROW
Address 7500 Meany Ave.	Address
City Bakersfield State Ca Zip 93308	City State Zip
Phone e-mail Bright@vwwater.co	APN N/a T 29S R 29E Sec 24
CONTRACTO	R'S INFORMATION
Environmental Contractor Kennedv/Jenks Cons. Inc. 303 Second St. Ste 300 South Address	Drilling Contractor Gregg Drilling and Testing Address 2726 Walnut Ave.
City San Francisco State Ca Zip 9410	City Signal Hill State Ca Zip 90755
Contact Mike McLeod Phone 415-243-2150	Contact Joanna McKeehan Phone 562-427-6899
e-mail mikemcleod@kennedyjenks.com	e-mail jmckeehan@greggdrilling.com
bodies or courses, drainage pattern, roads, existing wells, straction at 200' radius circle from well site location. For including: location of tanks, proposed monitoring and placement water within 500' radius of facility.	TOTAL ACRES: n/a ect to the following items: property lines, adjoining properties, water ctures, sewers or private disposal systems. Include dimensions nonitoring wells provide a description of the facility to be monitored, nearest street or intersection, location of any water wells or surface
Provide detailed directions to site:	
From the intersection of Breckinridge Road and Comand	e Drive, go northeast on Breckinridge 2.81 miles.
Well is in shoulder on north side of Breckinridge Rd.	

THIS APPLICATION BECOMES A PERMIT WHEN APPROVED

WELL CONSTRUCTION INFORMATION

METHOD: Reverse Rotary Rota	ary 🗌 Air Rotary X Hollow Stem Auger 🔲 Other:
WELL NAME / NUMBER	RTH#6
MAXIMUM WELL DEPTH	150
SEALING MATERIAL	Cement
SEAL DEPTH (HARD ROCK/ UNCONSOLIDATED)	115
CASING MATERIAL & GAUGE	SCH40 PVC
CASING - INSIDE DIAMETER	4"
SCREEN/PERFORATION DEPTH	120-150
CONDUCTOR DEPTH	N/a
CONDUCTOR DIAMETER	N/a
DEPTH TO GROUNDWATER	Unk., <120
LOCKING WELL CAP	
BOREHOLE DIAMETER	10"
SCREEN MATERIAL & GAUGE	SCH40 PVC
TYPE OF BENTONITE PLUG & DEPTH	Med. Bent. Chips 115-118
FILTER PACK MATERIAL & SIZE	Cemex #2/12
SCREEN SLOT SIZE & LENGTH	0.010-in., 30 ft.
SEALANT PLACEMENT METHOD	Tremie

WELL DESTRUCTION INFORMATION

WELL NUMBER	
WELL DEPTH	
CASING MATERIAL	
SEALANT MATERIAL	
SEALANT PLACEMENT METHOD	

GENERAL CONDITIONS FOR DESTRUCTION:

- 1. A well destruction application must be filed with this Division if a well is being destroyed that is <u>not</u> in conjunction with a test hole permit.
- 2. Destruction procedures must be followed as per UT-50.
- 3. Placement of the seal must be witnessed by a representative of this Division. Forty-eight hour advanced notice is required for an appointment.

GENERAL CONDITIONS FOR ALL PERMITS:

Permit applications may be submitted to the Planning Department by county staff for zoning, access, and flood plain clearances prior to approval of the Environmental Health Division (EHD). If you are drilling within city's limits, you will have to receive approval from their Planning Department.

1. Permit applications must be submitted to EHD at least ten (10) working days prior to the proposed starting date.

Well site approval is required <u>before beginning</u> any work related to water well construction. It is unlawful to continue work
past the stage at which an inspection is required unless inspection is waived or completed.

3. Other required inspections include: setting conductor casing, E-Logs, all seals, and final construction features.

- 4. In areas where a water well penetrates more than one aquifer, and one or more of the aquifers may contain water which is of a quality which may degrade the other aquifer(s) penetrated if allowed to commingle, an E-Log shall be required to determine the location of the confining clay layer(s) and assist in the placement of any required annular seal(s).
- 5. A phone call to the Division Hottine at (661) 862-8788 is required 48 hours before the placement of any seals or plugs.


6. Approval of water quality and final construction features is required before the water well is put into use.

Construction under this permit is subject to any instructions by EHD representatives.


- 8. Any misrepresentation or noncompliance with required permit conditions, or regulations, will result in issuance of a "Stop Work Order."
- A copy of the Department of Water Resources Driller's Report and water quality analyses must be submitted to EHD within sixty (60) days after completion of the work.
- 10. "Dry" holes must be properly destroyed within two (2) weeks of drilling. A water well destruction application must be filed with EHD.
- 11. The permit is void one (1) year after date of issuance if work has not been started and reasonable progress toward completion made. Fees are not refundable or transferable.
- 12. Lead appurtenances shall not be used in construction of any private or public water supply system. The use of solders containing more than 2/10 of 1% lead is prohibited in making joints and fittings in any private or public potable water system.
- 13. Drilling of a water well shall be performed by a C-57 contractor licensed in accordance with the provisions of the Contractors License Law (Chapter 9, Division 3, of the Business and Professions Code) unless exempted by that act, and registered to drill within the County of Kern.
- 14. Permittee shall assume entire responsibility for all activities and uses under this permit and shall indemnify, defend and save the County of Kern and/or Kern County Water Agency, its officers, agents, and employees, free and harmless from any and all expense, cost or liability in connection with or resulting from the exercise of this permit, including, but not limited to, property damage, personal injury, and wrongful death.
- UNDERSTAND THAT FUTURE DEVELOPMENT PERMITS MAY NOT BE ISSUED (KCOC 17.04.120) UNLESS RECORDED LEGAL ACCESS TO THE PROPERTY CAN BE DEMONSTRATED.

I certify that I am the owner of the above-described property, or the authorized representative of such owner, and that all the information I have furnished is current and accurate to the best of my knowledge, and I intend to construct the water well as represented above. I understand that all work is to be done in accordance with Kern County Ordinance Code Chapter 14.08, Bulletin 74-81 and all subsequent bulletins and the conditions of the Permit Application, including any conditions which may be added or changed by EHD upon review of this Application and issuance of the Permit. I further understand that any permit issued pursuant to this application is subject to such further conditions as may be deemed necessary to ensure compliance with the permit regulations.

Owner or Well Driller's Signature Authorized by Full name, title	
By checking this box, I consent to allowing this typewritten sig	mature to serve as a valid substitute for a nandwritten signature
Permit Approved: 12-9-14 Expiration Date:	Total Fee: Date Paid: Receipt #: Cash
Zone:	E-Log Required: Yes No Faxed to KCWA onby
REASONS FOR DENIAL OR	CONDITIONS OF PERMIT:



- Proposed Shallow Monitoring Well Location
- Proposed Deep Monitoring Well Location (to be installed by others)



and Wells

K/J 1365027*00 November 2014

Figure 2



MATTHEW CONSTANTINE DIRECTOR

2700 M STREET, SUITE 300

BAKERSFIELD, CALIFORNIA 93301-2370

VOICE: 661-862-8740

FAX: 661-862-8701

WWW.CO.KERN.CA.US/EH

APPLICATION MUST BE				VELL PERM		ARTING DATE
Mark Type of Permit: x	Construct New	Reconst	truct/Modify	☐ Deep	en	Destroy
1		Type	of Well			
Domestic/Private (1) Domestic (2-4 connection Domestic (5 or more connection)	tions)	Agricultural Test Hole Monitoring		Catho	1 F 1 F 1 F 1	n
1.1-	THE BOXES BELO		1 11 11	PONSIBLE FOR PARTY/FACIL	me 5 12 13	Tarrest and the
Valley Water Mar	THE RESERVE OF THE PERSON OF T	Marine Service Co Co.			1.00 17 40 17 17	MAITON
Address 7500 Meany Ave	Э.	Name Valley Water Management Co. 7500 Meany Ave. NO ADDRESS				
Bakersfield s	cate: Zip i	93308		kersfield	State Ca Z	_{ip} 93308
Phone 661-410-7500	e-mail Bright@vv	water.co	APN 36	TON	295 R 2	9E Sec 24
	Kennedy/Jenks Co		T	Gross Dril	ling and Tes	ina
nvironmental Contractor 303 Second St. S	The second secon	7 T 1 1 1 2 8	Drilling Cor Address	2726 Walnut Ave.		
San Francisco	State Ca	Zip 94107		nal Hill	State Ca	Zlp 90755
contact Mike McLeod	Phone 415	-243-2150	Contact	loanna McKeehan	Option of the P.Z. of the Phys. Rev. 1990	2-427-6899
-mail mikemcleod@ken				ckeehan@greggdri	The state of the s	and the second second
Attach a plot plan with the expodies or courses, drainage Draw a 200' radius circle including: location of tanks, potential within 500' radius of factors.	pattern, roads, exist from well site loo proposed monitoring ility.	well with respecting wells, structucation. For mo	t to the follow res, sewers onitoring well-	or private disposal sy s provide a description	lines, adjoining stems. <u>Inclu</u> on of the facilit	de dimensions y to be monitored
Provide detailed dire From the intersection of I	ctions to site:	and Comanche	Drive, go no	rtheast on Brecking	idae 1.54 mil	es.

Turn north through gate, go north 0.1 miles to base of dam to well site.

WELL CONSTRUCTION INFORMATION

WELL NAME / NUMBER	RTH#6	
MAXIMUM WELL DEPTH	150	
SEALING MATERIAL	Cement	
SEAL DEPTH (HARD ROCK/ UNCONSOLIDATED)	115	
CASING MATERIAL & GAUGE	SCH40 PVC	
CASING - INSIDE DIAMETER	4"	
SCREEN/PERFORATION DEPTH	120-150	
CONDUCTOR DEPTH	N/a	
CONDUCTOR DIAMETER	N/a	
DEPTH TO GROUNDWATER	Unk., <120	
LOCKING WELL CAP	Expanding J-plug	
BOREHOLE DIAMETER	10"	
SCREEN MATERIAL & GAUGE	SCH40 PVC	
TYPE OF BENTONITE PLUG & DEPTH	Med. Bent. Chips 115-118	
FILTER PACK MATERIAL & SIZE	Cemex #2/12	
SCREEN SLOT SIZE & LENGTH	0.010-in., 30 ft.	
SEALANT PLACEMENT METHOD	Tremie	

WELL DESTRUCTION INFORMATION

WELL NUMBER	** 0.5 (())	E AND	
WELL DEPTH			
CASING MATERIAL			
SEALANT MATERIAL			
SEALANT PLACEMENT METHOD			79

GENERAL CONDITIONS FOR DESTRUCTION:

- 1. A well destruction application must be filed with this Division if a well is being destroyed that is <u>not</u> in conjunction with a test hole permit.
- 2. Destruction procedures must be followed as per UT-50.
- 3. Placement of the seal must be witnessed by a representative of this Division. Forty-eight hour advanced notice is required for an appointment.


GENERAL CONDITIONS FOR ALL PERMITS:

Permit applications may be submitted to the Planning Department by county staff for zoning, access, and flood plain clearances prior to approval of the Environmental Health Division (EHD). If you are drilling within city's limits, you will have to receive approval from their Planning Department.

- 1. Permit applications must be submitted to EHD at least ten (10) working days prior to the proposed starting date.
- Well site approval is required <u>before beginning</u> any work related to water well construction. It is unlawful to continue work
 past the stage at which an inspection is required unless inspection is waived or completed.
- Other required inspections include: setting conductor casing, E-Logs, all seals, and final construction features.
- 4. In areas where a water well penetrates more than one aquifer, and one or more of the aquifers may contain water which is of a quality which may degrade the other aquifer(s) penetrated if allowed to commingle, an E-Log shall be required to determine the location of the confining clay layer(s) and assist in the placement of any required annular seal(s).
- A phone call to the Division Hotline at (661) 862-8788 is required 48 hours before the placement of any seals or plugs.
- 6. Approval of water quality and final construction features is required before the water well is put into use.
- 7. Construction under this permit is subject to any instructions by EHD representatives.
- Any misrepresentation or noncompliance with required permit conditions, or regulations, will result in issuance of a "Stop Work Order."
- A copy of the Department of Water Resources Driller's Report and water quality analyses must be submitted to EHD within sixty (60) days after completion of the work.
- "Dry" holes must be properly destroyed within two (2) weeks of drilling. A water well destruction application must be filed with EHD.
- 11. The permit is void one (1) year after date of issuance if work has not been started and reasonable progress toward completion made. Fees are not refundable or transferable.
- 12. Lead appurtenances shall not be used in construction of any private or public water supply system. The use of solders containing more than 2/10 of 1% lead is prohibited in making joints and fittings in any private or public potable water system.
- 13. Drilling of a water well shall be performed by a C-57 contractor licensed in accordance with the provisions of the Contractors License Law (Chapter 9, Division 3, of the Business and Professions Code) unless exempted by that act, and registered to drill within the County of Kern.
- 14. Permittee shall assume entire responsibility for all activities and uses under this permit and shall indemnify, defend and save the County of Kern and/or Kern County Water Agency, its officers, agents, and employees, free and harmless from any and all expense, cost or liability in connection with or resulting from the exercise of this permit, including, but not limited to, property damage, personal injury, and wrongful death.
- ☐ I UNDERSTAND THAT FUTURE DEVELOPMENT PERMITS MAY NOT BE ISSUED (KCOC 17.04.120) UNLESS RECORDED LEGAL ACCESS TO THE PROPERTY CAN BE DEMONSTRATED.

I certify that I am the owner of the above-described property, or the authorized representative of such owner, and that all the information I have furnished is current and accurate to the best of my knowledge, and I intend to construct the water well as represented above. I understand that all work is to be done in accordance with Kern County Ordinance Code Chapter 14.08, Bulletin 74-81 and all subsequent bulletins and the conditions of the Permit Application, including any conditions which may be added or changed by EHD upon review of this Application and issuance of the Permit. I further understand that any permit issued pursuant to this application is subject to such further conditions as may be deemed necessary to ensure compliance with the permit regulations.

necessary to ensure compliance with the permit regulations.	
Owner or Well Driller's Signature Authorized by Full name, title By checking this box, I consent to allowing this typewritten signal	The house of the second
, For intern	al use only
Permit Approved: Date: 12-2-14 Expiration Date:	Total Fee: 750- Date Paid: 11-25-11 Receipt #: DL 1815 Cash Defieck (#) Fee received by: 127
Zone: Flood Plain Approval Required: Yes No	E-Log Required: Yes No Faxed to KCWA on by
REASONS FOR DENIAL OR C	ONDITIONS OF PERMIT:



- Existing Shallow Monitoring Well Location
- Proposed Shallow Monitoring Well Location
- Proposed Deep Monitoring Well Location (to be installed by others)




Race Track Hill Borings and Wells

K/J 1365027*00 November 2014

Figure 2

Feet

Figure 1



Friday, Dec 05, 2014 11:38 AM

2700 "M" Street Bakersfield, CA 93301 (661) 862-8827 (661) 862-8987 Fax

COUNTY OF KERN

State of California
Resource Management Agency
Roads Department

Permit No. 1272 - 14

11/26/2014

ENCROACHMENT PERMIT

VALLEY WATER MANA 7500 MEANY AVE BAKERSFIELD	AGEMENT COMPANY CA 93308	LARRY BRIGHT (661) 410-7500 Phone () Cell () - Fax
In compliance with your reverse side hereof.	request of 11/25/2014 and sub	oject to all the terms, conditions and restrictions contained below and on the
RATED 12" DIAMETER WE EXISTING REGULATIONS GROUND SURFACE, LOC BRECKENRIDGE ROAD A	SO AS NOT TO PRESENT A HAZ ELL MONUMENT AND APPROPI FOR ABANDONING A WELL.TH EATED ALONG THE NORTH SHO	ZZARD, A 4" DIAMETER GROUNDWATER MONITORING WELL WITH TRAFFIC RIATE LOCATION MARKERS. THE WELL SHALL REMOVED AND CAPPED TO HE WELL IS AT AN APPROXIMATE DEPTH BETWEEN 10' AND 100' BELOW DULDER (APPROXIMATELY 5' INSIDE OF THE COUNTY RIGHT OF WAY) OF RTH EAST OF COMANCHE DRIVE. THE WELL WILL BE NEAR THE CREEK.
ROADS DEPARTMENT HA UNDERLYING FEE PROPE	AS THE AUTHORITY TO GRANT.	F ANY OTHER WORK OTHER THAN THAT WHICH THE KERN COUNTY . WHENEVER NECESSARY, PERMITTEE SHALL SECURE PERMISSION FROM START OF ANY AUTHORIZED HEREUNDER. SPECIAL ATTENTION IS THIS PERMIT.
SEE ATTACHED DRAWING	GS FOR DETAILS.	
** YOU MUST NOTIFY T Notify Scott Cunningham	ΓHE INSPECTOR 24 HOURS at (661) 487-2315, 24 hours p	PRIOR TO STARTING WORK OR YOUR PERMIT MAY BE REVOKED ** prior to starting work, for inspection and prior to any backfill.
Department of Transporta Upon Highways), and as Permit not valid for work of Final Inspection Tag may No work to be performed	ation's Manual of Traffic Contro directed by the Roads Departro outside county maintained righ be obtained upon completion. under this permit on Saturday	nt-of-way.
This permit must be on th	ne job site at all times while wo	rk is in progress.
This permit shall be void to	unless the work herein contem	plated shall have been completed before sundown.
Sunday 05/31/2015		
		nce of the work. Failure to so perform said work in accord with nimmediate revocation of this permit and without notice.
		KERN COUNTY ROADS DEPARTMENT

(SUBJECT TO ALL TERMS, CONDITIONS, AND RESTRICTIONS ON THE REVERSE SIDE HEREOF)

YSIDRO LOPEZ

Signature on Application

Signature of Permittee

30111110	LOCATIO	N		Breckenric	dae Ro	ad					Wall Name		RTH#5
ORILLIN	G COMPA		aa Dri	lling and Testing		, uu	DRIL		fuente	e	Well Name	allov V	Vater Management C
ORILLIN	G METHO	D(S)					DRIL	L BIT(S) S	IZE			aney v	
SOLATIO	ON CASIN		w Ster	m Auger - CME 9	15		FROI	И	ith 10-in. au TO	FT.	Project Number _	1	1365027.00
BLANK (CASING			n/a			FROI	<u>n/a</u> м	TO TO	/a FT.	TOC: 810.80 ft. A		TOTAL DEPTH 57.4 ft. bgs
SLOTTE	D CASING		4-inch	SCH 40 PVC			FROI	0.5	27	7.0 FT.	DATE STARTED 12/11/14		DATE COMPLETED 12/11/14
	4-in	ch SC		PVC 0.010-inch s	lotted			27.0	57	7.0	STATIC WATER ELEVATION 777.35 ft. AMS		NORTH 2332160.899
SIZE AN	D TYPE O	FFILIER		mex #2/12			FROI	24.5	то 57	7.4	LOGGED BY M. McLeod		EAST 6319525.753
SEAL		Wyo-l	Ben M	edium Bent. Chip	os		FROI	^M 22.5	то 2 4	FT. I.5	SAMPLING METHODS		WELL COMPLETION
GROUT		3% E	Benton	nite Cement Grou	ıt		FROI	м 3	то 22	FT. 2.5	Continuous coring		SURFACE HOUSING ☐ STAND PIPE
	SAMPLES		Drill	WELL CONST			USCS				CAMPLE DECORIDE	ON F	
Type & No.	Recovery (Feet)	Resist. Blows/6"	Depth (Feet)	well enclosure			Log	Lithology	Color		SAMPLE DESCRIPTION		
	5		- - - 5-				SW		10YR 7/4	OVEF	<u>- GRADED SAND (SV</u> RALL, <~5% GRAVEL,), ~20% MEDIUM GRANED SAND, DRY	, ~10%	COARSE GRAINED
	2		10 -	Bentonite- – Cement Grout			sw		10YR 6/3 10YR 8/1	BROV GRAV MEDI	/EL, ~20% COARSE (ABUND GRAINI ~30%	ANT WHITE, ~10-20% ED SAND, ~20-30% FINE GRAINED SAND,
	2		- - -	Plant Occion			sw	ø'. Ø	10YR 6/4	- BROV), ~10-20% MEDIUM (, <~109 GRAINI	HT YELLOWISH % COARSE GRAINED ED SAND, ~70% FINE ND CONSOLIDATED,
'	No		15 - -	Blank Casing —			GW			- VIOLE		RAVE	RING RATTLES L IN CUTTINGS. DRILL CKY TO 17 FT. AND LESS
	Core 2		20-							OVEF GRAN MEDI SAND	_ GRADED SAND (SV RALL WITH BROWNIS /EL, <~10% COARSE UM GRAINED SAND, D, VERY DENSE AND IORIZONTAL BROWN	SH YEL GRAIN ~10-20 CONS	LOW STREAKS, TRACE NED SAND, ~60-70% D% FINE GRAINED OLIDATED, DRY,
	No Core		- - 25 -	Bentonite Seal -					10YR 7/3-7/4	- - -			
	1		-	Filter Pack -			SW		10YR 6/8		/EL INCREASES TO A ETER	~10-20¹	%, UP TO 2.5-INCHES
	1.5		30 -	Slotted Screen - DTW:33.45 ft TOC, 12/21/14						- -			

	Name	V	alley V	Vater Management Co.	_ Pı	oject N	lumber		1365027.00 Well NameRTH#5
ype No.	Recovery (Feet)	Penetr. Resist. Blows/6"	Drill Depth (Feet)	WELL CONSTRUCTION		USCS Log	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
	2		_	First Encountered	-				GRAVELLY WELL GRADED SAND (SW) YELLOW OVERALL WITH BROWNISH YELLOW STREAKS, ~20% GRAVEL TO 2-INCHES, ~10%-20% COARSE GRAINED
	No Core		- - 40 <i>-</i>	Water	- - -				SAND, ~70% FINE GRAINED SAND, VERY DENSE, MOIST, ABUNDANT COARSE FELDSPAR AND QUARTZ
	1		-		- -			10YR	41 FT. MATERIAL IS WET. WATER LEVEL MEASURED A APPX. 37 FT.
_	No Core		- - 45 -	Filter Pack	- - - -			7/6 10YR 6/8	MATERIAL IS DENSE AND GRAVELLY-CANNOT PENETRATE WITH SAMPLE BARREL SO START ALTERNATING CORING/NON CORING RUNS
	No Core		-			SW			- - -
	1.5		50 - -	Slotted Screen	- -				50 FT. COLOR CHANGES TO BROWNISH YELLOW
_	No Core		- - 55 -					10YR 6/8	
	No Core		_ _		- -				57 FT. AUGER REFUSAL

NOTES

- 1. ALL CONTACTS APPROXIMATE
- 2. BGS: BELOW GROUND SURFACE
- 3. COLOR DESIGNATION IN ACCORDANCE WITH THE MUNSELL SOIL COLOR CHARTS (KOLLMORGEN INSTRUMENTS CORPORATION, 1990)
- 4. SOIL CLASSIFIED IN ACCORDANCE WITH THE UNIFIED SOIL CLASSIFICATION SYSTEM, ASTM D-2488-93

BORING & WELL CONSTRUCTION 1365027.00.GPJ KENNEDY JENKS.GDT 4/3/15

HOD(S) Hollo SING G ING -inch SC E OF FILTER	4-inch S CH 40 PV CPACK Cem Ben Me	ing and Testing Auger - CME 9 n/a SCH 40 PVC VC 0.010-inch s nex #2/12 dium Bent. Chip te Cement Grou WELL CONSTI Stand pipe Well cap	slotted ps it ruction	FI FI FI	RILL BIT(S) S Reamed v ROM n/a ROM +2.1 ROM 113.5 ROM 111.0 ROM 107.8 ROM 1 CS Litheless	TO n/3 TO 113 TO 143 TO 145 TO 107	B.5 FT. B.5.0 FT. B.7.0 FT. B.7.0 FT.	Project Name Valley Val	1365027.00 TOTAL DEPTH
SING ING ING INCH SC OF FILTER Wyo- 3% E ES very Penetr. Resist. Blows/6"	4-inch S CH 40 P R PACK Cem Ben Me Bentonit Drill Depth (Feet)	n/a SCH 40 PVC VC 0.010-inch s nex #2/12 dium Bent. Chip te Cement Grou WELL CONSTI	ps It	FI FI FI USG	ROM	TO n/s TO 113 TO 143 TO 145 TO 111 TO 107	B.5 FT. B.5 FT. B.5 FT. FT. FT. FT. FT. FT. FT. FT.	ELEVATION AND DATUM TOC: 1059.82 ft. AMSL DATE STARTED 12/8/14 STATIC WATER ELEVATION 939.51 ft. AMSL LOGGED BY M. MCLeod SAMPLING METHODS Continuous coring	TOTAL DEPTH 145.0 ft. bgs DATE COMPLETED 12/10/14 NORTH 2328430.428 EAST 6316629.347 WELL COMPLETION SURFACE HOUSING STAND PIPE 3
Wyo- 3% E ES Penetr. Resist. Blows/6"	CH 40 PY R PACK Cem Ben Me Bentonit Drill Depth (Feet)	SCH 40 PVC VC 0.010-inch s nex #2/12 edium Bent. Chip te Cement Grou WELL CONSTI	ps it ruction	FI FI FI USG	n/a ROM +2.1 ROM 113.5 ROM 111.0 ROM 107.8 ROM 1 CS Litheless	n/a TO 113 TO 143 TO 145 TO 107	B.5 FT. B.5 FT. B.0 FT. FT. FT. FT. FT.	TOC: 1059.82 ft. AMSL DATE STARTED 12/8/14 STATIC WATER ELEVATION 939.51 ft. AMSL LOGGED BY M. MCLeod SAMPLING METHODS Continuous coring	145.0 ft. bgs DATE COMPLETED 12/10/14 NORTH 2328430.428 EAST 6316629.347 WELL COMPLETION SURFACE HOUSING STAND PIPE 3
Wyo- 3% E ES Penetr. Resist. Blows/6"	CH 40 PY R PACK Cem Ben Me Bentonit Drill Depth (Feet)	VC 0.010-inch s nex #2/12 dium Bent. Chip te Cement Grou WELL CONSTI Stand pipe	ps it ruction	FI FI USG	+2.1 ROM 113.5 ROM 111.0 ROM 107.8 ROM 1 CS Litheless	113 TO 145 TO 111 TO 107	3.5 FT. 3.5 FT. 5.0 FT. 1.0 FT.	DATE STARTED 12/8/14 STATIC WATER ELEVATION 939.51 ft. AMSL LOGGED BY M. McLeod SAMPLING METHODS Continuous coring	DATE COMPLETED 12/10/14 NORTH 2328430.428 EAST 6316629.347 WELL COMPLETION SURFACE HOUSING STAND PIPE 3
Wyo- 3% E ES Penetr. Resist. Blows/6"	CH 40 PY R PACK Cem Ben Me Bentonit Drill Depth (Feet)	VC 0.010-inch s nex #2/12 dium Bent. Chip te Cement Grou WELL CONSTI Stand pipe	ps it ruction	FI FI USG	113.5 ROM 111.0 ROM 107.8 ROM 1 CS Lithology	143 TO 145 TO 111 TO 107	5.0 FT. I.0 FT.	STATIC WATER ELEVATION 939.51 ft. AMSL LOGGED BY M. MCLeod SAMPLING METHODS Continuous coring	PORTH 2328430.428 EAST 6316629.347 WELL COMPLETION SURFACE HOUSING STAND PIPE 3
Wyo- 3% E ES very Penetr. Resist. Blows/6"	Ben Me Bentonit Drill Depth (Feet)	nex #2/12 dium Bent. Chip te Cement Grou WELL CONSTI Stand pipe	ps it ruction	FI	111.0 ROM 107.8 ROM 1 CS Litteless	145 TO 111 TO 107	FT. FT. I.0	LOGGED BY M. McLeod SAMPLING METHODS Continuous coring	6316629.347 WELL COMPLETION SURFACE HOUSING STAND PIPE 3
3% E ES very Penetr. Resist. Blows/6"	Ben Me Bentonit	te Cement Grou WELL CONSTI	I t	FI	107.8 ROM 1	TO 111	FT. FT.	M. McLeod SAMPLING METHODS Continuous coring	6316629.347 WELL COMPLETION □ SURFACE HOUSING □ STAND PIPE 3
3% E ES very Penetr. Resist. Blows/6"	Bentonii Drill Depth (Feet)	te Cement Grou WELL CONSTI	I t	FI	107.8 ROM 1	111 TO 107	FT.	Continuous coring	☐ SURFACE HOUSING ☑ STAND PIPE
very Penetr. Resist. Blows/6"	- Drill Depth (Feet)	WELL CONSTI	RUCTION	USO	CS Litheless	107			⊠ STAND PIPE
very Penetr. Resist. Blows/6"	Depth (Feet)	Stand pipe ——				Color		SAMPLE DESCRIPTION and I	ORILLING REMARKS
et) Resist. Blows/6"	(Feet)			Lo		3			D. (122.110) (2.11) (1 (10
;	- - - - 5-			-		1			
				 	M	10YR = 5/4	COAF SAND	<u>(SAND (SM)</u> YELLOWISH E RSE GRAINED SAND, ~10-2), ~60-70% FINE GRAINED : PLASTIC FINES, DRY	20% MEDIUM GRAINED
	10-			- SV	N	10YR 7/3	OVEF MEDI	L GRADED SAND (SW) VER RALL, ~10-20% COARSE GR UM GRAINED SAND, ~70% DENSE AND CONSOLIDA	RAINED SAND, ~20% FINE GRAINED SAND,
i	- - -			M	L	2.5Y = 6/3	OVER NON- FRIAE	RALL, ~20-30% FINE GRAIN PLASTIC FINES, CEMENTE BLE; BREAKS INTO SUBHO	IED SAND, ~70% ED, BRITTLE, AND PRIZONTAL CHIPS
	15-	Bentonite- — Cement Grout		_ MI	L (2.5Y 5/4 _ 10YR 8/1 _	- ~40% SAND OLIVE	COARSE GRAINED SAND WHITE FELDSPAR AND Q BROWN SILT MATRIX, VE	TO MEDIUM GRAINED QUARTZ; ~60% LIGHT
	20-	Blank Casing —		-		- 10YR -	BROW ~20% WHIT SOME	WN OVERALL WITH YELLO GRAVEL, ~20% COARSE (E FELDSPAR), ~30% MEDI E MICAS), ~30% FINE GRAI	WISH BROWN STREAKS GRAINED SAND (MAINLY UM GRAINED SAND (INC
;	25-			SV		6/3 10YR 5/8	- 23 FT -	. SOME SUBHORIZONTAL	COLOR BANDING
				SM	V	2.5Y 6/3 _	- YELL	OWISH BROWN BANDING,	~80% FINE GRAINED
5	30 -			- - - - - - - - - - - - -	N	10YR 6/3 10YR 5/8	- BROV ~20% - WHIT _ SOME	WN OVERALL WITH YELLO GRAVEL, ~20% COARSE (E FELDSPAR), ~30% MEDI E MICAS), ~30% FINE GRAI	WISH BROWN STREAKS GRAINED SAND (MAINLY UM GRAINED SAND (INC
		20-	15 - Bentonite-Cement Grout 20 - Blank Casing -	15 - Bentonite-Cement Grout 20 - Blank Casing 25	Bentonite-Cement Grout M 20 - Blank Casing - SN 30 - SN	Bentonite-Cement Grout Blank Casing SW SM SW SW SW	20 - Blank Casing - ML 2.5Y 5/4 10YR 8/1 255 - SW 25 -	## Denting	Bentonite-Cement Grout ML 2.5Y 5/4 ML 2.5Y 5/4 10YR 8/1 2.5Y 5/4

F-40.1 (6-87) (3-88) (8-90)

oject	Name	V	alley W	ater Manageme	nt Co.	P	Project N	Number		1365027.00 Well Name RTH#6
S/ Type & No.	Recovery (Feet)	Penetr. Resist.	Drill Depth (Feet)	WELL CONSTR	RUCTION		USCS Log	Lithology	Color	SAMPLE DESCRIPTION and DRILLING REMARKS
	4	Blows/6"	-				- SM		2.5Y 6/3	SILTY SAND (SM) LIGHT YELLOWISH BROWN AND WHITE, ~15% WHITE MEDIUM GRAINED SAND FELDSPAR, ~70% LIGHT YELLOWISH BROWN FINE GRAINED SAND, ~15% NON-PLASTIC FINES, MOIST?
ŀ	5		40 -				SW		10YR 6/3 10YR 5/8	WELL GRADED SAND WITH GRAVEL (SW) PALE BROWN OVERALL WITH YELLOWISH BROWN STREAK ~20% GRAVEL, ~20% COARSE GRAINED SAND (MAINL) WHITE FELDSPAR), ~30% MEDIUM GRAINED SAND (IN SOME MICAS), ~30% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
			45 -				SM		2.5Y 6/3 	SAND INC. MICA, ~20% SILT AND SOME CLAY, VERY \STIFF/DENSE, NO TO LOW PLASTICITY
	5		-				 		2.5Y 6/3	SILTY SAND (SM) LIGHT OLIVE BROWN AND WHITE, ~80% FINE GRAINED SAND INC. MICA, ~20% \ NON-PLASTIC FINES, BRITTLE AND BREAKS INTO \SUBHORIZONTAL CHIPS
Į			50-						2.5Y 5/3	SANDY SILT (ML) LIGHT YELLOWISH BROWN OVERALL, ~10% SCATTERED WHITE MEDIUM GRAINEI SAND, ~20-30% SCATTERED FINE GRAINED SAND, ~60% NON-PLASTIC FINES AND POSS. CLAY, VERY STIFF, NO PLASTICITY, DRY
	4.5						ML - - ML		2.5Y6/8 2.5Y 6/3	SILT TO SANDY SILT (ML) LIGHT OLIVE BROWN OVERALL, ~5-10% FINE GRAINED SAND, ~80-90% SILT VERY STIFF AND BRITTLE 52 FT 54 FT. COLOR INCLUDES OLIVE YELLOW
	4.5		55 - - -	Bentonite- — Cement Grout			SM		2.5Y 6/2 2.5Y 7/2	SANDY SILT (ML) LIGHT YELLOWISH BROWN OVERALL, ~10-20% SCATTERED WHITE AND BLACK MEDIUM GRAINED SAND, ~80% NON-PLASTIC FINES, VERY STIFF, NO PLASTICITY
			60-	Blank Casing —			sw		2.5Y 6/2	SILTY SAND (SM) LIGHT BROWNISH GRAY TO LIGHT BROWN, ~60% FINE GRAINED SAND INC. MICAS, ~40-20% NON-PLASTIC FINES, MOIST TO DRY WELL GRADED SAND (SW) LIGHT BROWNISH GRAY
	4		-	Ü			<u> </u>			OVERALL, ~20% COARSE GRAINED SAND, ~40% MEDIUM GRAINED SAND, ~40% FINE GRAINED SAND, VERY DENSE, DRY SILTY SAND (SM) LIGHT OLIVE BROWN AND WHITE,
			65-				SM		5/3	~40% WHITE COARSE GRAINED SAND - MEDIUM GRAINED SAND FELSPAR AND QUARTZ; ~60% LIGHT OLIVE BROWN FINE GRAINED SAND AND NON-PLASTI FINES
	3.5		_ _ _ _				_ _ _ _		2.5Y 7/2	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH OLIVE YELLOW STAINS AND BLACK AND WHITE GRAINS, ~10% GRAVEL, ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
	3.5		70 -				- sw		2.5Y 5/8 10YR 8/1	- - -
			75-						2.5Y 6/3	SILTY SAND (SM) LIGHT YELLOWISH BROWN OVERALL WITH SOME SUBHORIZONTAL BANDING ANI OLIVE YELLOW STAINING, ~80-90% FINE GRAINED SAND, ~10-20% NON-PLASTIC FINES
	5		-				SM		2.5Y 6/8 — — — 2.5Y 5/3	

Project	Name	V	alley V	Vater Management	Co.	Proje	ct Number	' <u>-</u>	1365027.00 Well Name RTH#6
Type & No.	AMPLES Recovery	Penetr. Resist.	Drill Depth (Feet)	WELL CONSTRU	CTION		SCS Litholog	y Color	SAMPLE DESCRIPTION and DRILLING REMARKS
& No.	(Feet)	Blows/6"	(reel)					*\ •\ &	\ ~40% WHITE COARSE GRAINED SAND - MEDIUM -\ GRAINED SAND FELDSPAR AND QUARTZ; ~60% LIGHT
	4		-						OLIVE BROWN FINE GRAINED SAND AND NON-PLASTIC
			-			s	w kini	2.5Y 7/2	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH OLIVE YELLOW STAINS AND BLACK AND WHITE GRAINS, ~10% GRAVEL, ~20% COARSE
			85-					2.5Y 5/8	GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND
	3]			-		8/1	CONSOLIDATED SILTY SAND (SM) GRAYISH BROWN AND WHITE, ~20%
			-			s	SM	2.5Y 5/2	WHITE COARSE GRAINED SAND - MEDIUM GRAINED SAND FELDSPAR AND QUARTZ; ~40-60% GRAYISH BROWN FINE GRAINED SAND AND ~40% GRAYISH
			90 –	Bentonite- Cement Grout				8	BROWN NON-PLASTIC FINES WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, ~10% GRAVEL
_	4		4					2.5Y	 ~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED
			95-	Plank Casing		s	w !::::::	10YR 8/1	
			907	Blank Casing —				% &	
_	4.5		1						SILTY SAND (SM) GRAYISH BROWN OVERALL, TRACE
			100-			s	SM PROPERTY OF THE PARTY OF THE	2.5Y 5/2	COARSE GRAINED SAND, ~10-20% MEDIUM GRAINED SAND, ~70% FINE GRAINED SAND, ~20% NON-PLASTIC FINES, VERY DENSE, DRY
			-			+-		<u>.</u>	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, <10% GRAVEL
	4		-					\$	~20% COARSE GRAINED SAND, ~60% MEDIUM GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY
			105-					6	DENSE AND CONSOLIDATED
			-					6 8	_
Ī	4		-			s	W	2.5Y 7/2	_
			110	Bentonite Seal —	-			ଁ 8/1 ଚ	_
			=	Eiltor Dook					
	3		-	Filter Pack ——				* 	_
			115-	Slotted Screen					
	3		+					2.5Y 6/2	BROWNISH GRAY OVERALL, TRACE GRAVEL, TRACE
									COARSE GRAINED SAND, ~10-20 MEDIUM GRAINED SAND, ~70% FINE GRAINED SAND, ~10% NON-PLASTIC FINES, VERY DENSE, DRY
			120	DTW: 120.31 ft. TOC, 12/22/14			:	2.5Y 7/2	WELL GRADED SAND WITH GRAVEL (SW) LIGHT GRAY WITH BLACK AND WHITE GRAINS, ~10% GRAVEL ~20% COARSE GRAINED SAND, ~60% MEDIUM
	1			First Encountered				8/1	GRAINED SAND, ~10-20% FINE GRAINED SAND, VERY DENSE AND CONSOLIDATED 120-125 FT. DRILL WITHOUT SAMPLING DUE TO
]	First Encountered = Water				0	DENSITY AND GRAVEL BLOCKAGE 125 FT. AFTER LUNCH BREAK SOUND WATER LEVEL A

Project	Project Name Valley Water Management Co. Project Number 1365027.00 Well Name RTH#6											
Type & No.	Recovery (Feet)	Penetr. Resist. Blows/6"	Drill Depth (Feet)	WELL CONSTRUCTION	US	USCS Log Lithology		Color	SAMPLE DESCRIPTION and DRILLING REMARKS			
-			-		-				WELL GRADED SAND WITH GRAVEL CONT'D			
- - [3		-		_				125-130 FT. SAMPLER BARREL IS WET			
- 			130-		-			2.5Y	- -			
- - -	3		-					7/2 10YR 8/1	- - -			
- ■			135	Filter Pack	_ s	SW			135-140 FT. DRILL WITHOUT SAMPLING DUE TO DENSITY AND GRAVEL BLOCKAGE			
- -	No core		-		_				- -			
 			140-	Slotted Screen	-			2.5Y 6/2	140 FT. COLOR CHANGES TO LIGHT BROWNISH GRAY WITH WHITE AND BLACK GRAINS			
- -	3		-					10YR 8/1	- -			

NOTES

- 1. ALL CONTACTS APPROXIMATE
- 2. BGS: BELOW GROUND SURFACE
- 3. COLOR DESIGNATION IN ACCORDANCE WITH THE MUNSELL SOIL COLOR CHARTS (KOLLMORGEN INSTRUMENTS CORPORATION, 1990)
- 4. SOIL CLASSIFIED IN ACCORDANCE WITH THE UNIFIED SOIL CLASSIFICATION SYSTEM, ASTM D-2488-93

BORING & WELL CONSTRUCTION 1365027.00.GPJ KENNEDY JENKS.GDT 6/15/15

Appendix B-2

Monitoring Well Development Logs

MONITORING WELL DEVELOPMENT LOG



		Page of
All measurements taken from: Top of Ca	asing Protective Casing Ground Level	Sample ID
DT1/11/		Qty. of Drilling Fluid Lost
Well Number PTH #6	Borehole Diameter	Minimum Gal. to be Purged 170.62
Date DECEMBER 15-14	Screen Length	Development Method BATU - SUAB - BATU
Time Start:	Measured Depth (pre-development)\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	PUMP.
Client KENNEDY JENKS	Measured Depth (post-development)	Purging Equipment Z' GNOWFOS
Project PACK TRACK HIN SI	Le Static Water Level (ft.) 120. 16	Water Level Equipment <u>Reck</u>
Job Number	Standing Water Column (ft.) 26.25	pH/EC Meter HORIBA U-10
Installation Date	One Well Volume (gal.)	Turbidity Meter//
Well Diameter 4" SCH40.	One Annulus Vol. (gal.)	Other

Field Parameters Measured												
Amount	EC	pН	Temp.	Turbidity	D.O.	SAL.	GPM	Comments	Field Tech.			
Purged (gal)	MS/CM		C	NTU		/.	W.L.	Bail Suge				
175	492	7.14	24.0	999	6.16	0.24	127.	twice well is	Very			
195	4.29	7.13	23.6	999	6.33	0.21	2.0/137	· Sensitive, C	olor Grey			
215	5.14	7.29	24.3	999	5-12	0.26	1.0 / Dum) sutake) of	water			
2.25	5.03	7.23	24-4	810	5.38	0.26	1.0% W					
232	4.74	7.21	24.9	310	5.82	0.25	0.5/11					
238	4-72	7.20	24.9	175	5.77	0.24	11/11					
243	4-68	7.19	25-0	55	5.73	0.24	11/4	***				
248	4.68	7-20	25.1	15	5-71	0.24	11/11	36.				
254	4.68	7.19	25.2	5	5.73	0.24	11/11					
			Fina	l Field Parame	eter Measuremo	ents	,					
259	4.68	7-19	25.2	4	5.70	0.24	11/11					
	Purged (gal) 175 195 215 225 232 238 243 248 254	Purged (gal) MS/CM 175	Purged (gal) MS/CM 175	Amount Purged (gal) MS/CM C 175	Amount EC pH Temp. Turbidity Purged (gal) MS/CM C NTV 175	Amount EC pH Temp. Turbidity D.O. Purged (gal) MS/CM C NTV 175	Amount BC pH Temp. Turbidity D.O. SAL. Purged (gal) MS/CM C NTV 175 492 7.14 24.0 999 6.16 0.24 195 429 7.13 23.6 999 6.33 0.21 215 5.14 7.29 24.3 999 5.12 0.26 2.25 5.03 7.23 24.4 810 5.38 0.26 2.32 4.74 7.21 24.9 310 5.82 0.25 2.38 4.72 7.20 24.9 175 5.77 0.24 2.43 4.68 7.19 25.0 55 5.73 0.26 2.44 4.68 7.19 25.2 5 5.73 0.24 2.54 4.68 7.19 25.2 5 5.73 0.24 2.54 4.68 7.19 25.2 5 5.73 0.24 Final Field Parameter Measurements	Amount EC pH Temp. Turbidity D.O. SAL. GPM Purged (gal) MS/CM C NTU W.L. 175	Amount EC pH Temp. Turbidity D.O. SAL. GPM Comments Purged (gal) MS/CM C NTU W.L. Bail Surge 175 492 7.14 24.0 999 6.16 0.24 /27 twice Will 18 195 429 7.13 23.6 999 6.33 0.21 2.0/37 Sensitul (195 1.15 5.14 7.29 24.3 999 5.12 0.26 1.0/Dump (wtake) of 2.25 5.03 7.23 24.4 810 5.38 0.26 1.0/Dump (wtake) of 2.32 4.74 7.21 24.9 310 5.82 0.25 0.5/11 238 4.74 7.20 24.9 175 5.77 0.24 11/11 243 4.68 7.19 25.0 55 5.73 0.24 11/11 248 4.68 7.20 25.1 [5 5.71 0.24 11/11 254 4.68 7.20 25.1 [5 5.71 0.24 11/11 254 4.68 7.20 25.1 [5 5.73 0.24 11/11			

MONITORING WELL DEVELOPMENT LOG



Page of												
51-12												
-SWAB												
EDYFLOW Z												
K												
← U-10.												
AU-10												
Well Diameter One Annulus Vol. (gal.) Other												
-												
Field Tech.												
ell												
Surge D.A.												
Bail												
V												
S												

Appendix B-3

Survey Report

VALLEY WATER MANAGEMENT GROUNDWATER MONITORING WELLS RACETRACK HILL SECTION 24 29/29

WELL	<u>ELEV</u>	<u>DESC</u>	<u>DATUM</u>	<u>NORTHING</u>	<u>EASTING</u>
RTH#5	810.80	TOP PVC CASING	NAD83	2332160.8990	6319525.7530
	811.30	TOP MON RIM			
RTH#6	1059.82	TOP PVC CASING	NAD83	2328430.4280	6316629.3470
	1057.71	TOP WELL PAD			

BENCHMARK:

NGS MONUMENT BRASS CAP - PID "FU0159"

1991 ELEV = 785.40

HORIZONTAL DATUM NAD83, ZONE 5

PREPARED BY: DEE JASPAR & ASSOCIATES, INC. DATE OF SURVEY: December 22, 2014

GLOBAL_ID FIELD_PT_NAME	FIELD_PT_CLASS	XY_SURVEY_DATE	LATITUDE	LONGITUDE	XY_METHOD	XY_DATUM :	XY_ACC_VAL	XY_SURVEY_ORG	GPS_EQUIP_TYPE	XY_SURVEY_DESC	EFFECTIVE_DATE
RTH#5	MW	12/22/2013	35.23526153	-118.4844484	CGPS	NAD83	20	DEE JASPAR RCE, PE23042	EP25	SPECTRA PRECISION EPOCH 35	
RTH#6	WW	12/22/2013	35.23157424	-118.4919455	CGPS	NAD83	20	DEE JASPAR RCE, PE23042	EP25	SPECTRA PRECISION EPOCH 35	

GLOBAL_ID	FIELD_PT_NAME	ELEV_SURVEY_DATE	ELEVATION	ELEV_METHOD	ELEV_DATUM	ELEV_ACC_VAL	ELEV_SURVEY_ORG	RISER_HT	ELEV_DESC	EFFECTIVE_DATE
	RTH#5	12/22/2013	810.80	CGPS	88	3	DEE JASPAR RCE, PE23042		NGS BRASS CAP PID "FU0159" 1991 ELEV=785.4	
	RTH#6	12/22/2013	1059.82	CGPS	88	3	DEE JASPAR RCE, PE23042	2.11	NGS BRASS CAP PID "FU0159" 1991 ELEV=785.4	

Appendix B-4

Monitoring Well Purge Forms

8			Well N	/lonitori	ng Data	Sheet	300		
Project # \				Client:	Jalley L	Natur 1	Maragi me	t	j
Sampler	2 Privio	(Start Date:	121	22/14		×	
	RTH &			Well Diam	eter 2	3 4	6 8 Oth		
Total Well D	epth:			Depth to V	later: Pre:	120.31	Post: 12776	120.42 @	Sonoling
Depth to Fre	ee Product:			thickness o	of Free Proc	luct: (feet):			
Reference to	0:	PVC	Grade	Flow Cell 7	уре:				!
Purge Metho	od:	2"Grundfo	s Pump	Peristalitic	Pump	Bladder Pu	mp Oth	er:	
Sample Met		Dedicated		New Tubin		sable Bailei	s Oth	er:	W.
Flow Rate:				Pump Dep	th:				-
Well	Γ		I			Multiplier	for		
Volume Calculation (Fill in	Total Depth (ft)		Depth to Water (ft)	= -	Water Column (ft)	Casing Dia (in) 2 4	meter	asing Volume (gal)	
Before Purging)	143.5		130,31		23.19	0.16 0.64		4, 84	5
1405	Temp		Cond.	Turbiditiy	D.O.	ORP	Water Remove	d	ie:
Time	(2° or °F)	pH *	(mS or uS)	(NTUs)	((mg/l)	(mV)	(gals. or mL)	Observations	
1410	22.96	01.10	5337	12.6	7.10	30,0	2-5	121.8	:3
1412	393	7.07	53 ft	13.6	17.3	C 1:-1	4.5	121.95	
1438	24.68	153	2336	202	6.55	45.7	9.0	132.63	
1434	24.45	701	5387	34.6	6.31	42.8	14.0	193.50	
MAA.	25.33	YCT	YOY	33.2	40.0	0.0	19,0	123 60	
1468	25.4Y	28.1	5375	Woil	590	E.04	24.0	12388	. 19
1206	2494	637	2111	792	6.31	0,04	29,0	134.29	
9131	23.45	6,45	5109	4.17	6.35	P. ap	34.0	12620	
1626	23.64	6.95	20 PA	87.7	15.3	0.10	39.0	127.15	
1537	2343	651	4224	107.7	6.39	41.7	44.0	127.76	
		14.							=2
								1	
Did well dew	ater?	Yès	No	Amount ac	tually evacu	ated:			
Sampling Tir	ne: 🔿 省	30		Sampling D	Date: 17	123/14			
Sample I.D.:	RTHA	6-12	1314	Laboratory:	BC 1	abs			
Analyzed for		TPHg	BTEX	MTBE	TPHd	OTHER:			
Equipment B	lank I.D.		② Time	Duplicate I	D.a)96	

				Monitorii	ng Data	Sheet	Ver				
Project #	13650	5		Client:	dalle 1	Water 1	March	mer	+		
Sampler	R. PILL	ļu .	-	Start Date:	12/3	4/14	0	BOX	, 		
Well I.D.				Well Diam	eter 2	3 4	6 80	Other	Γ. Al		
Total Well D				Depth to Water: Pre: 33.45 Post: 35,91							
Depth to Fre	ee Product:			thickness o	of Free Prod	luct: (feet):	ii .				
Reference to	o:	PVC	Grade	Flow Cell Type: 451 6920							
Purge Metho	od:	2"Grundfo	s Pump	Peristalitic Pump Bladder Pump Other:							
Sample Met	hod:	Dedicated	Tubing	New Tubing Disposable Bailers Other:							
Flow Rate:	w:		•	Pump Depth:							
Well Volume Calculation (Fill in Before Purging)	Total Depth (ft)		Depth to Water (ft)	= ×	Water Column (ft)	Multiplier Casing Dia (in) 2 4 0.16 0.64	Diameter n) Casing Vo (gal)				
1350	Temp		Cond.	Turbiditiy	D.O.	ORP	Water Remo	ved	E 74		
Time	(°C or °F)	pН	(mS or us)	(NTUs)	((mg/l)	(mV)	(gals.)or m	L)	Observations		
1355	24.31	7,39	670	57	221	72.5	2.5		3/28		
1405	24.48	7.42	673	39.2	2.14	61.4	7.5				
6141	24.12	7.39	661	3.7	2.05	44.7	12.5		35,67		
1415	24.17	137	655	112	1,97	39,0	22.5	* 1	35.95		
1420.	24.18	7.36	653	3.5	1,92	38.3	32.5		14,02		
1427	24.16	7:34	600	7.7	1,99	36.8	44,5		35,92		
*					10						
) 			9		
Did well dew	ater?	Yes	N9	Amount ac	tually evacu	Water Street					
Sampling Tir	ne: 14	30		Sampling D	Date: 12	121/14					
Sample I.D.:	RIH	×5-12	2114	Laboratory	BC	Labs					
Analyzed for		TPHg	BTEX	MTBE TPHd OTHER:							
Equipment B	lank I.D.:		@ Time	Duplicate I.D.							

			Well	Monitorir	ng Data	Sheet			
Project #	13650	27 40)ဂ ႏ	Client:	Dalley 1	Date	Marajen	iert	
Sampler	Ren			Start Date:	12	12/14	9, -		
1.	RTH &			Well Diam	eler 2	3 (4	6 8 Oth	ner:	
Total Well D	epth:			Depth to V	Vater: Pre:	84,41	Post: 9116	5 4750	e
Depth to Fre	e Product:			thickness o	of Free Proc	luct: (feet):	4	Som	Bling
Reference to	o:	PVC	Grade	Flow Cell 7	Гуре: 🧡	51 6	920	•	-
Purge Metho	od:	2 Grundfo	s Pump	Peristalitic	Pump ,	Bladder Pu	mp Oth	ner:	
Sample Met	hod:	Dedicated	Tubing	New Tubin	g Dispo	osable Bailer	rs Oth	ner:	* **
Flow Rate:	955		-	Pump Dep	th:			2 2	
e * [232						, - 1 1	we was	
Well Volume Calculation (Fill in	Total Depth (ft)	5' 2 5 5	Depth to Water (ft)	a 15	Water Column (ft)	Multiplier Casing Dia (in) 2 4	meter (29.77 Casing Volume (gal)	
Before Purging)	99.92		14.48		15.51	0.16 0.64	1.44	1,92	
0750	·Temp		Cond.	Turbiditiy	D.O.	ORP	Water Remove	ed	
Time	(% or °F)	рН	(mS or us)	(NTUs)	((mg/l)	(mV)	(gals. or mL)	Observations	ļ
~ care	23.59	70,0x	6340	4.7	27.0	0.11	50	44.12	
0812	2325	7,04	6318	55 2	1,02	54.1	100	89,45	
0820	2324	703	4250	905	1.22	32.2	15,0	9071	
0830	23.33	10;0	6400	7,101	1.42	32.1	300	91.23	
OFYC.	2340	701	6494	43.4	1.78	34.6	260	91.53	
0380	33.46	6.98	U515	CYD	1,84	36.0	300	91,65	4
*									
	3								
	# = #								
		*							=
	•					10			
Did well dew	ater?	Yès (No	Amount ac	tually evacu	ıated:			
Sampling Tir	me: 09	05	\sim	Sampling [Date	12/22	-114		
Sample I.D.:	^	×4		Laboratory	BC	Labo	W 9		
Analyzed for		TPHg	BTEX	МТВЕ	TPHd	OTHER:			
Equipment B			@ Time	Duplicate I	.D.			8	

			Well N	/lonitorir	ng Data	Sheet					
Project #	136500	7 4 00		Client:	Valley	Water	- Mayo	3511	mont		
Sampler	D. ?(1)		18.0	Start Date:	-	22/14					
Well I.D.				Well Diam	eter 2	3 4	6 8	Olhe			
Total Well D	Depth: \o	4.50		Depth to Water: Pre: \$7,31 Post:							
Depth to Fre				thickness o	of Free Proc	luct: (feet):	71		,		
Reference to	o:	PVC	Grade	Flow Cell Type: 441 6920							
Purge Metho	od:	2"Grundfo	s Pump	Peristalitic Pump Bladder Pump Other:							
Sample Met	hod:	Dedicated	Tubing	New Tubing Disposable Bailers Other:							
Flow Rate:	,		=:	Pump Dep	Pump Depth:						
Well Volume Calculation (Fill in Before Purging)	Total Depth (ft)		Depth to Water (ft)	я	Water Column (ft)	Multiplier Casing Dia (in) 2 4 0.16 0.64	meter 6 =		37.00 using Volume (gal)		
10.30	·Temp		Cond.	Turbiditiy	D.O.	ORP	Water Rem	oved	= =		
Time :	(or °F)	pН	(mS orus)	(NTUs)	((mg/l)	(mV)	(gals. or n	nL)	Observations		
1035	22.97	.(32	1991	131.4	0.65	6.6	50		9100		
1045	27.70	6.35	190x	144.4	0.45	4.9	15.0		94.28		
1055	23.60	647	1667	18.3	0.19	22	340		97.65		
1205	23.92	6:37	1878	18.9	0,47	3.7	3300		99,90		
•	e e			3	b b	100					
26					00						
4			4								
	0.00								2		
Did well dew	Did well dewater? Yes Amount actually evacuated:										
Sampling Tir	me: 100	0.0		Sampling D	Date: 12	- 23 14	<u> </u>				
Sample I.D.:	HTS	43-121	423	Laboratory	: <u>(</u>	SC Labo					
Analyzed for		TPHg	BTEX	MTBE TPHd OTHER:							
Equipment B	llank I.D.		@ Time	Duplicate I.D.							

Sampled with bailer next morning.

			Well N	/lonitori	ng Data	Sheet			
Project #	13650	2017	00.	Client:	Jallue 1	weter n	Nargum	out	
Sampler	RAIN	4		Start Date:		22/14	U.	t/	
Well I.D.	× 47	× l		Well Diam	eter 2	3 4) 6 8 C	ther:	-
Total Well D	epth: '\?	.30		Depth to V	Vater: Pre:	48,15	Post: 52	DO ESG	noling
Depth to Fre	e Product:			L.	of Free Prod		1		, ,
Reference to	o:	PVC	Grade	Flow Cell	Гуре: Ү	51 60	120		*
Purge Metho	od:	2"Grundfo	s Pump	Peristalitic	Pump ,	Bladder Pu	mp O	ther:	
Sample Met	hod:	Dedicated	Tubing (New Tubin	g Disp	osable Baile	rs O	ther <u>:</u>	<u> </u>
Flow Rate:				Pump Dep	th;		-51		± .
v ⁷³						5 1 - 1 - 1 - 1 - 1 - 1	, , , , , , , ,		
Well Volume Calculation (Fill in Before	Total Depth (ft)	e en	Depth to Water (ft)	E '	Water Column (ft)	Multiplier Casing Dia (in)	meter	Casing Volum (gal)	ie .
Purging)	73.30		15.15		25,15	0.16 0.64	1.44	16.09	
1245	·Temp		Cond.	Turbiditiy	D.O.	ORP	Water Remo	ved	95 86
Time	or °F)	pΗ	(mS or us)	(NTUs)	((mg/l)	(mV)	(gals) or ml	_) Observation	ons
1250	22.46	6774	インイン	147	1.07	47.9	5.0	53.5	
1300	22,51	6.73	8410	55,0	1,06	36.0	15,00	60,40	
1310	22.57	6.75	8442	75.3	1,44	32.7	25.	6617	_
135	22.41	6:77	र पपप	51.9	1.67	32.0	30	64.50	
1319				500	17	1)		Dry (0	3 dow pump intales
					1.	1			
*			6						
									17
		3							# F
Did well dew	rater?	Yes	No	Amount ac	tually evacu	ıated:	/		
Sampling Tir		10	,,,,	Sampling [12/22	114		
Sample I.D.:	145.0		2214	Laboratory		1 aha			
Analyzed for		TPHg		MTBE	TPHd	OTHER:			
Equipment B			@ Time	Duplicate I			01-1412	-22	



Chain of Custody Form

et #: 1365037	400	1200		An	alysis	s Rec	uest	ed		7/			in .	Pag	ge	of
et Name: Qace Tiac	11:11	1/	F	7' 	4./	-	7 /	/		Con	ıment	s:	, ,	11.00	1.	
ä		1/1	150	5	er/to	hit b	ack	de esti	5/3	Sa	2 0	Hai	ray 1	ist tol	COM	HUTC
ler(s): D. Prince			1	2/5	/ ₅ /	And	etic	n. bød	0	1550	l my	m	tals u	ماد (-1:1] =	これかと
		79-	N	3	700	ad.		f	Sami	ple M	atrix	ı, Xs*	Are there ar	ny tests with h or equal to 4	olding times 8 hours?	less than
1 30	8	٤_	200	0	0				Wate	Water		round rk da	<u> </u>	Yes	☐ No	
Date Sampled	Time Sampled	40	148°	AK	37	N Co	2:		oil ludge rinking	round Vaste W	0.1	Turna # of wo	* Standar			rk days
11125 1					<u>/ </u>				SSIC	V	Other			Not	es	
			-					+		N			-			
		1		3				+		N. L	-			,A		
1	1410			>	-			+		X					-	
		\ \ \ \	e x	\Rightarrow	XX					X	14					
A 1	*				+				1					3		
1	-															
					-		12									
															27	
						K					-					
								4								
			Sylven					-						61		
		-														11 12 Au
						+										
						e .								1 .	94	
EDF Required? Geotracker			F)													
Yes No			Ву			Da	ite 122	14 (S	ne (0.5	1. Rec	eived By		R _	, D	ate 122/14	Time 1805
Send Copy to State o	10.70	4-1	Ву			Da	ate	Tiı				- AC	8			Time
	3. Relin	quished	Ву	v .		Da	ate	Tin	ne	3. Rec	eived B	Y		D	ate	Time
	Date Sampled 12 21 14 12 22 14 12 22 14 12 22 14 12 22 14 12 22 14 13 22 14 14 15 25 14 15 26 15 EDF Required? Geotracker Yes No Send Copy to State of CA? (EDT)	Sampled Sampled	Date Time Sampled Sampled 12 21 14 1430 12 22 14 0905 12 12 14 1410 14 14 14 14 14 14 14 14 14 14 14 14 14	Date Time Sampled 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 14 14 10 2 2 2 14 14 10 2 2 2 2 2 2 2 2 2	Date Time Sampled Sampled I2 21 14 1410 x x x x x x x x x x x x x x x x x x x	Date Time Sampled Sampled 12 21 14 1430 X X X X X X X X X X X X X X X X X X X	Date Time Sampled Sampled 12 21 14 (430 × × × × × × × × × × × × × × × × × × ×	Date Time Sampled Sampled 12 21 14 14 10 2 2 2 14 14 10 2 2 2 2 14 14 10 2 2 2 2 14 14 10 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Time Sampled Sampled For Sampled Sampl	The sampled sampled by the sampled sam	The sampled Sa	th Name: Coc. Trad. H:	t Name: Coc. Tind H. II er(s): L. Pinota Date Time Sampled Sampled Sampled I2 21 IV IV 30 X X X X X X X X X X X X X X X X X X	t Name: Date Time Sampled Samp	t Name: Roc. Tlad. Hill er(s): Prince Prince	t Name: Loc. Ted. Hill Comments: Comm



Chain of Custody Form

									_				_	_											
Report To: Client:	Konowal Jonks	Project #:	: 13	361	50;	27 *	00					naly	sis	Red	que	ste	j							Page	
	lika molood	Project N	ame:	Rac	uT(ach 1-	11:1		/	/=	7 7	1	/ /	1	7	/ /	Ι,		/ 9	Con	nmen	ts:	1 1:2 E		. 1
	dress: 303 Second St								fe	1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	4	le/	10/1	hư	bak	: /1	τy		0	20	e ar	1. 19ch	al wie Co	COMBUT	
City, Stat	e, Zip: San Flancisca, (A.	Sampler(s):	2	ins	(~		/	/	=/1	000	10	T/cJ	\$	n/cti	/n	/	/5	``	٠,١.	, 0.	mat	ale wire C.	1) Ciltur	λ.
Phone: 2	43 -250 & Fax: 896-0999							V .	1	huz	13	100		had	my	thy	d	Ľ							
Email Ad								平	1	Š		(200	nd,				Sa	mpl [발]	e M	Iatrix	nd ays*	Are there any tests or eq		iess man
Work Or	der #:							W.	Dieralund	703	603	C	\subseteq						g Wa	Vater	Other	Turnaround of work days*	Yes		
Sample	Description			Da		Tir		40	1,513	-	4mm 10000	Hd	70					dae	inkin	iste V		Thrn of w	* Standard Tur	naround = 10 wo	rk days
#			5	Sam	oled	Sam	pled	P	0	70	18	r	1	,			16	So	j j	5 8	Other	#		Notes	
	RT12# 6- 122314	de la	1	2 2	2/14	0%	30	$ \lambda $	×	×	->	×	ン		1 2	3			K	X					14
	RTH #3 - 122314		(2 2	2 14	100	9	X	7	7	-	k	٧							X					
					Ì		s									*									
				1	i			1											П						
	25			F	i													П	П						
	-	(€	7.		1										¥.										*
					1													П	T	1					
			-	+	+	1												H	Ħ	t	1				
-			-	_	+-			1	\vdash									H	Ħ	+					
			-	+				1										\vdash	\forall	+				, d	
				+		+		+-	-		-							H	+	+		-		-	
			-	- 1	+					1		-					-	H	+	+		+-	75.0		
				_		-			-	-	5	r			-	-		\vdash	H	+	-				
			_		- 10			+	-	+-	-	-		-				$^{+}$		+	-	+			
												_									_	-			
Billing	Same as	above	EDF Geot	Requiracker	ired?	y.	Glob (Need	al ID led for	EDF))													ystem # Needed for EDT)		
Client: _						No.	1. Rel	-	hed B	Зу				į.	Date	Ť.		ime	1	. R	eccived	By	2	Date	Time
Address		Y					2. Rel)	Zvr C	_				Date	23/1		ime	-(_ P	eceived	By)	/223/ Date	Time
City:	State Z	ip	Send CA?	Copy (EDT)	to Stat	e of	Z. Kel	inguis	mea E	эy				1	Date			TITLE	l'		- Car				1.7
Attn:			□ y			No.	3. Rel	inquis	hed E	Ву				1	Date		Т	ime		3. R	eceived	Ву		Date	Time
PO#:		eu:			<u> </u>	.0																		140	1

BC Laboratories, Inc. - 4100 Atlas Ct. - Bakersfield, CA 93308 - 661.327.4911 - Fax: 661.327.1918 - www.bclabs.com

Possible Haz	ards										(5) Analyses Requested	ENOUNTMENTED ISSTORE
Project Sampler N	Site Reartial 4:11 No. 13 & 50 20 *00 lame (2. Prince	_ Co	mpany ddress	K.121 303	5000 Elaba Elaba	ترب سام	6+		81 Case	14m		Lab Destination 46A Dat of Carrier/Way Bill No. 5770 4251 7984
(1) Lab ID No.	(1) Client ID No.	Date	lection Time	(2) Type	Depth C	(3) omp.	(4) Pres.	Turn- around	3	d		Comment/Conditions (container type, container number, etc.)
	RTH *5 - 122114	나비	14 1430			1	بكانعو		X	X		
	RTH * 4 - 122214	12(2)	W CHOIC						×	χ		
	RTH# 1- 122214	12/22	1410						×	×		
	RTH & 6-122314	nhal	4 073						×	V		
	CT H# 3-122214	1423)	1000				1		٧	×		
			, s									
												*

⁽⁵⁾ Write each analysis requested across top, Place an "X" in appropriate column to indicate type of analysis needed for each sample.

Sample Relinqui	isned by	Sample Received By								
Signature	Company	Date	Time	Print Name	Signature	Company	Date	Time		
30m.	Kerney Jesk	12/30	1200							
	Signature	Signature Company	Signature Company Date	Signature Company Date Time	Signature Company Date Time Print Name	Signature Company Date Time Print Name Signature	Signature Company Date Time Print Name Signature Company	Signature Company Date Time Print Name Signature Company Date		

⁽¹⁾ Write only one sample number in each space.

⁽²⁾ Specify type of sample(s): Water (W), Solid (S), or indicate type.

⁽³⁾ Mark each sample which should be composited in Laboratory as follows: Place an "A" in box for each sample that should be composited into one sample; use sequential letter for additional groups.

⁽⁴⁾ Preservation of sample.

Fullerton, CA 92831

ition: ce ID:

FULCE FULCE-POSO2

62641

oyee: saction:

840115772426

DARD OVERNIGHT

082517984 21.60 lb (S) 114.82

duled Delivery Date 12/31/2014

Shipment subtotal:

114.82

Total Due:

114.82

FedEx Account: ****4403 114.82

Rev. Data 11/10 • Part #163134 • @1994-2010 FedEx • PRINTED IN U.S.A. SRS

d to 5150 units se you declare a higher value, See beck for details, By using this Airbill you southers on the back of this Airbill and in the current FedEx Service Guide, including terms

119

M = Weight entered manually S = Weight read from scale

T = Taxable item

t to additional charges. See FedEx Service Guide ex.com for details. All merchandise sales final.

> Visit us at: fedex.com Or call 1.800.GoFedEx 1.800.463.3339

December 30, 2014 9:56:05 AM

JS Airbill has changed. er 150 bs., order the new FedEx E	Ex US Airbill has changed. Is over 150 lbs., order the new FedEx E	O For ship	The F
anged. № Fed£x E	anged. № FedEx E	ts ov	
anged. № Fed£x E	anged. № FedEx E	er 150 lbs.,	S Airb
anged. № FedEx E	anged. See Sec! № FedEx Express Freigh	order the	ill has
e d. See x Express	ed. See Sections Express Freight U	v Fe	ಶು
	Sectio Freight Ն	x Express	ed. See

0443453810	CITY TWEST State ZIPKS 71-0077	daliwir to FOO 100 and the codes. Dept. Rock State Room Holl. Desturday Falls Room Holl. Desturday Falls Rock and a room from the Holl. Desturday Falls Rock and a room for continuation of your shipping address. The Holl Toosetion address or for continuation of your shipping address.	Trope Laborators HOLD Waskday Hold Eactor nodres Hold Eactor nodres	1621-1638		MAZIN ST.	3210 El Camaine (Leg)	Sender's ROD Privice Phone 714 570-5186	
Acct. No. in Section Re	7 Payment Bill to:	No Yes attached Shipper's Declared No. Shipper's Declared Shipper's Declared No. Moreover Declared No. Shipper's Declared No. Shipper's Declared No. Shipper's Declared No. Shipper's Declared No. Shipper in Fedition Control	No Signature Required Pedugerany will introduce Signature Required Someone structure of delivery. Does this shipment contain dangerous goods? One box mark be shecked.	Special Handling and Delivery Signature Options SATURDAY Delivery Nor available for Freder Stand Overnight, Feder Zinay A.M., or Feder Engress Seven	ro ro	Next business affernoon Seturday Dalwary NOT	FedEx Priority Overnight Next business morning," Friday shipmorns will be differed on Monday unless SATURDAY Ballvery to solucted.	FedEx First Overnight Earliest net business marting delivery to select locations ridge shipments will be delivered on Manday unless SATURDAY Delivery is selected.	Noxt Business Day
Recipient Third	 Enter FedEx Acct. No. or Credit Card No. below. 	yes Shipper's Declaration not required. x be shipped in FedEx packaging	Direct Signe Someone et recheme sign for deliver in dengerous goods?	nd Delivery Sign Overnight, Fedex 2Day A.M.,	* FedEx Pak*	nt dualizationi eggin	DAY Belivery	eny to select fallwared on a selector	100000
Party	or Cradk Card No. bel] g _	Direct Signeture Someone et recipient a adress may aign for delivery. For applies. us goods?	ature Options or FedEx Express Sever.	FedEx Box	Fig.Ex. Express Saver The business day.* Saturday Balkery NOT available	FedEx 2Dey Segond busineds will be delivered a Delivery is solvent	NEW FedE Second husiness Saturday Dallins	2 or 3 Busi
Credit Card	, wa	Dry Ice, a un 1845 xx Cargo Aircraft Only	Indirect Signature Indirect Signature Irea ons is available at recip address, ammanare at a representation of the second of the		Tube FedEx	Fed Express Sever Thet business day,* Seturday Delivery NOT available.	FedEx 2Day, Sectord brainess attempon.* Trumbey straments will be delivered on Monday mises SATURDAY Delivery is selected.	NEW FedEx 2Day A.M. Second trainess morning.* Seturday Dalvery NOT noslebie.	2 or 3 Business Days
] Cash		July	at a reigh for deliven as only. A		×		AN INSTITUTE		

0ther

From Please print and press hard Date 12 30 14

Sender's FedEx Account Number

SENDER S FEDITION TO THE BUILD BUILD

Express Package Service *To most locate
NOTE Service order has changed. Please select carefully.

* To stost locations

FedEx Tracking Number

0

0-

П

Ĺſ

0 œ

F

5120



Monitoring Well Sample Laboratory Reports



Date of Report: 01/05/2015

Stuart Childs

Kennedy/Jenks Consultants 303 Second Street, Suite 300 San Francisco, CA 94107

Client Project: 1365027.00
BCL Project: Race Track Hill

BCL Work Order: 1430572 Invoice ID: B192463

Enclosed are the results of analyses for samples received by the laboratory on 12/22/2014. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Contact Person: Misty Orton

Client Service Rep

Authorized Signature

Certifications: CA ELAP #1186; NV #CA00014; OR ELAP #4032-001; AK UST101



Table of Contents

Sample Information	
Chain of Custody and Cooler Receipt form	3
Laboratory / Client Sample Cross Reference	6
Sample Results	
1430572-01 - RTH #5 - 122114	
Total Petroleum Hydrocarbons	7
Water Analysis (General Chemistry)	8
Metals Analysis	9
1430572-02 - RTH #4 - 122214	
Total Petroleum Hydrocarbons	
Water Analysis (General Chemistry)	11
Metals Analysis	
1430572-03 - RTH #1 - 122214	
Total Petroleum Hydrocarbons	
Water Analysis (General Chemistry)	14
Metals Analysis	15
1430572-04 - QCED - 01 - 141222	
Total Petroleum Hydrocarbons	
Water Analysis (General Chemistry)	
Metals Analysis	
Quality Control Reports	
Total Petroleum Hydrocarbons	
Method Blank Analysis	19
Laboratory Control Sample	20
Precision and Accuracy	21
Water Analysis (General Chemistry)	
Method Blank Analysis	22
Laboratory Control Sample	23
Precision and Accuracy	24
Metals Analysis	
Method Blank Analysis	26
Laboratory Control Sample	27
Precision and Accuracy	28
Notes	
Notes and Definitions	20

Report ID: 1000311913



Chain of Custody and Cooler Receipt Form for 1430572 Page 1 of 3 Oissolut motals work fiell, filter <u>Z</u> <u>≞</u> Time Time Comments: See affactual list for complete * Standard Turnaround = 10 work days Date १यम्याप Date Notes Į Ž BC Laboratories, Inc. - 4100 Atlas Ct. - Bakersfield, CA 93308 - 661.327.4911 - Fax: 661.327.1918 - www.bclabs.com (Needed for EDT) \$ 100 System # # of work days* 3. Received By Other Sample Matrix Drinking Water Ground Water Waste Water **Chain of Custody Form** Date Date X X Z Х NOILLION 3. Relinquished By N X (Needed for EDF) X Х Global ID 2010 25 G) H1 Project Name: Race Trade 14:11 Project #: (3 6 5 0 37 4 90 Send Copy to State of CA? (EDT) ° No □ Sampler(s): D. Alide 12 21 14 12 DD 14 ヹ 12 22 14 EDF Required? Geotracker d ☐ Yes ☐ Yes ظ Same as above Zip 2-43 - 2504 Fax: 496-0999 -62141-10-Sity, State, Zip. Son Flandille, CA - 122114 RTH * 1-123214 かしていートマ W-3057 Laboratories, Inc. X State Street Address: 30 3 Samo RTHAS DA SP ALX Work Order #: Email Address: Address: Client: lient: City: Attn: d 3 ÷

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com

Chain of Custody and Cooler Receipt Form for 1430572 Page 2 of 3

Kennedy/Jenks Consultants

Table 1: Groundwater Sample Test Methods

					*	. •
Constituent	Test Method ^(a)	Reporting Limit	Container ^(b)	Sample Volume ^(c)	Preservative ^(d)	Holding Time ^(e)
pН	SM4500-HB	0.1 unit	P	250 ml	None	24 hours
Electroconductivity (EC)	EPA 120.1	1 (μmhos/cm ^(f) @ 25°C)	Р	250 ml	None	28 days
Nitrate - Nitrogen (NO ₃ as N)	EPA 300.0	0.1 mg/l ^(g)	Р	250 ml	None	48 hours
Total Dissolved Solids (TDS)	SM2540C	10 mg/l	Р	250 ml	None	7 days
Total Organic Carbon (TOC)	EPA 415.3	1.0 mg/l	Р	250 ml	H₂SO₄ pH<2	28 days
Boron (B)	EPA 200.7	0.1 mg/l	, Р	250 ml	HNO ₃ pH<2	6 months
Chloride (CI)	EPA 300.0	0.2 mg/l	Р	250 ml	None	28 days
Calcium (Ca)	EPA 200.7	0.5 mg/l	P	250 ml	HNO ₃ pH<2	6 months
Magnesium (Mg)	EPA 200.7	0.5 mg/l	Р	250 ml	HNO ₃ pH<2	6 months
Sodium (Na)	EPA 200.7	0.5 mg/l	Р	250 ml	HNO ₃ pH<2	6 months
Potassium (K)	EPA 200.7	0.5 mg/l	Р	250 ml	HNO ₃ pH<2	6 months
Sulfate (SO ₄)	EPA 300.0	5.0 mg/l	Р	250 ml	None	28 days
Alkalinity as Carbonate (CO ₃)	EPA 310.1	1.0 mg/l	Р	250 ml	None	14 days
Alkalinity as Bicarbonate (HCO₃)	EPA 310.1	1.0 mg/l	Р	250 mi	None	14 days
TPH-Crude Oil (TPHc)	EPA 8015B	0.1 mg/l	G	1000 ml	None	14 days
Oxygen isotopes	CRDS ^(h)	n/a	G	10 ml	None	1-3 months
Hydrogen Isotopes	CRES	n/a	G	10'ml	None	1-3 months

Notes:

- (a) EPA = U.S. Environmental Protection Agency

- EFA = 0.5. Environmental Protection Agency
 SM = Standard Methods
 P = Polyethylene; G = Glass
 ml = milliller
 H₂SO₄ pH-2 = sulfuric acid at pH 2 or less; HNO₃ pH-2 = nitric acid at pH 2 or less
 All samples should be kept at 4 degrees Celsius from the time of collection until analysis.
- μmho/cm = micromhos per centimeter mg/l = milligrams per liter Cavity Ring-Down Spectrometer

Phase 2 Investigation Work Plan, Race Track Hill Area Valley Water Management Company, Edison Oil Field, California
G3IB-GruphAdmInUbih13N385027.00_WMX009-ReportsPn2-investigation-WPlantTablexTrable 01 Water Test Melhods_mrw.docan Page 1 of 1

4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com



Chain of Custody and Cooler Receipt Form for 1430572 Page 3 of 3

C LABORATORIES INC.	. 10	COO	ER RECE	IPT FOR	VI	Rev. No. 1	8 09/04/1	- Andrews		 -	
Submission #: 14-3057									erialization of the sec	200 si 60, sir	
				SHIPPING CONTAINER Ice Chest (None Box YES No Other (Specify)							
Refrigerant: Ice ႙ Blue Ice	e □ Nor	ne □	Other □	Comm	ents:	(Antro	Tiers	ere (17	32013074912	150 W. ST.	
Custody Seals Ice Chest I	Contair	ners 🗆	None	Comr	nents:	A STATE OF THE STA	171	Hairie	(a) vins		
All samples received? Yes 🐧 No 🗆	All sample	s containe	s intact? Y	es 🔼 Nol] ,	Descrip	tion(s) matcl	n COC? Ye	No No		
COC Received 以YES □ NO	Emissivity: _	0.98 re: (A)	Container: 3.4	PE *C 1	(C)	3.B	208 °c	Date/Time Analyst In	it K1B	7 - 	
SAMPLE CONTAINERS	N. JANA					NUMBERS			9	10	
SAMPLE CONTAINENTS	1 00	2	I AB	AB	5	6	7	8		1	
OT GENERAL MINERAL/ GENERAL	AB	AB	A16	AD						Ė	
PT PE UNPRESERVED			1 1 1 1 1 1 1								
OT INORGANIC CHEMICAL METALS	10	-	CD	00			-			 	
PT INORGANIC CHEMICAL METALS	CD	led_	1 W	CD		-					
PT CYANIDE		<u> </u>		<u> </u>			1			 	
PT NITROGEN FORMS			1	<u> </u>	<u> </u>	ļ				+	
PT TOTAL SULFIDE		<u> </u>								+	
2oz. NITRATE / NITRITE		<u> </u>	1	 	-		+		 	 	
PT TOTAL ORGANIC CARBON	ŧ	E	F	5			+			+	
PT TOX					 		-			+-	
PT CHEMICAL OXYGEN DEMAND					 					+	
PtA PHENOLICS			_	<u> </u>					 	1	
40ml VOA VIAL TRAVEL BLANK				<u> </u>			- 			+	
40ml VOA VIAL				 	ļ	_		 	-	+	
QT EPA 413.1, 413.2, 418.1				_	 	_				+-	
PT ODOR			-					 	<u> </u>	+-	
RADIOLOGICAL					ļ			 	 	+-	
BACTERIOLOGICAL		<u> </u>			ļ		 	 -		+	
40 ml VOA VIAL- 504					<u> </u>			 	_ 	+	
QT EPA 508/608/8080									 	+	
QT EPA 515.1/8150							_		<u> </u>		
QT EPA 525								 		-	
QT EPA 525 TRAVEL BLANK				_		_	_		+		
40ml EPA 547						_		ļ			
40ml EPA 531.1		1								+	
8oz Amber EPA 548								-	 		
QT EPA 549								<u> </u>			
OT EPA 632						Sler.		<u> </u>		+-	
OT EPA 8015M	P	L¥_	F	Ŧ						+-	
QT AMBER									_		
8 OZ. JAR											
32 OZ. JAR											
SOIL SLEEVE										+	
PCB VIAL											
PLASTIC BAG								<u> </u>		_}_	
FERROUS IRON										-	
ENCORE											
SMART KIT									•		
			$\overline{}$		1			1	1		

Report ID: 1000311913

01/05/2015 17:11 Reported: Project: Race Track Hill Project Number: 1365027.00 Project Manager: Stuart Childs

Laboratory / Client Sample Cross Reference

Laboratory	Client Sample Informati	Client Sample Information									
1430572-01	COC Number: Project Number: Sampling Location: Sampling Point: Sampled By:	 RTH #5 - 122114 R. Prince	Receive Date: Sampling Date: Sample Depth: Lab Matrix: Sample Type: Metal Analysis: 1-6 Acidified	12/22/2014 18:05 12/21/2014 14:30 Water Groundwater Field Filtered and							
1430572-02	COC Number: Project Number: Sampling Location: Sampling Point: Sampled By:	 RTH #4 - 122214 R. Prince	Receive Date: Sampling Date: Sample Depth: Lab Matrix: Sample Type: Metal Analysis: 1-f	12/22/2014 18:05 12/22/2014 09:05 Water Groundwater Field Filtered and							
1430572-03	COC Number: Project Number: Sampling Location: Sampling Point: Sampled By:	 RTH #1 - 122214 R. Prince	Receive Date: Sampling Date: Sample Depth: Lab Matrix: Sample Type: Metal Analysis: 1-f	12/22/2014 18:05 12/22/2014 14:10 Water Groundwater Field Filtered and							
1430572-04	COC Number: Project Number: Sampling Location: Sampling Point: Sampled By:	 QCED - 01 - 141222 R. Prince	Receive Date: Sampling Date: Sample Depth: Lab Matrix: Sample Type: Metal Analysis: 1-f	12/22/2014 18:05 12/22/2014 00:00 Water Groundwater Field Filtered and							

Page 6 of 29 Report ID: 1000311913

01/05/2015 17:11 Reported:

Project: Race Track Hill Project Number: 1365027.00

Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430572-01	Client Sample	lient Sample Name: RTH #5 - 122114, 12/21/2014 2:30:00PM, R. Prince							
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #	
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1	
Tetracosane (Surrogate	e)	81.9	%	37 - 134 (LC	CL - UCL)	EPA-8015B/FFP			1	

			Run		QC				
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID		
1	EPA-8015B/FFP	12/23/14	12/24/14 16:29	MWB	GC-2	1	BXL2238		

Page 7 of 29 Report ID: 1000311913

Reported: 01/05/2015 17:11 Project: Race Track Hill

Project Number: 1365027.00
Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430572-01	Client Samp	le Name:	RTH #5 -	122114, 12	2/21/2014 2:30:	00PM, R. Prin	ce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		62	mg/L	0.10	0.016	EPA-200.7	ND	Quais	1
Total Recoverable Ca	lcium	64	mg/L	0.10	0.014	EPA-200.7	ND		2
Dissolved Magnesium	1	22	mg/L	0.050	0.019	EPA-200.7	ND		1
Total Recoverable Ma	gnesium	23	mg/L	0.050	0.019	EPA-200.7	ND		2
Dissolved Sodium		50	mg/L	0.50	0.051	EPA-200.7	ND		1
Total Recoverable So	dium	51	mg/L	0.50	0.051	EPA-200.7	ND		2
Dissolved Potassium		6.3	mg/L	1.0	0.10	EPA-200.7	ND		1
Total Recoverable Po	tassium	6.4	mg/L	1.0	0.10	EPA-200.7	ND		2
Bicarbonate Alkalinity	as CaCO3	220	mg/L	4.1	4.1	EPA-310.1	ND		3
Carbonate Alkalinity as	s CaCO3	ND	mg/L	4.1	4.1	EPA-310.1	ND		3
Alkalinity as CaCO3		220	mg/L	4.1	4.1	Calc	ND		4
Chloride		26	mg/L	0.50	0.061	EPA-300.0	ND		5
Nitrate as N		0.57	mg/L	0.10	0.018	EPA-300.0	ND		5
Sulfate		92	mg/L	1.0	0.10	EPA-300.0	ND		5
рН		7.69	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivit	y @ 25 C	624	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solids	s @ 180 C	450	mg/L	20	20	SM-2540C	ND		8
Non-Volatile Organic O	Carbon	ND	mg/L	1.0	0.30	EPA-415.1	ND		9

Run # Method Prep Date Date/Time Analyst Instrument Dilution Batch ID 1 EPA-200.7 12/21/14 12/24/14 13:25 JRG PE-OP2 1 BXL2262 2 EPA-200.7 12/31/14 12/31/14 17:14 JRG PE-OP2 1 BXL2791 3 EPA-310.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 00:27 BMW IC8 1 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405 9 EPA-415.1 12/24/14 12/24/14 10:20 ALW				Run				QC
2 EPA-200.7 12/31/14 12/31/14 17:14 JRG PE-OP2 1 BXL2791 3 EPA-310.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 00:27 BMW IC8 1 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	Run #	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
3 EPA-310.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 00:27 BMW IC8 1 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	1	EPA-200.7	12/21/14	12/24/14 13:25	JRG	PE-OP2	1	BXL2262
4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 00:27 BMW IC8 1 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	2	EPA-200.7	12/31/14	12/31/14 17:14	JRG	PE-OP2	1	BXL2791
5 EPA-300.0 12/22/14 12/23/14 00:27 BMW IC8 1 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	3	EPA-310.1	12/26/14	12/26/14 12:26	RML	MET-1	1	BXL2456
6 EPA-150.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	4	Calc	12/24/14	01/05/15 07:49	MSA	Calc	1	BXL2319
7 EPA-120.1 12/26/14 12/26/14 12:26 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	5	EPA-300.0	12/22/14	12/23/14 00:27	BMW	IC8	1	BXL2267
8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 2 BXL2405	6	EPA-150.1	12/26/14	12/26/14 12:26	RML	MET-1	1	BXL2456
	7	EPA-120.1	12/26/14	12/26/14 12:26	RML	MET-1	1	BXL2456
9 EPA-415.1 12/24/14 12/24/14 10:20 ALW TOC2 1 BXL2125	8	SM-2540C	12/26/14	12/26/14 14:00	CAD	MANUAL	2	BXL2405
	9	EPA-415.1	12/24/14	12/24/14 10:20	ALW	TOC2	1	BXL2125

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 8 of 29



01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1430572-01	Client Sampl	ient Sample Name: RTH #5 - 122114, 12/21/2014 2:30:00PM, R. Prince							
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#	
Dissolved Boron		69	ug/L	100	10	EPA-200.7	ND	J	1	
Total Recoverable Bo	ron	66	ug/L	100	10	EPA-200.7	ND	J	2	

			Run					
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	12/21/14	12/24/14 13:25	JRG	PE-OP2	1	BXL2262	
2	EPA-200.7	12/31/14	12/31/14 17:14	JRG	PE-OP2	1	BXL2791	

Page 9 of 29 Report ID: 1000311913

01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430572-02	Client Sample	lient Sample Name: RTH #4 - 122214, 12/22/2014 9:05:00AM, R. Prince							
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #	
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1	
Tetracosane (Surrogate	:)	90.1	%	37 - 134 (LC	L - UCL)	EPA-8015B/FFP			1	

			Run		QC				
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID		
1	EPA-8015B/FFP	12/23/14	12/24/14 16:51	MWB	GC-2	1	BXL2238		

Page 10 of 29 Report ID: 1000311913

01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430572-02	Client Samp	le Name:	RTH #4 -	122214, 12	2/22/2014 9:05:	00AM, R. Princ	ce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		490	mg/L	0.10	0.016	EPA-200.7	ND ND	Quais	1
Total Recoverable Ca	alcium	490	mg/L	0.10	0.014	EPA-200.7	ND		2
Dissolved Magnesiu	m	170	mg/L	0.050	0.019	EPA-200.7	ND		1
Total Recoverable M	agnesium	180	mg/L	0.050	0.019	EPA-200.7	ND		2
Dissolved Sodium		630	mg/L	0.50	0.051	EPA-200.7	ND		1
Total Recoverable So	odium	680	mg/L	0.50	0.051	EPA-200.7	ND		2
Dissolved Potassium	1	22	mg/L	1.0	0.10	EPA-200.7	ND		1
Total Recoverable Po	otassium	23	mg/L	1.0	0.10	EPA-200.7	ND		2
Bicarbonate Alkalinit	y as CaCO3	210	mg/L	8.2	8.2	EPA-310.1	ND		3
Carbonate Alkalinity a	s CaCO3	ND	mg/L	8.2	8.2	EPA-310.1	ND		3
Alkalinity as CaCO3		210	mg/L	8.2	8.2	Calc	ND		4
Chloride		2000	mg/L	5.0	0.61	EPA-300.0	ND	A01	5
Nitrate as N		3.4	mg/L	1.0	0.18	EPA-300.0	ND	A10	5
Sulfate		370	mg/L	10	1.0	EPA-300.0	ND	A01	5
pH		7.38	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivi	ty @ 25 C	6540	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solid	is @ 180 C	5100	mg/L	200	200	SM-2540C	ND		8
Non-Volatile Organic	Carbon	1.1	mg/L	1.0	0.30	EPA-415.1	ND		9

Run # Method Prep Date Date/Time Analyst Instrument Dilution Batch ID 1 EPA-200.7 12/22/14 12/24/14 13:37 JRG PE-OP2 1 BXL2262 2 EPA-200.7 12/31/14 12/31/14 17:33 JRG PE-OP2 1 BXL2791 3 EPA-310.1 12/26/14 12/26/14 12:38 RML MET-1 2 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 01:26 OLH IC8 10 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405 9 EPA-415.1 12/24/14 12/24/14 10:35 ALW				Run				QC
2 EPA-200.7 12/31/14 12/31/14 17:33 JRG PE-OP2 1 BXL2791 3 EPA-310.1 12/26/14 12/26/14 12:38 RML MET-1 2 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 01:26 OLH IC8 10 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
3 EPA-310.1 12/26/14 12/26/14 12:38 RML MET-1 2 BXL2456 4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 01:26 OLH IC8 10 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	1	EPA-200.7	12/22/14	12/24/14 13:37	JRG	PE-OP2	1	BXL2262
4 Calc 12/24/14 01/05/15 07:49 MSA Calc 1 BXL2319 5 EPA-300.0 12/22/14 12/23/14 01:26 OLH IC8 10 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	2	EPA-200.7	12/31/14	12/31/14 17:33	JRG	PE-OP2	1	BXL2791
5 EPA-300.0 12/22/14 12/23/14 01:26 OLH IC8 10 BXL2267 6 EPA-150.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	3	EPA-310.1	12/26/14	12/26/14 12:38	RML	MET-1	2	BXL2456
6 EPA-150.1 12/26/14 12:38 RML MET-1 1 BXL2456 7 EPA-120.1 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12:6/14 14:00 CAD MANUAL 20 BXL2405	4	Calc	12/24/14	01/05/15 07:49	MSA	Calc	1	BXL2319
7 EPA-120.1 12/26/14 12/26/14 12:38 RML MET-1 1 BXL2456 8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	5	EPA-300.0	12/22/14	12/23/14 01:26	OLH	IC8	10	BXL2267
8 SM-2540C 12/26/14 12/26/14 14:00 CAD MANUAL 20 BXL2405	6	EPA-150.1	12/26/14	12/26/14 12:38	RML	MET-1	1	BXL2456
	7	EPA-120.1	12/26/14	12/26/14 12:38	RML	MET-1	1	BXL2456
9 EPA-415.1 12/24/14 12/24/14 10:35 ALW TOC2 1 BXL2125	8	SM-2540C	12/26/14	12/26/14 14:00	CAD	MANUAL	20	BXL2405
	9	EPA-415.1	12/24/14	12/24/14 10:35	ALW	TOC2	1	BXL2125

4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Report ID: 1000311913

Page 11 of 29



01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1430572-02	Client Sampl	e Name:	RTH #4 -	122214, 12	2/22/2014 9:05	ce		
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
Dissolved Boron		5200	ug/L	100	10	EPA-200.7	ND		1
Total Recoverable Bo	ron	5400	ug/L	100	10	EPA-200.7	ND		2

			Run					
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	12/22/14	12/24/14 13:37	JRG	PE-OP2	1	BXL2262	
2	EPA-200.7	12/31/14	12/31/14 17:33	JRG	PE-OP2	1	BXL2791	

Page 12 of 29 Report ID: 1000311913

01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430572-03	Client Sample	e Name:	RTH #1 -	122214, 12	2/22/2014 2:10:00	ce		
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate	e)	82.8	%	37 - 134 (LC	CL - UCL)	EPA-8015B/FFP			1

	Run							
Run #	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-8015B/FFP	12/23/14	12/24/14 17:14	MWB	GC-2	1	BXL2238	

Page 13 of 29 Report ID: 1000311913

Reported: 01/05/2015 17:11 Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430572-03	Client Samp	le Name:	RTH #1 -	122214, 12	2/22/2014 2:10:	00PM, R. Prin	ce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		520	mg/L	0.20	0.032	EPA-200.7	ND	A10	1
Total Recoverable Calci	um	550	mg/L	0.20	0.028	EPA-200.7	ND	A10	2
Dissolved Magnesium		41	mg/L	0.10	0.038	EPA-200.7	ND	A10	1
Total Recoverable Magr	nesium	45	mg/L	0.10	0.038	EPA-200.7	ND	A10	2
Dissolved Sodium		1200	mg/L	1.0	0.10	EPA-200.7	ND	A01	1
Total Recoverable Sodio	ım	1300	mg/L	1.0	0.10	EPA-200.7	ND	A01	2
Dissolved Potassium		8.1	mg/L	2.0	0.20	EPA-200.7	ND	A10	1
Total Recoverable Potas	ssium	9.0	mg/L	2.0	0.20	EPA-200.7	ND	A10	2
Bicarbonate Alkalinity a	s CaCO3	220	mg/L	8.2	8.2	EPA-310.1	ND		3
Carbonate Alkalinity as C	CaCO3	ND	mg/L	8.2	8.2	EPA-310.1	ND		3
Alkalinity as CaCO3		220	mg/L	8.2	8.2	Calc	ND		4
Chloride		2900	mg/L	10	1.2	EPA-300.0	ND	A01	5
Nitrate as N		14	mg/L	2.0	0.36	EPA-300.0	ND	A01	5
Sulfate		42	mg/L	20	2.0	EPA-300.0	ND	A01	5
рН		7.26	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivity (@ 25 C	8650	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solids (@ 180 C	7000	mg/L	500	500	SM-2540C	ND	<u> </u>	8
Non-Volatile Organic Ca	ırbon	1.6	mg/L	1.0	0.30	EPA-415.1	ND		9

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-200.7	12/22/14	12/24/14 13:52	JRG	PE-OP2	2	BXL2262
2	EPA-200.7	12/31/14	12/31/14 17:46	JRG	PE-OP2	2	BXL2791
3	EPA-310.1	12/26/14	12/26/14 13:20	RML	MET-1	2	BXL2456
4	Calc	12/24/14	01/05/15 07:49	MSA	Calc	1	BXL2319
5	EPA-300.0	12/22/14	12/23/14 01:40	OLH	IC8	20	BXL2267
6	EPA-150.1	12/26/14	12/26/14 13:20	RML	MET-1	1	BXL2456
7	EPA-120.1	12/26/14	12/26/14 13:20	RML	MET-1	1	BXL2456
8	SM-2540C	12/26/14	12/26/14 14:00	CAD	MANUAL	50	BXL2405
9	EPA-415.1	12/24/14	12/24/14 10:49	ALW	TOC2	1	BXL2125

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 14 of 29



01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1430572-03	Client Sampl	e Name:	RTH #1 - 122214, 12/22/2014 2:10:00PM, R. Prince						
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#	
Dissolved Boron		15000	ug/L	200	20	EPA-200.7	ND	A10	1	
Total Recoverable Bo	ron	16000	ug/L	200	20	EPA-200.7	ND	A10	2	

			Run					
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	12/22/14	12/24/14 13:52	JRG	PE-OP2	2	BXL2262	
2	EPA-200.7	12/31/14	12/31/14 17:46	JRG	PE-OP2	2	BXL2791	

Page 15 of 29 Report ID: 1000311913

01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430572-04	Client Sample	ent Sample Name: QCED - 01 - 141222, 12/22/2014 12:00:00AM, R. Prince						
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate	e)	81.7	%	37 - 134 (LC	L - UCL)	EPA-8015B/FFP			1

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-8015B/FFP	12/23/14	12/24/14 17:36	MWB	GC-2	1	BXL2238

Page 16 of 29 Report ID: 1000311913

Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027 00

Project Number: 1365027.00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430572-04	Client Samp	le Name:	QCED - 01 - 141222, 12/22/2014 12:00:00AM, R. Prince					
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		530	mg/L	0.20	0.032	EPA-200.7	ND	A10	1
Total Recoverable Calciu	ım	560	mg/L	0.20	0.028	EPA-200.7	ND	A10	2
Dissolved Magnesium		41	mg/L	0.10	0.038	EPA-200.7	ND	A10	1
Total Recoverable Magn	esium	45	mg/L	0.10	0.038	EPA-200.7	ND	A10	2
Dissolved Sodium		1200	mg/L	1.0	0.10	EPA-200.7	ND	A01	1
Total Recoverable Sodiu	ım	1300	mg/L	1.0	0.10	EPA-200.7	ND	A01	2
Dissolved Potassium		8.2	mg/L	2.0	0.20	EPA-200.7	ND	A10	1
Total Recoverable Potas	sium	9.0	mg/L	2.0	0.20	EPA-200.7	ND	A10	2
Bicarbonate Alkalinity as	s CaCO3	220	mg/L	8.2	8.2	EPA-310.1	ND		3
Carbonate Alkalinity as C	aCO3	ND	mg/L	8.2	8.2	EPA-310.1	ND		3
Alkalinity as CaCO3		220	mg/L	8.2	8.2	Calc	ND		4
Chloride		2900	mg/L	10	1.2	EPA-300.0	ND	A01	5
Nitrate as N		11	mg/L	2.0	0.36	EPA-300.0	ND	A01	5
Sulfate		40	mg/L	20	2.0	EPA-300.0	ND	A10	5
рН		7.24	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivity @	ฏ 25 C	8700	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solids @	0 180 C	7000	mg/L	500	500	SM-2540C	ND	<u> </u>	8
Non-Volatile Organic Ca	rbon	1.6	mg/L	1.0	0.30	EPA-415.1	ND		9

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-200.7	12/22/14	12/24/14 13:54	JRG	PE-OP2	2	BXL2262
2	EPA-200.7	12/31/14	12/31/14 17:49	JRG	PE-OP2	2	BXL2791
3	EPA-310.1	12/26/14	12/26/14 13:27	RML	MET-1	2	BXL2456
4	Calc	12/24/14	01/05/15 07:49	MSA	Calc	1	BXL2319
5	EPA-300.0	12/22/14	12/23/14 01:55	OLH	IC8	20	BXL2267
6	EPA-150.1	12/26/14	12/26/14 13:27	RML	MET-1	1	BXL2456
7	EPA-120.1	12/26/14	12/26/14 13:27	RML	MET-1	1	BXL2456
8	SM-2540C	12/26/14	12/26/14 14:00	CAD	MANUAL	50	BXL2405
9	EPA-415.1	12/24/14	12/24/14 11:04	ALW	TOC2	1	BXL2125

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 17 of 29



01/05/2015 17:11 Reported: Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1430572-04	Client Sampl	e Name:	e: QCED - 01 - 141222, 12/22/2014 12:00:00AM, R. Prince								
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#			
Dissolved Boron		15000	ug/L	200	20	EPA-200.7	ND	A10	1			
Total Recoverable Bo	ron	16000	ug/L	200	20	EPA-200.7	ND	A10	2			

			Run				QC	
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	12/22/14	12/24/14 13:54	JRG	PE-OP2	2	BXL2262	
2	EPA-200.7	12/31/14	12/31/14 17:49	JRG	PE-OP2	2	BXL2791	

Page 18 of 29 Report ID: 1000311913

Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027.00

Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2238						
TPH - Crude Oil	BXL2238-BLK1	ND	ug/L	500	140	
Tetracosane (Surrogate)	BXL2238-BLK1	84.4	%	37 - 13	4 (LCL - UCL)	

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 19 of 29

Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027.00
Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	RPD	Control I Percent Recovery	Lab Quals	
QC Batch ID: BXL2238										
Tetracosane (Surrogate)	BXL2238-BS1	LCS	84.295	100.00	ug/L	84.3		37 - 134		

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 20 of 29

Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027.00
Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Precision & Accuracy

									Control L	imits.	
		Source	Source		Spike			Percent	Pe	rcent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD Re	covery	Quals
	_										
QC Batch ID: BXL2238	Use	d client samp	ole: N								
Tetracosane (Surrogate)	MS	1425343-55	ND	85.265	100.00	ug/L		85.3	37 -	134	
	MSD	1425343-55	ND	43.105	100.00	ug/L	65.7	43.1	37 -	134	

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 21 of 29

Reported: 01/05/2015 17:11
Project: Race Track Hill
roject Number: 1365027 00

Project Number: 1365027.00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2125						
Non-Volatile Organic Carbon	BXL2125-BLK1	ND	mg/L	1.0	0.30	
QC Batch ID: BXL2262						
Dissolved Calcium	BXL2262-BLK1	ND	mg/L	0.10	0.016	
Dissolved Magnesium	BXL2262-BLK1	ND	mg/L	0.050	0.019	
Dissolved Sodium	BXL2262-BLK1	ND	mg/L	0.50	0.051	
Dissolved Potassium	BXL2262-BLK1	ND	mg/L	1.0	0.10	
QC Batch ID: BXL2267						
Chloride	BXL2267-BLK1	ND	mg/L	0.50	0.061	
Nitrate as N	BXL2267-BLK1	ND	mg/L	0.10	0.018	
Sulfate	BXL2267-BLK1	ND	mg/L	1.0	0.10	
QC Batch ID: BXL2319						
Alkalinity as CaCO3	BXL2319-BLK1	ND	mg/L	4.1	4.1	
QC Batch ID: BXL2405						
Total Dissolved Solids @ 180 C	BXL2405-BLK1	ND	mg/L	6.7	6.7	
QC Batch ID: BXL2456						
Bicarbonate Alkalinity as CaCO3	BXL2456-BLK1	ND	mg/L	4.1	4.1	
Carbonate Alkalinity as CaCO3	BXL2456-BLK1	ND	mg/L	4.1	4.1	
QC Batch ID: BXL2791						
Total Recoverable Calcium	BXL2791-BLK1	ND	mg/L	0.10	0.014	
Total Recoverable Magnesium	BXL2791-BLK1	ND	mg/L	0.050	0.019	
Total Recoverable Sodium	BXL2791-BLK1	ND	mg/L	0.50	0.051	
Total Recoverable Potassium	BXL2791-BLK1	ND	mg/L	1.0	0.10	

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 22 of 29

01/05/2015 17:11 Reported: Project: Race Track Hill Project Number: 1365027.00

Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Laboratory Control Sample

							-			
								Control I	Limits	
				Spike		Percent		Percent		Lab
Constituent	QC Sample ID	Type	Result	Level	Units	Recovery	RPD	Recovery	RPD	Quals
QC Batch ID: BXL2125										
Non-Volatile Organic Carbon	BXL2125-BS1	LCS	5.2640	5.0000	mg/L	105		85 - 115		
QC Batch ID: BXL2262										
Dissolved Calcium	BXL2262-BS1	LCS	9.9825	10.000	mg/L	99.8		85 - 115		
Dissolved Magnesium	BXL2262-BS1	LCS	10.293	10.000	mg/L	103		85 - 115		
Dissolved Sodium	BXL2262-BS1	LCS	9.8719	10.000	mg/L	98.7		85 - 115		
Dissolved Potassium	BXL2262-BS1	LCS	9.7945	10.000	mg/L	97.9		85 - 115		
QC Batch ID: BXL2267										
Chloride	BXL2267-BS1	LCS	50.546	50.000	mg/L	101		90 - 110		
Nitrate as N	BXL2267-BS1	LCS	4.6130	5.0000	mg/L	92.3		90 - 110		
Sulfate	BXL2267-BS1	LCS	100.66	100.00	mg/L	101		90 - 110		
QC Batch ID: BXL2405										
Total Dissolved Solids @ 180 C	BXL2405-BS1	LCS	560.00	586.00	mg/L	95.6		90 - 110		
QC Batch ID: BXL2456										
рН	BXL2456-BS2	LCS	7.0500	7.0000	pH Units	101		95 - 105		
Electrical Conductivity @ 25 C	BXL2456-BS1	LCS	303.50	303.00	umhos/cm	100		90 - 110		
QC Batch ID: BXL2791										
Total Recoverable Calcium	BXL2791-BS1	LCS	10.334	10.000	mg/L	103		85 - 115		
Total Recoverable Magnesium	BXL2791-BS1	LCS	10.807	10.000	mg/L	108		85 - 115		
Total Recoverable Sodium	BXL2791-BS1	LCS	10.498	10.000	mg/L	105		85 - 115		
Total Recoverable Potassium	BXL2791-BS1	LCS	10.153	10.000	mg/L	102		85 - 115		
-										

Page 23 of 29 Report ID: 1000311913

Report ID: 1000311913

Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027.00
Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Precision & Accuracy

									Cont		
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2125	Use	d client samp	ole: N								
Non-Volatile Organic Carbon	 DUP	1430583-03	ND	ND		mg/L			10		
	MS	1430583-03	ND	5.3990	5.0251	mg/L		107		80 - 120	
	MSD	1430583-03	ND	5.3749	5.0251	mg/L	0.4	107	10	80 - 120	
QC Batch ID: BXL2262	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 122	114, 12/21/2	014 14	1:30			
Dissolved Calcium	DUP	1430572-01	61.502	61.623		mg/L	0.2		20		
	MS	1430572-01	61.502	68.803	10.204	mg/L		71.5		85 - 115	A03
	MSD	1430572-01	61.502	69.333	10.204	mg/L	8.0	76.7	20	85 - 115	A03
Dissolved Magnesium	DUP	1430572-01	21.775	21.690		mg/L	0.4		20		
	MS	1430572-01	21.775	30.631	10.204	mg/L		86.8		85 - 115	
	MSD	1430572-01	21.775	30.930	10.204	mg/L	1.0	89.7	20	85 - 115	
Dissolved Sodium	DUP	1430572-01	49.712	49.424		mg/L	0.6		20		
	MS	1430572-01	49.712	57.000	10.204	mg/L		71.4		85 - 115	A03
	MSD	1430572-01	49.712	58.069	10.204	mg/L	1.9	81.9	20	85 - 115	A03
Dissolved Potassium	DUP	1430572-01	6.2869	6.2787		mg/L	0.1		20		
SSOIVEU FOIASSIUIII	MS	1430572-01	6.2869	15.622	10.204	mg/L		91.5		85 - 115	
	MSD	1430572-01	6.2869	15.997	10.204	mg/L	2.4	95.2	20	85 - 115	
QC Batch ID: BXL2267	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 122	114, 12/21/2	014 14	1:30			
Chloride	DUP	1430572-01	25.687	25.710		mg/L	0.1		10		
	MS	1430572-01	25.687	82.508	50.505	mg/L		113		80 - 120	
	MSD	1430572-01	25.687	82.498	50.505	mg/L	0.0	112	10	80 - 120	
litrate as N	DUP	1430572-01	0.56900	0.56200		mg/L	1.2		10		
	MS	1430572-01	0.56900	5.7111	5.0505	mg/L		102		80 - 120	
	MSD	1430572-01	0.56900	5.7091	5.0505	mg/L	0.0	102	10	80 - 120	
Sulfate	DUP	1430572-01	92.207	92.440		mg/L	0.3		10		
	MS	1430572-01	92.207	206.65	101.01	mg/L		113		80 - 120	
	MSD	1430572-01	92.207	206.57	101.01	mg/L	0.0	113	10	80 - 120	
QC Batch ID: BXL2405	Use	d client samp	ole: Y - Des	cription: RT	H #4 - 122	214, 12/22/2	014 09	9:05			
Total Dissolved Solids @ 180 C	DUP	1430572-02	5100.0	5120.0		mg/L	0.4		10		
QC Batch ID: BXL2456	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 122	114, 12/21/2	014 14	1:30			
Bicarbonate Alkalinity as CaCO3	DUP	1430572-01	215.12	215.27		mg/L	0.1		10		
Carbonate Alkalinity as CaCO3	DUP	1430572-01	ND	ND		mg/L			10		
oH 	DUP	1430572-01	7.6900	7.6900		pH Units	0		20		
Electrical Conductivity @ 25 C	DUP	1430572-01	623.50	632.10		umhos/cm	1.4		10		
QC Batch ID: BXL2791	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 122	114, 12/21/2	014 14	1:30	-		-

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

All results listed in this report are for the exclusive use of the submitting party. BC Laboratories, Inc. assumes no responsibility for report alteration, separation, detachment or third party interpretation.

4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com

Reported: 01/05/2015 17:11
Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Precision & Accuracy

									Cont	rol Limits	·
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Туре	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2791	Use	ed client samp	ole: Y - Des	cription: RT	H #5 - 1221	14, 12/21/	2014 14	1:30			
Total Recoverable Calcium	DUP	1430572-01	63.986	63.890		mg/L	0.1		20		
	MS	1430572-01	63.986	70.525	10.000	mg/L		65.4		75 - 125	A03
	MSD	1430572-01	63.986	73.377	10.000	mg/L	4.0	93.9	20	75 - 125	
Total Recoverable Magnesium	DUP	1430572-01	22.926	22.876		mg/L	0.2		20		
	MS	1430572-01	22.926	31.913	10.000	mg/L		89.9		75 - 125	
	MSD	1430572-01	22.926	32.989	10.000	mg/L	3.3	101	20	75 - 125	
Total Recoverable Sodium	DUP	1430572-01	51.368	51.063		mg/L	0.6		20		
	MS	1430572-01	51.368	58.987	10.000	mg/L		76.2		75 - 125	
	MSD	1430572-01	51.368	61.380	10.000	mg/L	4.0	100	20	75 - 125	
Total Recoverable Potassium	DUP	1430572-01	6.4494	6.3864		mg/L	1.0		20		
	MS	1430572-01	6.4494	16.206	10.000	mg/L		97.6		75 - 125	
	MSD	1430572-01	6.4494	16.614	10.000	mg/L	2.5	102	20	75 - 125	

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 25 of 29



Reported: 01/05/2015 17:11
Project: Race Track Hill
roject Number: 1365027 00

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2262						
Dissolved Boron	BXL2262-BLK1	ND	ug/L	100	10	
QC Batch ID: BXL2791						
Total Recoverable Boron	BXL2791-BLK1	ND	ug/L	100	10	

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 26 of 29



Reported: 01/05/2015 17:11
Project: Race Track Hill
Project Number: 1365027.00
Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Laboratory Control Sample

		_	Result	Spike		Percent		Control L		Lab
Constituent	QC Sample ID	Туре	Result	Level	Units	Recovery	RPD	Recovery	KPD	Quals
QC Batch ID: BXL2262										
Dissolved Boron	BXL2262-BS1	LCS	982.54	1000.0	ug/L	98.3		85 - 115		
QC Batch ID: BXL2791										
Total Recoverable Boron	BXL2791-BS1	LCS	1021.5	1000.0	ug/L	102		85 - 115		

Report ID: 1000311913 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 27 of 29

Kennedy/Jenks Consultants

303 Second Street, Suite 300 San Francisco, CA 94107

Reported: 01/05/2015 17:11 Project: Race Track Hill

Project Number: 1365027.00 Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Precision & Accuracy

									Con	trol Limits	
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Туре	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2262	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 1221	14, 12/21/	2014 1	4:30			
Dissolved Boron	DUP	1430572-01	69.031	69.465		ug/L	0.6		20		J
	MS	1430572-01	69.031	1029.9	1020.4	ug/L		94.2		85 - 115	
	MSD	1430572-01	69.031	1076.7	1020.4	ug/L	4.4	98.7	20	85 - 115	
QC Batch ID: BXL2791	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 1221	14, 12/21/	2014 1	4:30			
Total Recoverable Boron	DUP	1430572-01	66.183	65.663		ug/L	8.0		20		J
	MS	1430572-01	66.183	1064.4	1000.0	ug/L		99.8		75 - 125	
	MSD	1430572-01	66.183	1093.1	1000.0	ug/L	2.7	103	20	75 - 125	

4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Report ID: 1000311913

Page 28 of 29

Kennedy/Jenks Consultants Reported: 01/05/2015 17:11 303 Second Street, Suite 300 Project: Race Track Hill San Francisco, CA 94107 Project Number: 1365027.00

Project Manager: Stuart Childs

Notes And Definitions

Estimated Value (CLP Flag) MDL Method Detection Limit

ND Analyte Not Detected at or above the reporting limit

Practical Quantitation Limit **PQL** Relative Percent Difference RPD

PQL's and MDL's are raised due to sample dilution. A01

A03 The sample concentration is more than 4 times the spike level.

A10 PQL's and MDL's were raised due to matrix interference.

S05 The sample holding time was exceeded.

4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 29 of 29 Report ID: 1000311913



Date of Report: 01/07/2015

Stuart Childs

Kennedy/Jenks Consultants 303 Second Street, Suite 300 San Francisco, CA 94107

Client Project: 1365027*00 Race Track Hill **BCL Project:**

1430662 **BCL Work Order:** B192806 Invoice ID:

Enclosed are the results of analyses for samples received by the laboratory on 12/23/2014. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Contact Person: Misty Orton

Client Service Rep

Authorized Signature

Certifications: CA ELAP #1186; NV #CA00014; OR ELAP #4032-001; AK UST101

Report ID: 1000313293



Table of Contents

Sample Information	
Chain of Custody and Cooler Receipt form	3
Laboratory / Client Sample Cross Reference	6
Sample Results	
1430662-01 - RTH #6 - 122314	
Total Petroleum Hydrocarbons	7
Water Analysis (General Chemistry)	
Metals Analysis	
1430662-02 - RTH #3 - 122314	
Total Petroleum Hydrocarbons	10
Water Analysis (General Chemistry)	
Metals Analysis	
Quality Control Reports	
Total Petroleum Hydrocarbons	
Method Blank Analysis	13
Laboratory Control Sample	
Precision and Accuracy	
Water Analysis (General Chemistry)	
Method Blank Analysis	
Laboratory Control Sample	17
Precision and Accuracy	
Metals Analysis	
Method Blank Analysis	20
Laboratory Control Sample	
Precision and Accuracy	
Notes	
Notes and Definitions	22

Report ID: 1000313293



Chain of Custody and Cooler Receipt Form for 1430662 Page 1 of 3 Time * Standard Turnaround = 10 work days Are there any tests with holding times less or equal to 48 hours? Dissolved motale wire Field Giltored Date SS COT ı X NOLTHIN SUB-OUT BC Laboratories, Inc. - 4100 Atlas Ct. - Bakersfield, CA 93308 - 661.327.4911 - Fax: 661.327.1918 - www.bclabs.com System # Turnaround # of work days* 3. Received By Other Drinking Water Ground Water Waste Water Sludge Time Chain of Custody Form Date بر $\boldsymbol{\chi}$ 3. Relinquished By (Needed for EDF) হ Global ID 9 x3 3 1365027 400 000 Project Name: Racy Track Send Copy to State of CA? (EDT) 08 □ 19 23 14 23 14 EDF Required? Geotracker ď ☐ Yes ☐ Yes ල Sampler(s): Project #: Same as above Zip Fax: 696-0999 S # 6- 12 23 W 14-30662 Laboratories, Inc. City, State, Zip Scho Cancisco, Street Address: 303 Secon 250€ ガゴじ Attm: Mika Mc FAR. Email Address: Work Order #: Phome: 343 Address: Client: _ City: Attn:



Chain of Custody and Cooler Receipt Form for 1430662 Page 2 of 3

Kennedy/Jenks Consultants

Groundwater Sample Test Methods

						•
Constituent	Test Method ^(a)	Reporting Limit	Container ^(b)	Sample Volume ^(c)	Preservative ^(d)	Holding Time ^(e)
рH	SM4500-HB	0.1 unit	Р	250 ml	None	24 hours
Electroconductivity (EC)	EPA 120.1	1 (µmhos/cm ^(f) @ 25°C)	Р	250 ml	None	28 days
Nitrate - Nitrogen (NO ₃ as N)	EPA 300.0	0.1 mg/l ^(a)	Р	250 ml	None	48 hours
Total Dissolved Solids (TDS)	SM2540C	10 mg/l	P	250 ml	None	7 days
Total Organic Carbon (TOC)	EPA 415.3	1.0 mg/l	Р	250 ml	H₂SO₄ pH<2	28 days
Børon (B)	EPA 200.7	0.1 mg/l	, P	250 mt	HNO ₃ pH<2	6 months
Chloride (CI)	EPA 300.0	0.2 mg/l	Р	250 ml	None	28 days
Calcium (Ca)	EPA 200.7	0.5 mg/l	P	250 ml	HNO ₃ pH<2	6 months
Magnesium (Mg)	EPA 200.7	0.5 mg/l	Р	250 ml	HNO₃ pH<2	6 months
Sodium (Na)	EPA 200.7	0.5 mg/l	P	250 ml	HNO₃ pH<2	6 months
Potassium (K)	EPA 200.7	0.5 mg/l	Р	250 ml	HNO₃ pH<2	6 months
Sulfate (SO ₄)	EPA 300.0	5.0 mg/l	Р	250 ml	None	28 days
Alkalinity as Carbonate (CO ₃)	EPA 310.1	1.0 mg/l	Р	250 ml	None	14 days
Alkalinity as Bicarbonate (HCO ₃)	EPA 310.1	1.0 mg/l	P	250 ml	None	14 days
TPH-Crude Oil (TPHc)	EPA 8015B	0.1 mg/l	G	1000 ml	None	14 days
Øxygen Isotopes	CRDs(in)	Na	G	10 ml	None	1-3 months
Hydrogen Isotopes	CRDS	n/a		10 mil	None /	1-3 months

Notes:

- EPA = U.S. Environmental Protection Agency SM = Standard Methods
- P = Polyethylene; G = Glass
- H₂SO₄ pH<2 = sulfuric acid at pH 2 or less; HNO₃ pH<2 = nitric acid at pH 2 or less
 H₂SO₄ pH<2 = sulfuric acid at pH 2 or less; HNO₃ pH<2 = nitric acid at pH 2 or less
- All samples should be kept at 4 degrees Celsius from the time of collection until analysis.
- µmho/cm = micromhos per centimeter mg/l = milligrams per liter
- (h) Cavity Ring-Down Spectrometer

Phase 2 Investigation Work Plan, Race Track Hill Area Valley Water Management Company, Edison Oil Field, California
GIB-GruppAdminUshtsN1385027.00_WMXC009-RopotalP12-Invesligation-WPlantTablestTable 01 Water Teet Methods_mmx.docs Page 1 of 1



Chain of Custody and Cooler Receipt Form for 1430662 Page 3 of 3

BC LABORATORIES INC. Submission #: リーろい	مادي ا	coo	LER REC	EIPT FOR	RM	Rev. No.	18 09/04	/14 Pa	ge C)f <u> </u>	
SHIPPING INF Federal Express UPS BC Lab Field Service Oth	ORMATION Hand De	livery 🗹		Ice Ch	est 🖺	CONTAI None 🗆	Box 🗆		FREE LIC		
Refrigerant: Ice D Blue le	ce □ Nor	ne 🗆	Other 🗆	Comr	nents:						
CONTROL OF THE PROPERTY OF THE	NED/SECRETARISTS	consumer description									
Custody Seals Ice Chest	Contail Intact? Ye	CHARLEST CONTRACTOR OF A CONTR	None	Com	ments:		· · · · · · · · · · · · · · · · · · ·			i	
All samples received? Yes 💋 No □							tion(s) mate	ch COC? Y	es No		
CØC Received I⊒ YES □ NO	Emissivity:),48 re: (A)	Container:	<i>P</i> € ′′	Thermor	meter ID:	?⊘ } °c	Date/Tim	1 <u>22</u> 3	314 3112	
SAMPLE NUMBERS											
SAMPLE CONTAINERS	1	2	3	4	5	6	7	8	9	10	
QT GENERAL MINERAL/ GENERAL	₽e	D, €			ļ						
PT PE UNPRESERVED			ļ		-						
QT INORGANIC CHEMICAL METALS	1 -	h -			ļ	_	-		-		
PT INORGANIC CHEMICAL METALS	BIC	BIC		<u> </u>						 	
PT CYANIDE				a a			+	 		 	
PT NITROGEN FORMS		 			<u> </u>					1	
PT TOTAL SULFIDE				-			 			ļ	
20z. NITRATE / NITRITE	- 	A		<u> </u>	 						
PT TOTAL ORGANIC CARBON PT TOX	A	<u> </u>				 	1				
PT CHEMICAL OXYGEN DEMAND				-			-				
PtA PHENOLICS			<u> </u>		<u> </u>					 	
40ml VOA VIAL TRAVEL BLANK							·				
40ml VOA VIAL							·			 	
QT EPA 413.1, 413.2, 418.1							1			<u> </u>	
PT ODOR											
RADIOLOGICAL											
BACTERIOLOGICAL											
40 ml VOA VIAL- 504											
QT EPA 508/608/8080											
QT EPA 515.1/8150											
QT EPA 525											
QT EPA 525 TRAVEL BLANK								,			
40ml EPA 547											
40ml EPA 531.1						ļ					
80z Amber EPA 548						ļ					
QT EPA 549				ļ		1				ļ	
QT EPA 632			***			 				ļ	
QT EPA 8015M	F	F									
QT AMBER					ļ		· ·			<u> </u>	
8 OZ. JAR			-	ļ	ļ					<u> </u>	
32 OZ. JAR					ļ			-		-	
SOIL SLEEVE									1		
PCB VIAL					ļ	 				 	
PLASTIC BAG				 	<u></u>	-				 	
FERROUS IRON			*****							+	
ENCORE											
SMART KIT											
Summa Canister			•		<u> </u>	L	<u></u>			<u></u>	
Comments:Completed By:	Cn			<u></u>	<i> </i>		dPerfect\LAB_D				

Report ID: 1000313293

Reported: 01/07/2015 15:06 Project: Race Track Hill Project Number: 1365027*00

Project Manager: Stuart Childs

Laboratory / Client Sample Cross Reference

Client Sample Information Laboratory

Kennedy/Jenks Consultants

San Francisco, CA 94107

303 Second Street, Suite 300

1430662-01 COC Number:

Project Number: Sampling Location:

Sampling Point: RTH #6 - 122314

Sampled By: R. Prince

Sample Depth:

Lab Matrix: Water Sample Type: Wastewater

Metal Analysis: 1-Field Filtered and

Acidified

1430662-02 COC Number:

> **Project Number:** Sampling Location:

Sampling Point: RTH #3 - 122314

Sampled By: R. Prince **Receive Date:**

Receive Date:

Sampling Date:

12/23/2014 11:25 12/23/2014 10:00

Page 6 of 23

12/23/2014 11:25

12/23/2014 08:30

Sampling Date: Sample Depth:

Lab Matrix: Water Sample Type: Wastewater

Metal Analysis: 1-Field Filtered and

Acidified

Report ID: 1000313293

01/07/2015 15:06 Reported: Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430662-01	Client Sample	e Name:	RTH #6 -	122314, 12	2/23/2014 8:30:00	OAM, R. Prin	се	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate	e)	81.3	%	37 - 134 (LC	L - UCL)	EPA-8015B/FFP			1

	Run					QC				
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID			
1	EPA-8015B/FFP	12/26/14	12/27/14 01:06	MWB	GC-2	1	BXL2442			

Page 7 of 23 Report ID: 1000313293

Reported: 01/07/2015 15:06
Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430662-01	Client Samp	le Name:	RTH #6 -	122314, 12	2/23/2014 8:30:	00AM, R. Princ	ce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		390	mg/L	0.10	0.016	EPA-200.7	ND	Quais	1
Total Recoverable Calci	ium	400	mg/L	0.10	0.014	EPA-200.7	ND		2
Dissolved Magnesium		48	mg/L	0.050	0.019	EPA-200.7	ND		1
Total Recoverable Magn	nesium	48	mg/L	0.050	0.019	EPA-200.7	ND		2
Dissolved Sodium		560	mg/L	0.50	0.051	EPA-200.7	ND		1
Total Recoverable Sodi	um	570	mg/L	0.50	0.051	EPA-200.7	ND		2
Dissolved Potassium		21	mg/L	1.0	0.10	EPA-200.7	ND		1
Total Recoverable Pota	ssium	22	mg/L	1.0	0.10	EPA-200.7	ND		2
Bicarbonate Alkalinity a	s CaCO3	190	mg/L	8.2	8.2	EPA-310.1	ND		3
Carbonate Alkalinity as 0	CaCO3	ND	mg/L	8.2	8.2	EPA-310.1	ND		3
Alkalinity as CaCO3		190	mg/L	4.1	4.1	Calc	ND		4
Chloride		1300	mg/L	5.0	0.61	EPA-300.0	ND	A01	5
Nitrate as N		23	mg/L	1.0	0.18	EPA-300.0	ND	A01	5
Sulfate		290	mg/L	10	1.0	EPA-300.0	ND	A01	5
рН		7.34	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivity	@ 25 C	4680	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solids (@ 180 C	3500	mg/L	200	200	SM-2540C	ND	<u> </u>	8
Non-Volatile Organic Ca	arbon	1.2	mg/L	1.0	0.30	EPA-415.1	ND		9

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-200.7	12/23/14	12/30/14 14:50	JRG	PE-OP2	1	BXL2640
2	EPA-200.7	12/31/14	12/31/14 17:44	JRG	PE-OP2	1	BXL2791
3	EPA-310.1	12/26/14	12/26/14 14:46	RML	MET-1	2	BXL2457
4	Calc	12/24/14	01/05/15 07:55	MSA	Calc	1	BXL2326
5	EPA-300.0	12/23/14	12/24/14 07:46	OLH	IC1	10	BXL2337
6	EPA-150.1	12/26/14	12/26/14 14:46	RML	MET-1	1	BXL2457
7	EPA-120.1	12/26/14	12/26/14 14:46	RML	MET-1	1	BXL2457
8	SM-2540C	12/29/14	12/29/14 08:30	CAD	MANUAL	20	BXL2533
9	EPA-415.1	12/24/14	12/24/14 15:08	ALW	TOC2	1	BXL2180

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 8 of 23



Reported: 01/07/2015 15:06 Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1430662-01	Client Sampl	e Name:	RTH #6 -	122314, 12	2/23/2014 8:30	ce		
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
Dissolved Boron		2900	ug/L	100	10	EPA-200.7	ND		1
Total Recoverable Bo	ron	3000	ug/L	100	10	EPA-200.7	ND		2

			Run				QC			
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID			
1	EPA-200.7	12/23/14	12/30/14 14:50	JRG	PE-OP2	1	BXL2640			
2	EPA-200.7	12/31/14	12/31/14 17:44	JRG	PE-OP2	1	BXL2791			

Page 9 of 23 Report ID: 1000313293

Reported: 01/07/2015 15:06 Project: Race Track Hill Project Number: 1365027*00

Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1430662-02	Client Sample	e Name:	RTH #3 -	122314, 12	2/23/2014 10:00:0	0AM, R. Prin	ice	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate	e)	75.5	%	37 - 134 (LC	L - UCL)	EPA-8015B/FFP			1

			Run				QC	
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-8015B/FFP	12/26/14	12/27/14 01:29	MWB	GC-2	1	BXL2442	

Page 10 of 23 Report ID: 1000313293

Reported: 01/07/2015 15:06
Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1430662-02	Client Samp	le Name:	RTH #3 -	122314, 12	2/23/2014 10:00	:00AM, R. Prir	ice	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab	Run#
Dissolved Calcium		170	mg/L	0.10	0.016	EPA-200.7	ND	Quals	1 Rull #
Total Recoverable Calc	cium	170	mg/L	0.10	0.014	EPA-200.7	ND		2
Dissolved Magnesium		84	mg/L	0.050	0.019	EPA-200.7	ND		1
Total Recoverable Mag	jnesium	81	mg/L	0.050	0.019	EPA-200.7	ND		2
Dissolved Sodium		190	mg/L	0.50	0.051	EPA-200.7	ND		1
Total Recoverable Sod	ium	180	mg/L	0.50	0.051	EPA-200.7	ND		2
Dissolved Potassium		22	mg/L	1.0	0.10	EPA-200.7	ND		1
Total Recoverable Pota	assium	22	mg/L	1.0	0.10	EPA-200.7	ND		2
Bicarbonate Alkalinity	as CaCO3	100	mg/L	8.2	8.2	EPA-310.1	ND		3
Carbonate Alkalinity as	CaCO3	ND	mg/L	8.2	8.2	EPA-310.1	ND		3
Alkalinity as CaCO3		100	mg/L	4.1	4.1	Calc	ND		4
Chloride		130	mg/L	1.0	0.12	EPA-300.0	ND	A01	5
Nitrate as N		0.16	mg/L	0.20	0.036	EPA-300.0	ND	J,A10	5
Sulfate		800	mg/L	2.0	0.20	EPA-300.0	ND	A01	5
рН		6.91	pH Units	0.05	0.05	EPA-150.1		S05	6
Electrical Conductivity	@ 25 C	1920	umhos/c m	1.00	1.00	EPA-120.1			7
Total Dissolved Solids	@ 180 C	1500	mg/L	50	50	SM-2540C	ND		8
Non-Volatile Organic C	arbon	3.4	mg/L	1.0	0.30	EPA-415.1	ND		9

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-200.7	12/23/14	12/30/14 15:03	JRG	PE-OP2	1	BXL2640
2	EPA-200.7	12/31/14	12/31/14 17:52	JRG	PE-OP2	1	BXL2791
3	EPA-310.1	12/26/14	12/26/14 14:59	RML	MET-1	2	BXL2457
4	Calc	12/24/14	01/05/15 07:55	MSA	Calc	1	BXL2326
5	EPA-300.0	12/23/14	12/24/14 08:01	OLH	IC1	2	BXL2337
6	EPA-150.1	12/26/14	12/26/14 14:59	RML	MET-1	1	BXL2457
7	EPA-120.1	12/26/14	12/26/14 14:59	RML	MET-1	1	BXL2457
8	SM-2540C	12/29/14	12/29/14 08:30	CAD	MANUAL	5	BXL2533
9	EPA-415.1	12/24/14	12/24/14 15:23	ALW	TOC2	1	BXL2180

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 11 of 23



Reported: 01/07/2015 15:06 Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	, , , , , , , , , , , , , , , , , , , ,					2/23/2014 10:00	nce		
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Boron		670	ug/L	100	10	EPA-200.7	ND		1
Total Recoverable Bo	ron	650	ug/L	100	10	EPA-200.7	ND		2

			Run				QC	
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	12/23/14	12/30/14 15:03	JRG	PE-OP2	1	BXL2640	
2	EPA-200.7	12/31/14	12/31/14 17:52	JRG	PE-OP2	1	BXL2791	

Page 12 of 23 Report ID: 1000313293



San Francisco, CA 94107

Kennedy/Jenks Consultants

Reported: 01/07/2015 15:06
303 Second Street, Suite 300

Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2442						
TPH - Diesel (FFP)	BXL2442-BLK1	ND	ug/L	200	34	
TPH - Crude Oil	BXL2442-BLK1	ND	ug/L	500	140	
Tetracosane (Surrogate)	BXL2442-BLK1	73.3	%	37 - 13	4 (LCL - UCL)	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 13 of 23

 Reported:
 01/07/2015
 15:06

 Project:
 Race Track Hill

 Project Number:
 1365027*00

Project Number: 1365027*00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Laboratory Control Sample

								Control L	imits	
O a markit was not	00.0	-	D	Spike	11	Percent	222	Percent	DDD	Lab
Constituent	QC Sample ID	Туре	Result	Level	Units	Recovery	RPD	Recovery	RPD	Quals
QC Batch ID: BXL2442										
TPH - Diesel (FFP)	BXL2442-BS1	LCS	2003.0	2500.0	ug/L	80.1		52 - 128		
Tetracosane (Surrogate)	BXL2442-BS1	LCS	89.145	100.00	ug/L	89.1		37 - 134		

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 14 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill

Project Number: 1365027*00
Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

Quality Control Report - Precision & Accuracy

									Cont	rol Limits	
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2442	Use	d client samp	le: N								
TPH - Diesel (FFP)	MS	1425343-78	ND	1879.8	2500.0	ug/L		75.2		50 - 127	
	MSD	1425343-78	ND	1647.1	2500.0	ug/L	13.2	65.9	24	50 - 127	
Tetracosane (Surrogate)	MS	1425343-78	ND	88.750	100.00	ug/L		88.8		37 - 134	
	MSD	1425343-78	ND	77.790	100.00	ug/L	13.2	77.8		37 - 134	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 15 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill
Project Number: 1365027*00
Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2180						
Non-Volatile Organic Carbon	BXL2180-BLK1	ND	mg/L	1.0	0.30	
QC Batch ID: BXL2326						
Alkalinity as CaCO3	BXL2326-BLK1	ND	mg/L	4.1	4.1	
QC Batch ID: BXL2337						
Chloride	BXL2337-BLK1	ND	mg/L	0.50	0.061	
Nitrate as N	BXL2337-BLK1	ND	mg/L	0.10	0.018	
Sulfate	BXL2337-BLK1	ND	mg/L	1.0	0.10	
QC Batch ID: BXL2457						
Bicarbonate Alkalinity as CaCO3	BXL2457-BLK1	ND	mg/L	4.1	4.1	
Carbonate Alkalinity as CaCO3	BXL2457-BLK1	ND	mg/L	4.1	4.1	
QC Batch ID: BXL2533						
Total Dissolved Solids @ 180 C	BXL2533-BLK1	ND	mg/L	6.7	6.7	
QC Batch ID: BXL2640						
Dissolved Calcium	BXL2640-BLK1	ND	mg/L	0.10	0.016	
Dissolved Magnesium	BXL2640-BLK1	ND	mg/L	0.050	0.019	
Dissolved Sodium	BXL2640-BLK1	ND	mg/L	0.50	0.051	
Dissolved Potassium	BXL2640-BLK1	ND	mg/L	1.0	0.10	
QC Batch ID: BXL2791						
Total Recoverable Calcium	BXL2791-BLK1	ND	mg/L	0.10	0.014	
Total Recoverable Magnesium	BXL2791-BLK1	ND	mg/L	0.050	0.019	
Total Recoverable Sodium	BXL2791-BLK1	ND	mg/L	0.50	0.051	
Total Recoverable Potassium	BXL2791-BLK1	ND	mg/L	1.0	0.10	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 16 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill
Project Number: 1365027*00
Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Laboratory Control Sample

					-			Control I	imits	
				Spike		Percent		Percent		Lab
Constituent	QC Sample ID	Туре	Result	Level	Units	Recovery	RPD	Recovery	RPD	Quals
QC Batch ID: BXL2180										
Non-Volatile Organic Carbon	BXL2180-BS1	LCS	5.3160	5.0000	mg/L	106		85 - 115		
QC Batch ID: BXL2337										
Chloride	BXL2337-BS1	LCS	50.382	50.000	mg/L	101		90 - 110		
Nitrate as N	BXL2337-BS1	LCS	4.6270	5.0000	mg/L	92.5		90 - 110		
Sulfate	BXL2337-BS1	LCS	100.92	100.00	mg/L	101		90 - 110		
QC Batch ID: BXL2457										
рН	BXL2457-BS2	LCS	7.0500	7.0000	pH Units	101		95 - 105		
Electrical Conductivity @ 25 C	BXL2457-BS1	LCS	300.70	303.00	umhos/cm	99.2		90 - 110		
QC Batch ID: BXL2533										
Total Dissolved Solids @ 180 C	BXL2533-BS1	LCS	555.00	586.00	mg/L	94.7		90 - 110		
QC Batch ID: BXL2640										
Dissolved Calcium	BXL2640-BS1	LCS	10.163	10.000	mg/L	102		85 - 115		
Dissolved Magnesium	BXL2640-BS1	LCS	10.894	10.000	mg/L	109		85 - 115		
Dissolved Sodium	BXL2640-BS1	LCS	10.259	10.000	mg/L	103		85 - 115		
Dissolved Potassium	BXL2640-BS1	LCS	9.9429	10.000	mg/L	99.4		85 - 115		
QC Batch ID: BXL2791										
Total Recoverable Calcium	BXL2791-BS1	LCS	10.334	10.000	mg/L	103		85 - 115		
Total Recoverable Magnesium	BXL2791-BS1	LCS	10.807	10.000	mg/L	108		85 - 115		
Total Recoverable Sodium	BXL2791-BS1	LCS	10.498	10.000	mg/L	105		85 - 115		
Total Recoverable Potassium	BXL2791-BS1	LCS	10.153	10.000	mg/L	102		85 - 115		

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 17 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Precision & Accuracy

									Cont	rol Limits	
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2180	Use	d client samp	ole: N								
Non-Volatile Organic Carbon	 DUP	1430634-01	0.66800	0.47500		mg/L	33.8		10		J,A02
-	MS	1430634-01	0.66800	5.8342	5.0251	mg/L		103		80 - 120	
	MSD	1430634-01	0.66800	5.8090	5.0251	mg/L	0.4	102	10	80 - 120	
QC Batch ID: BXL2337	Use	d client samp	ole: N								
Chloride	 DUP	1430644-01	70.307	70.417		mg/L	0.2		10		
	MS	1430644-01	70.307	125.07	50.505	mg/L		108		80 - 120	
	MSD	1430644-01	70.307	124.94	50.505	mg/L	0.1	108	10	80 - 120	
Nitrate as N	DUP	1430644-01	6.8030	6.8400		mg/L	0.5		10		
	MS	1430644-01	6.8030	12.140	5.0505	mg/L		106		80 - 120	
	MSD	1430644-01	6.8030	12.061	5.0505	mg/L	0.7	104	10	80 - 120	
	DUP	1430644-01	218.71	218.85		mg/L	0.1		10		
	MS	1430644-01	218.71	324.10	101.01	mg/L		104		80 - 120	
	MSD	1430644-01	218.71	323.85	101.01	mg/L	0.1	104	10	80 - 120	
QC Batch ID: BXL2457	Use	d client samp	ole: Y - Des	cription: RT	H #6 - 1223	314, 12/23/2	2014 08	3:30			
Bicarbonate Alkalinity as CaCO3	DUP	1430662-01	188.95	189.86		mg/L	0.5		10		
Carbonate Alkalinity as CaCO3	DUP	1430662-01	ND	ND		mg/L			10		
ЬН	DUP	1430662-01	7.3400	7.3500		pH Units	0.1		20		
Electrical Conductivity @ 25 C	DUP	1430662-01	4676.7	4557.1		umhos/cm	2.6		10		
QC Batch ID: BXL2533	Use	d client samp	ole: Y - Des	cription: RT	H #6 - 1223	314, 12/23/2	2014 08	3:30			
Total Dissolved Solids @ 180 C	DUP	1430662-01	3520.0	3600.0		mg/L	2.2		10		
QC Batch ID: BXL2640	Use	d client samp	ole: Y - Des	cription: RT	H #6 - 1223	314, 12/23/2	2014 08	3:30			
Dissolved Calcium	─ DUP	1430662-01	388.52	390.55		mg/L	0.5		20		
	MS	1430662-01	388.52	392.25	10.204	mg/L		36.5		85 - 115	A03
	MSD	1430662-01	388.52	391.32	10.204	mg/L	0.2	27.4	20	85 - 115	A03
Dissolved Magnesium	DUP	1430662-01	47.934	47.971		mg/L	0.1		20		
-	MS	1430662-01	47.934	57.247	10.204	mg/L		91.3		85 - 115	
	MSD	1430662-01	47.934	57.746	10.204	mg/L	0.9	96.2	20	85 - 115	
Dissolved Sodium	DUP	1430662-01	563.18	567.66		mg/L	0.8		20		
	MS	1430662-01	563.18	559.21	10.204	mg/L		-38.9		85 - 115	A03
	MSD	1430662-01	563.18	564.55	10.204	mg/L	1.0	13.4	20	85 - 115	A03
		4420000 04	21.213	21.253		mg/L	0.2		20		
Dissolved Potassium	DUP	1430662-01	21.210								
Dissolved Potassium	DUP MS	1430662-01	21.213	31.191	10.204	mg/L		97.8		85 - 115	

QC Batch ID: BXL2791

Used client sample: Y - Description: RTH #5 - 122114, 12/21/2014 14:30

Report ID: 1000313293 4100 Atlas Court Ba

Reported: 01/07/2015 15:06 Project: Race Track Hill

Project Number: 1365027*00
Project Manager: Stuart Childs

Water Analysis (General Chemistry)

Quality Control Report - Precision & Accuracy

	·								Cont	rol Limits	
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2791	Use	d client samp	ole: Y - Des	cription: RT	H #5 - 1221	14, 12/21/	2014 14	1:30			
Total Recoverable Calcium	DUP	1430572-01	63.986	63.890		mg/L	0.1		20		
	MS	1430572-01	63.986	70.525	10.000	mg/L		65.4		75 - 125	A03
	MSD	1430572-01	63.986	73.377	10.000	mg/L	4.0	93.9	20	75 - 125	
Total Recoverable Magnesium	DUP	1430572-01	22.926	22.876		mg/L	0.2		20		
	MS	1430572-01	22.926	31.913	10.000	mg/L		89.9		75 - 125	
	MSD	1430572-01	22.926	32.989	10.000	mg/L	3.3	101	20	75 - 125	
Total Recoverable Sodium	DUP	1430572-01	51.368	51.063		mg/L	0.6		20		
	MS	1430572-01	51.368	58.987	10.000	mg/L		76.2		75 - 125	
	MSD	1430572-01	51.368	61.380	10.000	mg/L	4.0	100	20	75 - 125	
Total Recoverable Potassium	DUP	1430572-01	6.4494	6.3864		mg/L	1.0		20		
	MS	1430572-01	6.4494	16.206	10.000	mg/L		97.6		75 - 125	
	MSD	1430572-01	6.4494	16.614	10.000	mg/L	2.5	102	20	75 - 125	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 19 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill
Project Number: 1365027*00
Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Method Blank Analysis

Constituent	QC Sample ID	MB Result	Units	PQL	MDL	Lab Quals
QC Batch ID: BXL2640						
Dissolved Boron	BXL2640-BLK1	ND	ug/L	100	10	
QC Batch ID: BXL2791						
Total Recoverable Boron	BXL2791-BLK1	ND	ug/L	100	10	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 20 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill
Project Number: 1365027*00
Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Laboratory Control Sample

Constituent	QC Sample ID	Type	Result	Spike Level	Units	Percent Recovery	RPD	Control L Percent Recovery	Lab Quals
QC Batch ID: BXL2640									
Dissolved Boron	BXL2640-BS1	LCS	1001.3	1000.0	ug/L	100		85 - 115	
QC Batch ID: BXL2791									
Total Recoverable Boron	BXL2791-BS1	LCS	1021.5	1000.0	ug/L	102		85 - 115	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 21 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Metals Analysis

Quality Control Report - Precision & Accuracy

									Con	trol Limits	
		Source	Source		Spike			Percent		Percent	Lab
Constituent	Type	Sample ID	Result	Result	Added	Units	RPD	Recovery	RPD	Recovery	Quals
QC Batch ID: BXL2640	Use	d client samp	le: Y - Des	cription: RT	H #6 - 1223 ⁻	14, 12/23/	2014 08	3:30			
Dissolved Boron	D UP	1430662-01	2880.9	2866.2		ug/L	0.5		20		
	MS	1430662-01	2880.9	3922.7	1020.4	ug/L		102		85 - 115	
	MSD	1430662-01	2880.9	3897.5	1020.4	ug/L	0.6	99.6	20	85 - 115	
QC Batch ID: BXL2791	Use	d client samp	le: Y - Des	cription: RT	H #5 - 1221	14, 12/21/	2014 14	4:30			
Total Recoverable Boron	DUP	1430572-01	66.183	65.663		ug/L	8.0		20		J
	MS	1430572-01	66.183	1064.4	1000.0	ug/L		99.8		75 - 125	
	MSD	1430572-01	66.183	1093.1	1000.0	ug/L	2.7	103	20	75 - 125	

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 22 of 23

Reported: 01/07/2015 15:06
Project: Race Track Hill
Project Number: 1365027*00
Project Manager: Stuart Childs

Notes And Definitions

J Estimated Value (CLP Flag)

MDL Method Detection Limit

ND Analyte Not Detected at or above the reporting limit

PQL Practical Quantitation Limit

RPD Relative Percent Difference

A01 PQL's and MDL's are raised due to sample dilution.

A02 The difference between duplicate readings is less than the PQL.

A03 The sample concentration is more than 4 times the spike level.

A10 PQL's and MDL's were raised due to matrix interference.

S05 The sample holding time was exceeded.

Report ID: 1000313293 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 23 of 23

Christopher J. Eastoe, Ph.D. Staff Scientist 520-621-1638 (office) 520-621-2672 (fax) eastoe@email.arizona.edu



Laboratory of Isotope Geochemistry Department of Geosciences Gould-Simpson Building 1040 E. 4th Street, Building No. 0077 Tucson, Arizona 85721-0077, USA

Mr. Mike McLeod Kennedy Jenks Inc. 303 Second St. San Francisco CA 94107 mikemcleod@kennedyjenks.com January 16, 2014

REPORT OF ANALYSES 5 water samples for O and H isotopes,

W	Sample		δ ¹⁸ Ο ‰	δD ‰
61248	RTH #5	-122114	-8.8	-64
61249	RTH #4	-122114	-6.8	-58
61250	RTH #1	-122114	-6.2	-54
61251	RTH#6	-122314	-5.8	-56
61252	RTH #3	-122314	-6.7	-60

Analytical precision, 1-sigma

60.08

0.9

C.J.Eastoe

Staff Scientist

Appendix C

Report on Installation of Deep Monitor Wells at the Valley Water Management Company Race Track Hill and Plant-C Facilities in Kern County

REPORT ON INSTALLATION OF DEEP MONITOR WELLS AT VALLEY WATER MANAGEMENT COMPANY RACETRACK HILL AND PLANT-C FACILITIES IN KERN COUNTY

prepared for Dee Jaspar and Associates Bakersfield, California

by
Kenneth D. Schmidt and Associates
Groundwater Quality Consultants
Bakersfield, California

KENNETH D. SCHMIDT AND ASSOCIATES

GROUNDWATER QUALITY CONSULTANTS 3701 PEGASUS DRIVE, SUITE 112 BAKERSFIELD, CALIFORNIA 93308 TELEPHONE (661) 392-1630

June 24, 2015

Mr. Dee Jaspar Dee Jaspar and Associates 2730 Unicorn Rd, Building A Bakersfield, CA 93308-6843

Re: Deep Monitor Wells at Valley Water Management Racetrack Hill and Plant-C Facilities

Dear Dee:

Submitted herewith is our report on the installation and initial testing of the deep monitor wells at the Valley Water Management Company Racetrack Hill and Plant-C Facilities in Kern County. We appreciate your assistance and the cooperation of Bradley & Sons of Del Rey in conducting this work.

Sincerely Yours,

Kenneth D. Schmidt Geologist No. 1578

Certified Hydrogeologist

No. 176

KDS/td



TABLE OF CONTENTS

	Page			
LIST OF TABLES	ii			
LIST OF ILLUSTRATIONS	iii			
INTRODUCTION	1			
WELL INSTALLATION	4			
SUBSURFACE GEOLOGIC CONDITIONS Racetrack Hill Facility Plant-C Facility	5 5 7			
WELL DEVELOPMENT	7			
WATER LEVELS	8			
GROUNDWATER QUALITY Racetrack Hill Facility Plant-C Facility				
SUMMARY AND CONCLUSIONS	16			
REFERENCES	18			
ATTACHMENT A GEOPHYSICAL LOGS				
ATTACHMENT B GEOLOGIC LOGS				
ATTACHMENT C WELL COMPLETION DIAGRAMS				
ATTACHMENT D WELL COMPLETION REPORTS				
ATTACHMENT E WELL SURVEY DATA				
ATTACHMENT F FIELD MEASUREMENTS FOR WELL SAMPLING				
ATTACUMENT C IABODATODY ANALYTICAL SUFFERS				

LIST OF TABLES

No.	Title	Page
1	Construction Data for Deep Monitor Wells	6
2	Water-Level Data for Deep Monitor Wells (March 17, 2015)	9
3	Chemical Analyses of Water from Deep Monitor Wells (March 11-17, 2015)	12

LIST OF ILLUSTRATIONS

<u>No.</u>	Title	Page
1	Location of Racetrack Hill Facility, and Shallow and	
	Deep Monitor Wells	2
2	Location of Plant-C Facility and Deep Monitor Well	3
3	Water-Level Elevations and Direction of Deep Ground- water Flow for Racetrack Hill Facility (March 17,	
	2015)	10
4	Trilinear Diagram for Water from Shallow and Deep	
	Monitor Wells	15

REPORT ON INSTALLATION OF DEEP MONITOR WELLS AT VALLEY WATER MANAGEMENT COMPANY RACETRACK HILL AND PLANT-C FACILITIES IN KERN COUNTY

INTRODUCTION

In October 2014, Kenneth D. Schmidt and Associates (KDSA) provided a workplan for installation of deep monitor wells at Valley Water Management Company (VWM) Racetrack Hill and Plant-C Facilities. The wells were installed and developed during January-February, 2015, and the initial monitoring was completed in March 2015. Three deep monitor wells were installed, developed, and tested at the Racetrack Hill facility. All of those are located near wastewater ponds. The Racetrack Hill facility is located east of Bakersfield in part of Section 24, T29S/R29E. Figure 1 shows the location of the facility and the deep monitor wells (RTH-7D, RTH-8D, and RTH-9D). All of these wells were installed adjacent to a previously completed shallow monitor well (Kennedy/Jenks Consultants, 2015). RTH-7D was installed adjacent to RTH-6, RTH-8D was installed adjacent to RTH-1.

One deep monitor well was installed, developed, and tested at the Plant-C facility. The Plant-C facility is located north of Edison near the southwest corner of Section 34, T29S/R29E. Figure 2 shows the location of this facility and the deep monitor well (C-1D), which is located southwest of a pond. A shallow well was




FIGURE 1 - LOCATION OF RACETRACK HILL FACILITY, AND SHALLOW AND DEEP MONITOR WELLS




FIGURE 2 - LOCATION OF PLANT-C FACILITY AND DEEP MONITOR WELL

not previously installed at the Plant-C facility because of the great depth to water (exceeding 200 feet) that was documented by an exploratory boring.

WELL INSTALLATION

Bradley & Sons of Del Rey installed the deep monitor wells by the direct rotary method during January 26-February 24, 2015. An electric log and sonic log were run in the hole for each new monitor well (Attachment A). A geologic log for each monitor well is provided in Attachment B and a completion diagram for each well is provided in Attachment C.

At the Racetrack Hill facility, saturated deposits at the time of drilling were indicated below depths ranging from about 70 to 155 feet. At the Plant-C facility, saturated deposits were indicated below a depth of 270 feet. Deposits opposite the perforated intervals of the new wells were primarily alternating layers of sand, gravel, and sandy clay. A five-inch diameter Schedule 40 PVC casing was installed in a twelve-inch diameter hole for each deep well at the Racetrack Hill facility. At the Plant-C facility, a five-inch diameter Schedule 80 PVC casing was installed in a twelve-inch diameter hole. Flush joints and threaded ends were used and all joints for the casing were made using clean couplings. No glue or solvents were used in connecting the casing

joints. Machine-cut 0.03-inch slot factory perforated was used for the perforated sections. Table 1 shows construction information for the deep monitor wells.

The tops of the perforations in the Racetrack Hill facility wells ranged from 191 to 312 feet in depth and the bottoms of the perforations ranged from are 210 to 350 feet in depth. The top of the perforations are 395 feet and the bottom of the perforations are 435 feet in depth at the Plant-C facility deep well. For all of the deep monitor wells, SRI 6x20 sand was used for the gravel packs, which were placed in the annular space from the bottom up to depths extending above the tops of the perforations. Four to six feet of bentonite were placed in the annular space above the tops of the gravel packs, and sand-cement grout was installed above the bentonite. The base of the annular seals in the deep wells ranged from 168 to 381 feet in depth and the seals extended up to the land surface. Completion reports for the wells are provided in Attachment D.

SUBSURFACE GEOLOGIC CO'NDITIONS

Racetrack Hill Facility

A subsurface geologic cross section was previously developed that extended through the western and northern parts of the facility. The shallowest deposits beneath the facility are part of the Kern River-Chanac Formation and are generally unconsolidated.

TABLE 1-CONSTRUCTION DATA FOR DEEP MONITOR WELLS

Well No.	Date Completed	Drilled Depth (feet)	Cased Depth (feet)	Perforated Int. (feet)	Gravel Pack feet)	Annular Seal (feet)
RTH-7D	2/11/15	360	330	282-330	223-340	0-223
RTH-8D	1/28/15	260	210	191-210	168-210	0-168
RTH-9D	2/17/15	360	350	312-350	289-360	0-289
C-1D	2/24/15	460	435	395-435	381-455	0-381

Monitor wells were constructed by Bradley & Sons of Del Rey and have 5-inch diameter PVC casings. Schedule 40 was used for the first three wells, and Schedule 80 for C-1D.

These alluvial deposits dip to the southwest beneath the facility. These deposits pinch out east of the facility and are indicated to be about 700 feet thick near the west edge of the facility.

The next deeper deposits beneath the facility are the marine Santa Margarita Formation. These deposits are indicated to extend to a depth of about 800 feet near the northeast corner of the facility and to a depth of about 1,500 feet near the west edge of the facility. Beneath the Santa Margarita Formation is the Edison Shale, which is of low permeability and forms the base of the aquifer. Comparison of the logs for the deep monitor wells with the cross section indicates that RTH-8D encountered the top of the Santa Margarita Formation at a depth of about 140 feet. The other two deep monitor wells at the Racetrack Hill facility only encountered deposits of the Kern River-Chanac Formation.

Plant-C Facility

At the Plant-C facility, the top of the Santa Margarita Formation is more than 1,200 feet deep. Water supply wells in this area and the deep monitor well (C-1D) tap deposits of the overlying Kern River-Chanac Formation.

WELL DEVELOPMENT

Bradley & Sons developed the perforated intervals in each of the monitor wells by bailing with a bailer. On January 29, RTH-8D was for bailed for three hours and on February 12, RTH-7D was bailed for three hours. On February 18, RTH-9D was bailed five hours, and on February 25, C-1D was bailed six hours. After this preliminary development was completed, a submersible pump was installed in each of the wells, and development continued by pumping and surging until the water was clear. RTH-8D was pumped and surged for two hours on February 5, RTH-7D for four hours on February 13, RTH-9D for four hours on February 24, and C-1D for six hours on February 25-26. Pumping rates ranged from about 5 to 15 gpm.

WATER LEVELS

Table 2 provides water-level data for the deep monitor wells on March 17, 2015. Depth to water in the deep monitor wells at Racetrack Hill facility ranged from 86.9 feet below the measuring point at RTH-8D to 225.3 feet at RTH-9D. Depth to water in C-1D at the Plant-C facility was 298.4 feet below the measuring point. Considering the depths where saturated deposits were indicated during drilling, the higher water levels in the completed wells indicate that the groundwater tapped by the wells is under pressure. Dee Jaspar and Associates, Inc. of Bakersfield surveyed the

TABLE 2-WATER-LEVEL DATA FOR DEEP MONITOR WELLS (MARCH 17, 2015)

	Measuring Point	Depth to	Water-Level
Well No.	Elevation (feet)	Water (feet)	Elevation (feet)
RTH-7D	1,061.8	207.5	854.3
RTH-8D	874.7	86.9	787.8
RTH-9D	1,025.2	225.3	799.9
C-1D	635.5	298.4	337.1

Water levels were measured by KDSA. Measuring point elevations were surveyed by Dee Jaspar and Associates, Inc., of Bakersfield on March 20, 2015.

elevations of the new wells (Attachment E). Water-level elevations for the monitor wells at the Racetrack Hill facility ranged from 854.3 feet above mean sea level at RTH-7D to 787.8 feet at RTH-8D. Figure 3 shows water-level elevations and the direction of groundwater flow for the deep monitor wells at the Racetrack Hill facility on March 17, 2015. A north-northwest direction of groundwater flow was indicated. This indicates that pumping of wells north-northwest of the facility has influenced the flow direction. The water-level slope averaged about 130 feet per mile beneath the facility. The water-level elevation in C-1D at the Plant-C facility was 337.1 feet above mean sea level.

GROUNDWATER QUALITY

Attachment F provides field measurements for the initial sampling of the deep monitor wells, which was done during March 11-17, 2015. Three well volumes were removed by pumping from each well prior to the collection of water samples for laboratory analyses. The samples were preserved and shipped to FGL Environmental in Santa Paula for determination of inorganic chemical constituents and total organic carbon (TOC), to APPL, Inc. in Clovis for total petroleum hydrocarbons-diesel (TPH-d), and to the University of Arizona Environmental Isotope Laboratory, Tucson, Arizona for stable isotopes of water.






FIGURE 3 - WATER-LEVEL ELEVATIONS AND DIRECTION OF DEEP GROUNDWATER FLOW FOR RACETRACK HILL FACILITY (MARCH 17, 2015)

Table 3 summarizes the results of the laboratory analyses of water from the deep monitor wells. Laboratory analytical reports are provided in Attachment G.

Racetrack Hill Facility

Total dissolved solids (TDS) concentrations in the water samples from the deep monitor wells at this facility ranged from 2,960 to 4,180 mg/l. The lowest TDS concentration was at RTH-9D, and the highest (3,900 to 4,180 mg/l) were in water from RTH-7D and RTH-8D. Chloride concentrations in water from these wells ranged from 820 to 2,060 mg/l. The chloride concentration was highest in water from RTH-8D and was lowest in water from RTH-9D. Boron concentrations in water from these wells ranged from 0.2 to 9.1 mg/l. The lowest boron concentrations (0.2 to 0.3 mg/l) were in water from wells RTH-7D and RTH-9D, and the highest concentration was in water from RTH-8D. Sulfate concentrations in water from these wells ranged from 23 to 910 mg/l. The lowest sulfate concentration was for RTH-8D and the highest concentrations (860 to 910 mg/l) were in water from RTH-7D and RTH-9D. Sulfate type groundwater was previously found at RTH-3, a shallow monitor well south of RTH-8D. Total petroleum hydrocarbon-diesel (TPH-d) concentrations ranged from less than 50 to 280 ppb. The only detectable TPH-d concentration was in RTH-8D. Stable isotopes of water analyses indicate that the isotopically heaviest water was in

TABLE 3-CHEMICAL ANALYSES OF WATER FROM DEEP MONITOR WELLS (MARCH 11-17, 2015)

Constituent (mg/l)	RTH-7D	RTH-8D	RTH-9D	C-1D
Calcium	535	514	464	101
Magnesium	104	161	26	18
Sodium	411	376	321	130
Potassium	35	14	17	4
Carbonate	<10	<10	<10	<10
Bicarbonate	320	310	210	280
Sulfate	910	23	860	110
Chloride	1,250	2,060	820	229
Nitrate	0.4	2.7	1.0	<0.5
Total Organic Carbon	0.5	0.8	0.5	0.9
Boron	0.3	9.1	0.2	0.2
рН	6.6	6.6	7.0	7.2
Electrical Conductivity				
(micromhos/cm @ 25°C)	5,420	6,490	4,000	1,400
Total Dissolved Solids				
(@ 180°C)	3,900	4,180	2,960	800
Iron	0.54	<0.05	<0.05	<0.05
Manganese	1.13	0.11	0.79	0.88
Deuterium (°/00)	-60	-60	-65	-68
Oxygen 18 (°/00)	-6.2	-7.4	-7.4	-8.4
Total Petroleum				
Hydrocarbons-Diesel (ppb)	<50	280	<50	<50
Temperature (°F)	79	71	77	80
Date	3/16/15	3/11/15	3/17/15	3/17/15
Perforated Interval (feet)	282-330	191-210	312-350	395-435

Laboratory analyses for inorganic chemical constituents and total organic carbon by FGL of Santa Paula, total petroleum hydrocarbons-diesel by APPL of Clovis, and stable isotopes by University of Arizona Environmental Isotope Laboratory, Tucson, Arizona.

water from RTH-7D and RTH-8D.

The quality of water from RTH-8D has been affected by the wastewater ponds, as indicated by the high concentrations of chloride, boron, and TPH-diesel.

Figure 4 is a trilinear diagram for water from the shallow and deep monitor wells at the Racetrack Hill facility and some other wells in the vicinity. The anion part of the diagram is considered most useful for interpretation, as the anions aren't influenced by processes such as cation exchange. Four different water types can be observed on the anion part of the diagram:

- Greater than 80 percent chloride equivalents (RTH-1, 4, 6, and 8D). All of these monitor wells with this type are near facility wastewater ponds.
- 2. Chloride percentage less than 20 and sulfate percentage of 40 to 60 (RTH-5). RTH-5 taps shallow groundwater along Cotton-wood Creek that has been not influenced by facility wastewater. Two off-site wells along Cottonwood Creek (12F and 26B) also had this water type.
- 3. Sulfate percentage of about 80 (RTH-3). RTH-3 taps shallow groundwater along the drainage along the east side of the facility. The inorganic chemical composition of this groundwater is similar to that of shallow groundwater along the west side of the San Joaquin Valley, where gypsum is common in the alluvial deposits.




FIGURE 4-TRILINEAR DIAGRAM FOR WATER FROM WELLS

4. Chloride percentages ranging from about 50 to 60 and bicarbonate percentages of less than 10 (RTH-7D and 9D). RTH-7D and 9D are two deep monitor wells along the western part of the facility. Water from these two wells is indicated to be a mixture of the high sulfate percent (RTH-3) and high chloride percent groundwater (RTH-1, 4, and 6).

A water sample was recently collected from Domestic Well 26B, located along Cottonwood Creek upstream of RTH-5. Well 26B taps groundwater in the Santa Margarita Formation. A water sample was also collected from an unused Well 12F tapping alluvial deposits along Cottonwood Creek near Highway 178. The analyses of water from these wells indicates that high sulfate concentrations are present in background groundwater near Cottonwood Creek.

Plant-C Facility

Water from C-1D had a TDS concentration of 800 mg/l, chloride concentration of 229 mg/l, and boron concentration of 0.2 mg/l, all of which are not indicative of facility pond seepage. The anion percentages in water from C-1D aren't similar to either the high chloride water, the high sulfate water, or the apparent mixtures of the water types at the Racetrack Hill facility. The stable isotope of water analysis C-1D indicated the isotopically lightest composition of all of the deep monitor wells.

SUMMARY AND CONCLUSIONS

Three monitor wells were installed at the Racetrack Hill facility and one deep monitor well was installed at the Plant-C facility in February 2015. At the Racetrack Hill facility, each of the deep monitor wells was adjacent to an existing shallow monitor well. The deep monitor wells at the Racetrack Hill facility ranged from 210 feet deep in a topographically low area (RTH-8D) to 340 to 360 feet deep in topographically higher areas (RTH-7D and 9D). The northeastermost and lowest elevation deep well (RTH-8D) is indicated to tap the Santa Margarita Formation, whereas the other two deep monitor wells (RTH-7D and 9D) tap the overlying deposits of the Kern River-Chanac Formation. The monitor well at the Plant-C facility is 435 feet deep and also taps the Kern River-Chanac Formation.

Water-level measurements for the deep monitor wells on March 17, 2015 indicated depth to water ranged from about 87 to 225 feet at the Racetrack Hill facility and was about 298 feet at the Plant-C facility. The direction of groundwater flow at the Racetrack Hill facility was indicated to be to the north-northwest on March 17, 2015. The hydraulic gradient was about 130 feet per mile beneath the facility.

Total dissolved solids concentrations in water from the deep monitor wells at the Racetrack Hill facility ranged from 2,960 to

4,180 mg/l. Chloride concentrations ranged from 820 to 2,060 mg/l. A trilinear plot for anions (generally not influenced by exchange processes such as cations) indicates that water from RTH-8D was of same type as that for the nearby shallow monitor well (RTH-4). ter from both of these wells is indicated to have been influenced by wastewater pond seepage. Whereas the sulfate concentration in water from RTH-8D was low (23 mg/l), sulfate concentrations in water from RTH-7D and 9D ranged from 860 to 910 mg/l. The higher sulfate concentrations are not indicated to be associated with wastewater and are likely derived from naturally occurring processes. Appreciable sulfate concentrations have also been found in two off-site wells along Cottonwood Creek that haven't been affected by facility operations. At RTH-8D, the low sulfate concentration is indicated to be due to sulfate reduction. Reducing conditions have commonly been found in shallow groundwater beneath oil wastewater ponds. Water from RTH-7D and 9D thus appears to be a mixture of the high sulfate native groundwater and wastewater applied for irrigation. When the wastewater has been applied for irrigation, oxidizing conditions can be expected in the shallow groundwater.

The TDS concentration in water from C-1D was 800 mg/l and the chloride concentration was 110 mg/l, indicated to be at background levels in groundwater in the vicinity. Thus the results of sampling C-1D are indicative of no influence of the wastewater ponds in the vicinity of this well.

REFERENCES


Kennedy/Jenks Consultants, 2015, "Phase 1 Subsurface Investigation at the Field 34 Facility and Racetrack Hill Area, Edison Oil Field, California", 23 p.

Kenneth D. Schmidt and Associates, 2014, "Workplan for Deep Monitor Wells at Valley Water Management Company Racetrack Hill and Plant-C Facilities in Kern County", 17 p.

ATTACHMENT A GEOPHYSICAL LOGS

-	V in	1		
144		en	0	-
WW				

			ELEC	TRIC	LOG				
FILING N		4DANIX	Bradley & Sons	Drilling					
	CON	IF ANT	A Company of the Comp		DTU 7	D (0 U-)			-
	WEL	.L	Valley Water Ma	nagement C	D. KIH-/	D (South)			_
	FIEL	.D	Racetrack Hill						_
	STA	TE _	California	COUNTY Kern					
1.5 Miles Northeast of Commar 0.1 Mile North of Breckenridge				Brecker	nridge Road.	Sor	ER SERVICES: nic		
ЈОВ NO 17674		4M TMD. 29	S RGE: 29E LAT.		LONG		EDIDIAN		
Permanen			d Level			W		K B	E+
1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	ured From:		d Level	•		Perm. Datum		D.F	
24 10 25 10 CO. 10 A.	easured Fro	n: Groun	d Level					G.L.	
Run		One							
Date		Feb. 0	6, 2015						
Depth-Drill	er	360	Ft		Ft		Ft		Ft
Depth-Log	ger	360	Ft		Ft		Ft		Ft
Top Logge	d Interval	7	Ft		Ft		Ft		Ft
Btm. Logge	ed Interval	359	Ft		Ft		Ft		Ft
Casing-Dri	ller	None	n@ Ft	In @	Ft	In @	Ft	In @	Ft
Casing-Log	gger	None		In @	Ft	In @	Ft	t In @	
Bit Size		8.75	In		In		In		In
Time On B	ottom	10:45							
Type Fluid	In Hole	Bentor	nite						
Density	Viscosity	N/A	N/A						
рН	Fluid Loss	N/A	N/A ml		ml		ml		ml
Source of Sa	mple	Pit							
Rm @ Meası	ired Temp.	4.5	@ 75 °F	@	°F	@	°F	@	°F
Rmf @ Meas	ured Temp.	3.9	@ 75 °F	@	°F	@	°F	@	°F
Rmc @ Meas	sured Temp.	N/A	@ °F	@	°F	@	°F	@	°F
Source Rm	f Rmc	Meas	N/A	==	11				
Rm @BHT	71	N/A	@ °F	@	°F	@	°F	@	°F
Time Since	e Circulation	1	Hr		Hr		Hr		H
Max. Rec.	Temp.	N/A	°F		°F		°F		°F
Van No.	Location	LV-1	Bfld						
Recorded	Ву	David	Jackson						
Witnessed	Ву	Jim Ar	igell						




Phone: (800) 445-9914 Fax: (661) 834-2550 Email: welenco@welenco.com Web: www.welenco.com (Prepared with Log Print, a professional software application developed by welenco, inc.)

CA. Contractor's License: 722373

12 21 22	7	
wel	OM	00
- VV 🗀 I		

			SO	NI	C-VD	L-P	OROSI	TY LC	G		
FIL	ING NO.	001	/PANY	Bra	dley & Son	s Drill	ina				
		A STATE OF	<i>M</i> 100 5 8 -	3.00			on or Ar war	7D (Courth	· ·		
		WEL	.L _	119	Contraction of the		ement Co. RTH	-10 (South)		-
		FIEL	.D _	Rac	etrack Hill						
		STA	TE _	Cali	fornia		COUNTY	Kern			
		1.5 N			st of Comn Breckenrid		e Drive & Brecl ad.	kenridge R		OTHER SER Elog	VICES:
	7674 si	EC: _2	4M TWP: 2	98 F	RGE: 29E LA	AT.:	LONG	:	MERIDIA	N.:	
Perm	anent Datun	n:	Groun				, Elev		Ft.	Elev.: K.E	Ft.
	Measured Fr		Groun		1131	,_	0 Ft. Abov	e Perm. Da	atum		Ft.
Drillir	ng Measured	d Fro								G.I	Ft.
Date			Feb. 0	-	15						
Туре	Of Log		Sonic								
Run			One								
Depth	-Driller		360		Ft		Ft		F	t	Ft
Depth	-Logger		360		Ft		Ft		F	Ft	
Top L	ogged Interv	al	7		Ft		Ft		F	Ft F	
Btm. I	_ogged Interv	val	359		Ft		Ft	Ft		Ft Ft	
Туре	Fluid In Hole		Bento	nite							
Flui	id Level		Full		Ft		Ft		F	t	Ft
Max T	emp		N/A		°F		°F		°F		°F
Opera	ting Rig Tim	е	.5		Hr		Hr		н	r	Hi
Van N	lo. Locati	ion	LV-1	В	fld						
Recor	ded By		David	Jack	son						
Witne	ssed By		Jim A	ngell							
RUN	В	OREH	HOLE RE	COR	D			CASI	NG RECO	RD	
NO.	BIT		FROM	1	то		SIZE	TYPE	FR	ОМ	то
1	8.75	In	0	Ft	360	Ft	None In			Ft	Ft
2		In		Ft		Ft	ln			Ft	Ft
3		In		Ft		Et	In			Ft	Et



Phone: (800) 445-9914 Fax: (661) 834-2550 Email: welenco@welenco.com Web: www.welenco.com (Prepared with Log Print, a professional software application developed by welenco, inc.)

CA. Contractor's License: 722373

	70	en	00
- 1/1/			
			VV

			ELE	CTRIC	LOG				
FILING NO.		DANIV	Bradley & Soi	ns Drilling					
	COM	PANY _			0 5711.05	ALC: NO SERVICES			-
	WEL	L _	Valley Water I	Management	Co. RTH-8D	(Northeast)			
	FIEL	D _	Racetrack Hil						
	STAT	re _	California		COUNTY_	Kern			
	LOCA	TION:			A Second		ОТН	ER SERVICES:	
			heast of Coma		Breckenric	lge Road,	So	nic	
JOВ NO. 17665									
	Charles of the Control					MER		0.76.00	Sed.
Permanent	7777		id Level			F1	. Ele		
Log Measur Drilling Mea	ACTOR AND ACTOR			_,	t. Above P	erm. Datum		D.F	
	isurea Fron	10000	iu Levei					G.L	Ft.
Run Date		One	7, 2015				-		
Date Depth-Driller		260	7, 2015 Ft		Ft		Ft		F
Depth-Logge		256	Ft		Ft		Ft		F
Top Logged		27			Ft		Ft		F
Btm. Logged		255	Ft		Ft		Ft		F
Casing-Drille		N/A	In @ Ft	In @	Ft	In @	Ft	In @	
Casing-Logg	jer		In @ Ft	ln @	Ft	In @	Ft	In @	F
Bit Size		8.75	In		In		In		Ir
Time On Bot	tom	11:30							
Type Fluid Ir	n Hole	Bento	nite						
Density	Viscosity	N/A	N/A						
рН	Fluid Loss	N/A	N/A ml		ml		ml		m
Source of Sam	ple	Pit							
Rm @ Measure	ed Temp.	6.7	@ 75 °F	@	°F	@	°F	@	°F
Rmf @ Measur	ed Temp.	5.8	@ 75 °F	@	°F	@	°F	@	°F
Rmc @ Measur	red Temp.	N/A	@ °F	@	°F	@	°F	@	٥
Source Rmf	Rmc	Meas	N/A				- 6		
Rm @ BHT		N/A	@ °F	@	°F	@	°F	@	٥١
Time Since (Circulation	.5	Нг		Hr		Hr		Н
Max. Rec. T	emp.	N/A	°F		°F		°F		۰۱
Van No. L	ocation	LV-3	Bfld			1			
Recorded By	y	David	Jackson						
Witnessed B	Ву	Jim A	ngell	_					

(Prepared with Log Print, a professional software application developed by welenco, inc.)

CA. Contractor's License: 722373



	- Marie Marie	No. of	S	INC	C LOG					
FILI	W	ELL V	radley & So alley Water I acetrack Hil	Manage	ing ement Co. RTI	H-8D (Northea	ast)			
	2.5	CATION:			COUNT	Arc en las	E	THER SER	VICES:	
	B NO. 7665 SEC:	24C TWP: 29S	RGE: 29E L	AT.:	LONG	3.:	_ MERIDIAN			
Log M	inent Datum <u>:</u> easured From g Measured F		_evel	_,_	A	ve Perm. Datı		D.F	Ft. Ft. Ft.	
Date		Jan. 27,	2015							
Туре С	of Log	Sonic								
Run		One								
Depth-	Driller	260	260 Ft		Ft		Ft		Ft	
Depth-	Logger	256	Ft		Ft		Ft		Ft	
Top Lo	gged Interval	27	Ft		Ft		Ft		Ft	
Btm. Lo	ogged Interval	255	Ft		Ft			Ft		
Type F	luid In Hole	Bentonit	e							
Fluid	d Level	Full	Ft		Ft		Ft		Ft	
Мах Те	emp	N/A	°F		°F	/	°F		°F	
Operat	ing Rig Time	.5	Hr		Hr		Hr			
Van No	. Location	LV-3	Bfld							
Record	led By	David Ja	ckson							
Witnes	sed By	Jim Ang	ell							
RUN	BOR	EHOLE RECC	RD			CASIN	G RECOR	D		
NO.	BIT	FROM	то		SIZE	TYPE	FRC	M	ТО	
1	8.75 In	0 F	t 256	Ft	N/A In			Ft	Ft	
2	In	F	t	Ft	In			Ft	Ft	
3	In	F	t	Ft	In			Ft	Ft	

14/0	010	-
- 1/1/ (-) /		
wel		VV

			E	LEC	TRIC	LOG				
FILING NO	12.	IPANY_	Bradley	& Sons [Orilling				1	
	The same of		Valley W	ator Mar	nagement C	o PTH-OF	(Most)			_
	WEL			July 201	lagement o	0. KTH-9L	(west)			_
	FIEL	D _	Racetrac	k Hill						
	STA	TE _	Californi	а	COUNTY Kern					
	LOCA	TION:			OTHER SERVICES					
	2.4 M 0.3 M	liles Nort	heast of 0	Comanci enridge	nche Drive & Breckenridge Road, ge Road.					
JOB NO. 17665	SEC: 24	IE TWP: 29	S RGE: 2	29E LAT.:		LONG:	МІ	ERIDIAN :		
Permanent			nd Level						v.: K.B	Ft
Log Measu	red From:	Groun	nd Level			. Above P		D.F		
Drilling Me	asured Fron	n: Grour	d Level						G.L.	
Run		One							-	
Date		Jan. 3	0, 2015							
Depth-Drille	r	360		Ft		Ft		Ft		Ft
Depth-Logg	er	360 Ft			Ft		Ft		Ft	
Top Logged	Interval	27 Ft		Ft		Ft		Ft		Ft
Btm. Logge	- 31.30.50 S-205-1	255		Ft		Ft		Ft		Ft
Casing-Drill		N/A	In @	Ft	In @	Ft	In @	Ft	ln @	
Casing-Log	ger		In @	Ft	In @	Ft	In @	Ft	In @	Ft
Bit Size		8.75		In		In		In		In
Time On Bo	00.000	13:30						-7/		
Type Fluid I		Bento	nite							
Density	Viscosity	N/A	N/A							
рН	Fluid Loss	N/A	N/A	ml		ml		ml		ml
Source of Sam		Pit		30/2						
Rm @ Measur	ed Temp.	7.1	@ 75	°F	@	°F	@	°F	@	°F
Rmf @ Measur	red Temp.	6.7	@ 75	°F	@	°F	@	°F	@	°F
Rmc @ Measu	red Temp.	N/A	@	°F	@	°F	@	°F	@	°F
Source Rmf	Rmc	Meas	N/A							
Rm @ BHT		N/A	@	°F	@	°F	@	°F	@	°F
Time Since		.5		Hr		Hr		Hr		Hr
Max. Rec. T	San	N/A	1	°F		°F		°F		°F
200000000000000000000000000000000000000	ocation	LV-3	Bfld							
Recorded B	,	David	Jackson							
Witnessed F	3v	lim A	llone							

(Prepared with Log Print, a professional software application developed by welenco, inc.)

CA. Contractor's License: 722373


wel	010	-
- 1/1// () /		

			so	NIC	C-VD	L-P	ORC	SIT	Y LOG	3				
FILIN	NG NO.	CO	MPANY_	Brad	lley & Soi	ns Dril	ling							
		WE		Valle	y Water I	Manag	ement Co	o. RTH-9	9D (West)					
		FIE		Race	track Hill									
		STA			ornia		COUNTY Kern							
		LOC 2.4 I	ATION:	heast	t of Coma	inche ge Ro	Drive & B	5000	ridge Road,	- / / /	OTHER SER Elog	VICES:		
	8 NO. 665	SEC: 2	24E TWP: 25	9 S RO	3E: 29E L	AT.:		LONG.:		MERIDIA	N.:			
Permanent Datum: Ground Level Log Measured From: Ground Level Drilling Measured From: Ground Level						, E	lev	Perm. Datun	_ Ft.	Elev.: K.E D.F	3 	_Ft.		
Date			Jan. 30), 201	5			-1						
Гуре О	f Log		Sonic											
Run			One											
Depth-D	Oriller		360		Ft			Ft		Ft			Ft	
Depth-L	ogger		360		Ft			Ft		Ft	Ft		Ft	
Гор Log	gged Inter	val	13		Ft		Ft		Ft		Ft			
3tm. Lo	gged Inte	rval	355		Ft			Ft Ft			1 + -	Ft		
Type FI	uid In Hol	le	Bentor	nite						1				
Fluid	Level		Full		Ft			Ft		Ft	Ft Ft		Ft	
Max Te	mp		N/A		°F		°F		°F			°F		
Operatii	ng Rig Tir	ne	.5		Hr			Hr		H			Hr	
/an No	. Loca	ation	LV-3	Bf	ld									
Recorde	ed By		David .		on									
Vitness	ed By		Jim An	gell										
RUN	- I	BORE	HOLE REC	ORD	H				CASING	RECOF	RD			
10.	BIT		FROM	-	ТО		SIZE		TYPE	FR	MC	ТО		
1	8.75	In	0	Ft	360	Ft	N/A	In			Ft		Ft	
3		In In		Ft		Ft Ft		In In			Ft		Ft	
0		11.1		F U		F()		In			Ft		Ft	

CA. Contractor's License: 722373


	0 10	-
_ \		
wel		UU

			E	LE	CTRIC	LOG				
FILING I		ADANIX E	Bradlev	& Son	s Drilling					
	CON	AL ZINT	33			0.0000				-
	WEI	L	alley W	ater N	Management C	ompany	C-1D			-
	FIEL	.D _	Plant							
	STA	TE (Californi	ia	C	OUNTY	Kern			
	LOCA	TION:						ОТН	IER SERVICES:	
	A 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 3 4 7 4 7	liles West lile South						So	nic	
ЈОВ NO 1769		4N TWP: 295	RGE:	29E_LA	ат.: <u>35° 21' 17.2'</u>	LONG.: 1	18° 51' 38.8" _{ME}	RIDIAN.:_	Mt. Diablo	
Permane	nt Datum:	Ground	Level			Elev		t. Ele	v.: K.B	Ft.
Log Meas	sured From:	Ground	Level			t. Above F	Perm. Datum		D.F	Ft.
Drilling N	leasured Fro	m: Ground	Level				<u> </u>		G.L	Ft.
Run		One								
Date		Feb. 19	, 2015							
Depth-Dri	ller	460		Ft		Ft		Ft		Ft
Depth-Log	gger	460		Ft		Ft		Ft		Ft
Top Logge	ed Interval	7		Ft		Ft		Ft		Ft
Btm. Logo	ged Interval	459		Ft		Ft		Ft		Ft
Casing-Dr	iller	None	n @	Ft	In @	Ft	ln @	Ft	In @	Ft
Casing-Lo	ogger	None	1@	Ft	In @	Ft	ln @	Ft	In @	Ft
Bit Size		8.75		In		In		In		In
Time On E	Bottom	10:23		- 4						
Type Fluid	d In Hole	Benton	ite							
Density	Viscosity	N/A	N/A							
рН	Fluid Loss	N/A	N/A	ml		ml		ml		ml
Source of S	ample	Pit								
Rm @ Meas	ured Temp.	9.6	@ 75	°F	@	°F	@	°F	@	°F
Rmf @ Mea	sured Temp.	8.7	a 75	°F	@	°F	@	°F	@	°F
Rmc @ Mea	sured Temp.	N/A	a	°F	@	°F	@	°F	@	°F
Source Rn	nf Rmc	Meas	N/A		Ĭ		Ĭ		Ĭ	
Rm @ BHT		N/A	a	°F	@	°F	@	°F	@	°F
Time Sinc	e Circulation	1		Hr		Hr		Hr		Hr
Max. Rec.	Temp.	N/A		°F		°F		°F		°F
Van No.	Location	LV-1	Bflo	1						
Recorded	Ву	David .	ackson				1			
Witnesse	d Bv	Jim An	aell							



-	I A A	AM	000
-		en	
_			

	Fl	JLL W	AVEFO	DRI	I SONIC	- VDL	LO	G	
FILIN	IG NO.	OMPANY	Bradley & So	ns Dril	ling			100	
					ement Compa	ny C-1D			
			C Plant						
	4.3		California		COUNTY	Kern			
		CATION:	Jamorina		COUNTY	Keili		OTHER SER	VICES:
			of Comanch					Elog	1,000
ЈОВ 176	200	34N TWP: 29	S RGE: 29E L	AT.: 35	° 21' 17.2" LONG	.: 118° 51' 38.8	" MERIDIAI	N.: Mt. Dia	iblo
Log Me	nent Datum: easured From Measured Fr	Ground : Ground	Level		, Elev		Ft.	Elev.: K.E D.F	BFt. FFt. Ft.
Date		Feb. 19	, 2015						
Гуре Of	Log	Sonic							
Run		One							
Depth-D	riller	460	Ft		Ft		Ft		Ft
Depth-L	ogger	460	Ft		Ft		Ft		Ft
Гор Log	ged Interval	7	Ft		Ft		Ft		Ft
3tm. Lo	gged Interval	459	Ft		Ft		Ft		Ft
Type Flu	uid In Hole	Benton	ite						
Fluid	Level	Full	Ft		Ft		Ft		Ft
Max Ter	mp	N/A	°F		°F		°F		°F
Operatir	ng Rig Time	.5	Hr		Hr		H		Hi
/an No.	Location	LV-1	Bfld						
Recorde	ed By	David J	2.00						
Vitness		Jim Ang		-					
RUN	- 4	EHOLE REC					G RECOR	RD	
10.	BIT	FROM	ТО	-	SIZE	TYPE	FR	MC	ТО
1	8.75 In		Ft 460	Ft	None In			Ft	Ft
3	In In		Ft Ft	Ft Ft	In In			Ft Ft	Ft.
J	11.1		I L	FU	111			TI.	Ft



CA. Contractor's License: 722373

ATTACHMENT B GEOLOGIC LOGS

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL RTH-7D

Depth (feet)	Description	USC
0-7	Yellowish brown silty fine to medium sand	SM
7-11	Brown fine to coarse sand	SW
11-14	Yellowish brown fine sandy silt	ML
14-17	Yellowish brown, olive brown and white medium	
	coarse sandy silt	ML
17-27	Brown and some yellowish brown fine to coarse	
	sand with gravel	SW
27-30	Yellowish brown silty fine sand	SM
30-35	Brown and some yellowish brown fine to coarse	
	Sand with gravel	SW
35-39	Yellowish brown and white silty fine to medium	
	sand	SM
39-43	Brown and some yellowish brown fine to coarse	
	sand with gravel	SW
43-47	Yellowish brown, olive brown and white silty fine	
	sand with some clay	SM
47-55	Yellowish brown and olive brown fine to medium	
	sandy silt	ML
55-59	Brownish gray silty fine sand	SM
59-61	Brownish gray fine to coarse sand	SW
61-65	Olive brown and white silty fine to coarse sand	SM
65-75	Gray and some olive yellow fine to coarse sand	
	with gravel	SW
75-80	Yellowish brown, olive brown and some olive	
	yellow silty fine sand	SM
80-87	Gray and some olive yellow fine to coarse sand	
	with gravel	SW
87-90	Grayish brown and white silty fine sand	SM
90-98	Gray fine to coarse sand with gravel	SW
98-101	Grayish brown fine to medium sand	SM
101-116	Gray fine to coarse sand with some gravel	SW
116-117	Brownish gray fine to medium sand with silt	SW
117-140	Gray fine to coarse sand with gravel	SW
140-146	Brownish gray fine to coarse sand with gravel	SW
146-162	Gray-brown clay	CL
162-185	Gray-brown fine to coarse silty sand	SM
185-194	Gray sandy clay	CL
194-208	Brown-gray fine to coarse silty sand	SM
208-216	Brown-gray fine silty sand	SM
216-224	Brown-gray and blue sandy clay	CL

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL RTH-7D (Continued:)

Depth (feet)	Description	USC
224-230	Brown-gray fine to coarse silty sand with gravel	SM
230-246	Gray-blue fine to coarse silty sand with gravel	SM
246-255	Gray-blue sandy clay	CL
255-268	Gray-blue fine to coarse silty sand	SM
268-293	Gray-blue fine to coarse sandy gravel	GP
293-326	Gray-blue fine to coarse silty sand with gravel	SM
326-334	Gray-blue clay	CL
334-360	Gray-blue fine to coarse silty sand with gravel	SM

Date Hole Drilled: 2/6/15

Saturated Deposits at about 134 feet deep Depth to Water: 207 feet (pressure level)

Note: The log for the interval from 0 to 145 feet in depth was also based on the geologic log for adjacent well RTH-6 by Kennedy/Jenks Consultants.

James R. Angell Geologist No. 8460 Certified Hydrogeologist No. 919

March 18, 2015

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL RTH-8D

Depth (feet)	Description	USC
0-22	Yellowish brown silty fine sand	SM
22-32	Yellowish brown, olive yellow, brown fine sandy	
	silt	ML
32-45	Gray and some olive yellow fine to medium sand	SP
45-47	Brownish gray fine sandy silt	ML
47-55	Gray and some brownish yellow fine to coarse	
	sand	SW
55-57	Brownish gray fine sandy silt	ML
57-66	Gray and some brownish yellow fine to coarse	
	sand	SW
66-73	Gray and some brownish yellow sandy silt	ML
73-90	Gray and some brownish yellow fine to coarse	
	sand	SW
90-102	Yellowish brown, black, and gray fine to coarse	
	sandy gravel and gravelly sand	GW/SW
102-106	Brown and white yellow fine to coarse sand	SP
106-135	Brown silty fine sand	SM
135-144	Gray fine to coarse sand	SW
144-184	Brown silty fine sand and clay	SM/SC
184-206	Brown-gray fine to coarse sand with some gravel	SP
206-218	Blue and brown-gray clay	CL
218-224	Gray-brown fine to medium silty sand	SM
224-226	Blue and gray-brown clay	CL
226-234	Gray-brown medium sand	SP
234-244	Gray-brown fine to coarse sand	SP
244-256	Gray-brown clayey fine to coarse sand	SC

Date Hole Drilled: 1/27/15

Saturated Deposits at about 90 feet deep

Note: The log for the interval from 0 to 150 feet in depth was also based on the geologic log for adjacent well RTH-4 by Kennedy/Jenks Consultants.

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL RTH-9D

Depth (feet)	Description
0-23	Yellowish brown silty fine to medium sand with Clay
23-32	Brownish gray fine sandy silt with clay
32-38	Brownish gray clayey and silty fine to coarse Sand
38-58	White and brownish gray fine to coarse sand
58-60	Brownish gray silty fine to coarse sand
60-63	Brownish gray fine to medium sand
63-76	Brownish gray and white fine to coarse sand
	with some silt
76-77	Brownish gray silty fine sand
77-87	Brownish gray and white fine to medium sand
87-111	Gray, brownish gray and white fine to coarse
	sand
111-120	Gray and brown fine to medium sand
120-146	Gray and brown clayey fine to medium sand with
	some gravel
146-187	Brown, white, black, gray fine to medium sand
	with some gravel and clay
187-204	Brown, white, black, and green-gray clayey fine
	sand
204-220	Brown, white, black and green-gray fine sand
220-229	Brown-gray coarse sand with some gravel
229-234	Brown-gray clay
234-242	Brown-gray clayey coarse silty sand
242-249	Brown-gray clay
249-256	Brown-gray fine to medium silty sand
256-264	Brown-gray clay
264-284	Brown gray fine to coarse sand
284-292	Blue and brown clay
292-299	Blue and brown fine to coarse silty sand with
	gravel
299-360	Brown fine to coarse sand with gravel

Date Hole Drilled: 1/30/15

Saturated Deposits at about 72 feet in depth Depth to Water: 225 feet (pressure level)

Note: The log for the interval from 0 to 102 feet in depth was also based on the geologic logs for adjacent well RTH-1 and TH-2 by Kennedy/Jenks Consultants.

James R. Angell Geologist No. 8460 Certified Hydrogeologist No. 919 March 18, 2015

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL C-1D

Depth (feet)	Description
0-12	Brown fine to coarse silty sand with some clay
12-20	Brown coarse sand with gravel
20-26	Brown clay
26-45	Brown fine to coarse sand with gravel
45-50	Brown clay
50-60	Brown fine to coarse sand with gravel
60-74	Brown clay
74-79	Brown fine to coarse sand with gravel
79-87	Brown clay
87-98	Brown fine to coarse sand with gravel
98-107	Brown clay
107-110	Brown sandy clay with gravel
110-115	Brown clay
115-120	Brown fine to coarse sand with gravel
120-143	Brown clayey fine to coarse sand with gravel
143-152	Brown clay
152-170	Brown fine to coarse sand with gravel
170-183	Brown clay
183-191	Brown sandy clay with gravel
191-199	Brown fine to coarse sand with gravel
199-211	Brown clay
211-217	Brown fine to coarse silty sand with gravel and
	clay
217-220	Brown clay
220-232	Brown fine silty sand with gravel
232-242	Brown clay
242-245	Brown clayey fine sand
245-251	Brown clay
251-258	Brown clayey fine to coarse sand with gravel
258-264	Brown fine to coarse silty sand with gravel
264-268	Brown clayey fine to coarse sand with gravel
268-277	Brown clay
277-287	Brown fine to coarse sand with some gravel
287-294	Brown fine sandy clay
294-301	Brown clay
301-316	Brown fine to coarse sand with gravel
316-330	Brown clay
330-347	Brown fine to coarse sand with some gravel
347-354	Brown clay
354-362	Brown fine to coarse sand with some gravel
362-366	Brown clay

GEOLOGIC LOG FOR VALLEY WATER MANAGEMENT CO. DEEP MONITOR WELL C-1D (Continued:)

Depth (feet)	Description	USC
366-374	Brown fine silty sand with some gravel	SM
374-393	Brown clay	CL
393-399	Brown fine silty sand	SM
399-415	Brown clay	CL
415-425	Brown fine silty sand with some gravel and clay	SM
425-432	Gray clay	CL
432-442	Brown fine silty sand with gravel and some clay	SM
442-460	Gray clay	CL


Date Hole Drilled: 2/19/15

Saturated Deposits at about 380 feet deep


Pressure Level 298 feet deep

James R. Angell Geologist No. 8460 Certified Hydrogeologist No. 919 March 18, 2015


ATTACHMENT C
WELL COMPLETION DIAGRAMS




SCHEMATIC DIAGRAM FOR DEEP MONITOR WELL RTH-7D
AT THE RACE TRACK HILL FACILITY



SCHEMATIC DIAGRAM FOR DEEP MONITOR WELL RTH-8D
AT THE RACE TRACK HILL FACILITY



SCHEMATIC DIAGRAM FOR DEEP MONITOR WELL RTH-9D AT THE RACE TRACK HILL FACILITY



SCHEMATIC DIAGRAM FOR DEEP MONITOR WELL C-1D AT PLANT-C

ATTACHMENT D
WELL COMPLETION REPORTS

TRIPLICATE Owner's Copy

Page I of 1

STATE OF CALIFORNIA

WELL COMPLETION REPORT

., .	****	332.0						
	Ma		0	9	E.	0	0	C
	No.	仁	U	1	5	O	0	C

Owner's Well No. RTH #7D Date Work Began 2/5/2015

, Ended2/19/2015

STATE W	ELL NO./ STATION NO.
I a I a	
LATITUDE	LONGITUDE

Level De	mit Ac	CHECKERN COUNTY HEALTH	APN/TRS//	OTHER
Local Fc	No W	Permit Date 12.55.12	WELL OWNED -	
ORIENTATI	ON /V	GEOLOGIC LOG ✓ VERTICAL — HORIZONTAL — ANGLE — (SPECIFY)	Name VALLEY WATER MANAGEMENT Mailing Address 7500 MEANY AVE.	
DEPTH F	ROM	DESCRIPTION WATER	BAKERSFIELD CITY	CA 93308 STATE ZIP
	471	Describe material, grain, size, color, etc.	Address S OF 178 ON COMMANCHE ROAL)
0	80	BROWN CLAY, MEDIUM/COARSE SAND,	Address S OF 178 ON COMMANGIL ROXE	
		SOME SMALL GRAVEL	City BAKERSFIELD CA 93306	
80	100	SILTY GRAY CLAY, SOME MEDIUM SAND	County KERN	
100	160	SILTY GRAY CLAY, MEDIUM AND AND GRAVEL	APN Book 387 Page 060 Parcel 03	
160	200	SILTY GRAY CLAY, SOME MEDIUM SAND	Township 29 S Range 29 Section 24	
200	240	GRAY CLAY, MEDIUM/FINE SANDS	Latitude	DEG. MIN. SEC.
240	280	MEDIUM/COARSE SAND GRAVEL MEDIUM/COARSE SAND, GRAVEL, ROCK	DEG. MIN. SEC. LOCATION SKETCH	ACTIVITY (∠) —
			NEST SOUTH	MODIFICATION/REPAIR Deepen Other (Specify) DESTROY (Describe Procedures and Materials Under "GEOLOGIC LOG PLANNED USES (*) WATER SUPPLY Domestic Public Industrial Industrial MONITORING TEST WELL CATHODIC PROTECTION HEAT EXCHANGE DIRECT PUSH INJECTION VAPOR EXTRACTION SPARGING REMEDIATION
			Hustrate or Describe Distance of Well from Roads, Buildings, Fences, Rivers, etc. and attach a map. Use additional paper if necessary. PLEASE BE ACCURATE & COMPLETE.	OTHER (SPECIFY)
			DEPTH TO FIRST WATER (FL) BELOW SURFA DEPTH OF STATIC WATER LEVEL (FL) & DATE MEASURED	ACE
			ESTIMATED YIELD (GPM) & TEST TYPE_	AIR LIFT
TOTAL	EPTLIC	F BORING 360 (Feet)	TEST LENGTH 4 (Hrs.) TOTAL DRAWDOWN	(Ft.)
TOTAL	COTHO	F COMPLETED WELL 360 (Feet)	May not be representative of a well's long-term y	rield.
TOTALL	EPINO	1 COM EDITOR TEDE	may not be real	THE R. P. LEWIS CO., LANSING MICH.

DEPTH FROM SURFACE		BORE - HOLE DIA. (Inches)	CASING (S)							DEPTH FROM SURFACE		ANNULAR MATERIAL. TYPE				
			ANK	YPE	CON. T	PIPE (MATERIAL / GRADE	INTERNAL DIAMETER	GAUGE OR WALL	SLOT SIZE IF ANY			CE- MENT	BEN- TONITE		FILTER PACK (TYPE/SIZE)
Ft. 10	Ft	(notice)	BLANK	SCR	88	를		(Inches)	THICKNESS	(Inches)	FL to	o Ft.	(<u>v</u>)	(<u>v</u>)	(1)	
0	280	12 1/4"	1	-			PVC	5"	SCH 40		0	220	1			10.5 SACK SA
280	330	12 1/4"		1			PVC	5"	SCH 40	.030	220	225		1		
200	000						1 40		2011.10		225	340			V	6X20 GRAVE
						1		-			· · · · · ·		-	-		
			-	-		1-1	_	1				_				
	ATTACI	AMENTS	11	1						CERTIFICA	TION STAT	TEMEN	r —			

ATTACHMENTS (\(\sigma \)	
Geologic Log	I, the
Well Construction Diagram	NAM
Geophysical Log(s) Soll/Water Chemical Analysis Other	362 ADDF
ATTACH ADDITIONAL INFORMATION, IF IT EXISTS.	Signe
A SECOND	

, the undersigned, certify that this report is complete and accurate to the best of a NAME_BRADLEY & SONS	ny knowledge and belief.		
(PERSON, FIRM, OR CORPORATION) (TYPED OR PRINTED)		4.7	mm x 5-465
	REY	CA	93616
ADDRESS 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	CITY	STATE	ZIP
Sund NIGHTS INCOME	02/25/15	414	4178
Signed WELL DRILLER/AUTHORIZED REPRESENTATIVE	DATE SIGNED	C-5	7 LICENSE NUMBER

TRIPLICATE Owner's Copy

STATE OF CALIFORNIA

WELL COMPLETION REPORT

No. EO252667

Page 1 of	1		
Owner's	Well No.	RTH	8D

Date Work Began 1/26/2015

. Ended 2/4/2015

Local Permit Agency ENVIRO HEALTH, KERN CTY

DWR USE ONLY	DO NOT FILL IN
STATE WEL	L NO./ STATION NO.
June 1	IE CLASSIE
1 in the second	LONGITUDE
LATITUDE	Editorios
APN/	TRS/OTHER

Permit	No. VV	GEOLOGIC LOG	WELL OWNER -	
ORIENTATI	ON (≰)	✓ VERTICAL — HORIZONTAL — ANGLE(SPECIFY) DRILLING ROTARY — FLUID WATER	Name VALLEY WATER MANAGEMENT Mailing Address 7500 MEANY AVE	CA 93308
	DESCRIPTION		BAKERSFIELD	STATE ZIP
Ft. to	Ft.	Describe material, grain, size, color, etc. COARSE SAND, GRAVEL	Address S OF 178 ON COMMANCHE ROAD	
0			City BAKERSFIELD CA 93306	
20		COARSE SAND, CLAY COARSE/MEDIUM SAND AND GRAVEL		
40	60	COARSE/MEDIUM SAND AND GRAVEL	County KERN	
60	80	COARSE SAND, SOME GRAVEL, TAN CLAY	APN Book 387 Page 060 Parcel 03	
80		COARSE SANDY GRAVEL	Township 29 S Range 29 E Section 24	
120	200	CLAY, GRAVEL	Latitude DEG. MIN. SEC. LOCATION SKETCH	DEG. MIN. SEC.
200		HARD BLACK GRAY CLAY TAN CLAY, GRAVEL	LOCATION SKETCH	—ACTIVITY (∠) —
			SOUTH South Buildings	Deapen Olher (Specify) DESTROY (Describe Procedures and Materials Under "GEOLOGIC LOG" PLANNED USES (✓) WATER SUPPLY Domestic Public ✓ Infigation Industrial MONITORING ✓ TEST WELL CATHODIC PROTECTION HEAT EXCHANGE DIRECT PUSH INJECTION VAPOR EXTRACTION SPARGING REMEDIATION
			Hlustrate or Describe Distance of Well from Roads, Buildings, Fences, Rivers, etc. and attach a map. Use additional paper if necessary. PLEASE BE ACCURATE & COMPLETE.	OTHER (SPECIFY)
			WATER LEVEL & YIELD OF COMPI DEPTH TO FIRST WATER (FL) BELOW SURFACE DEPTH OF STATIC WATER LEVEL (FL) & DATE MEASURED ESTIMATED YIELD * (GPM) & TEST TYPE	AIR LIFT
TOTAL D	EPTH O	F BORING 250 (Feet) F COMPLETED WELL 250 (Feet)	TEST LENGTH 4 (Hrs.) TOTAL DRAWDOWN May not be representative of a well's long-term yie	(Ft.)

DEPTH DC		PORE					C	ASING (S)	-		DEP			ANNU		MATERIAL		
FROM SUR	RFACE	BORE -				()	Constitution of	INTERNAL	GAUGE	SLOT SIZE	FROM SU	REAGE	CE- BE		IY	PE		
Ft. to	Ft.	DIA. (Inches)	BLANK		CON	UCTOR.	GRADE	DIAMETER (Inches)	DIAMETER	OR WALL THICKNESS	DIAMETER OR WALL	IF ANY (Inches)	Ft. to	Ft.	MENT (✓)	TONITE	FILL	FILTER PACK (TYPE/SIZE)
0:	190	12 1/4"	1	1	1	7	PVC	5"	SCH 40		0	163	1			10.5 SACK		
190	210	12 1/4"	Ť		1		PVC	5"	SCH 40	.030	163	168		V				
150:	210	12 1/1		Ť			FVO		0011.10		168	211			1	6 X 20 SANI		
-			-	1	1	+					211	219		1				
			1		T													
				1														
	ATTAC	HMENTS	11	1	_		1.1			CERTIFICA	TION STA	TEMEN	r -	_	_			

ATTACHMENTS (∠)
Geologic Log Well Construction Diagram
Geophysical Log(s)
Soil/Water Chemical Analysis
Other
ATTACH ADDITIONAL INFORMATION, IF IT EXISTS.

I, the undersigned, certify that this report is complete and accurate to the best of	my knowledge and belief.			
MAME BRADLEY & SONS	Service and a contract of			_
(PERSON, FIRM, OR CORPORATION) (TYPED OR PRINTED) 3625 S. HIGHLAND DE	LREY	CA	93616	
ADDRESS / DOLLAR / DOLLAR	CITY	STATE	4178	
Signed WELL DRIFLER/AUTHORIZED REPRESENTATIVE	02/25/15 DATE SIGNED		7 LICENSE NU	JMBE

TRIPLICATE Owner's Copy

STATE OF CALIFORNIA

WELL COMPLETION REPORT Refer to Instruction Pamphlet

Page 1 of 1 Owner's Well No. RTH 9D

No. EO2526682

Date Work Began 1/29/2015

_, Ended2/4/2015

STATE WEI	L NO./ STATION NO.
SIAIC WE	
LATITUDE	LONGITUDE
and the state of	1 1 1 1 1 1 1 1

Local Pe	rmit Ag	ency ENVIRO HEALTH, KERN CTY		APN/TRS/(OTHER
Permit	No. W	P15778 Permit Date 12/30/2014		- WELL OWNER -	
ORIENTATI	ON (⊻)	GEOLOGIC LOG ✓ VERTICAL HORIZONTAL ANGLE (SPECIFY) DRILLING ROTARY FLUID WATER	Name VALLEY WATE		
DEPTH F SURFA		DESCRIPTION	CITY		STATE ZIP
Ft to	Ft.	Describe material, grain, size, color, etc.	Address S OF 178 ON	WELL LOCATION	
0		CLAY, GRAVEL, COARSE SAND	Address S OF 1/8 ON	A COMMANCHE RUAL	
60		TAN CLAY, SMALL GRAVEL, COARSE SAND	City BAKERSFIELD C	A 93306	
120		CLAY, MEDIUM/COARSE SAND	County KERN		
140	160	TAN CLAY, SOME MEDIUM SAND	APN Book 387 Pag	e 060 Parcel 03	
160		TAN CLAY, SOME MEDIM SAND AND GRAVEL	Township 29 S Rar	ge29 E Section 24	
200		TAN CLAY, MEDIUM SAND	Latitude	222	DEG. MIN. SEC.
220		ROCK, CLAY	DEG. MIN.	SEC. N SKETCH	ACTIVITY (4)
280	360	CLAY, SOME GRAVEL, MEDIUM SAND	NOF	TH	. NEW WELL
			NE SOIL	EAST	DESTROY (Describe Procedures and Materials Under "GEOLOGIC LOG" PLANNED USES (✓) WATER SUPPLY Domestic Public Irrigation Industrial MONITORING ✓ TEST WELL CATHODIC PROTECTION HEAT EXCHANGE DIRECT PUSH INJECTION VAPOR EXTRACTION SPARGING REMEDIATION
		1	Hustrate or Describe Distance of Fences, Rivers, etc. and attach a necessary. PLEASE BE ACCU	Well from Roads Buildings.	OTHER (SPECIFY)
		BORING 350 (Feet)	DEPTH TO FIRST WATER— DEPTH OF STATIC WATER LEVEL ESTIMATED YIELD * TEST LENGTH 4 (Hrs	(Ft.) & DATE MEASURED (Ft.) & DATE MEASURED (GPM) & TEST TYPE TOTAL DRAWDOWN	AIR LIFT
		F BORING 350 (Feet) F COMPLETED WELL 350 (Feet)	TEST LENGTH 4 (Hrs	.) TOTAL DRAWDOWNive of a well's long-term yie	(FL)

DEPTH		DODE		CASING (S)					DEPTH			ANNULAR MATERIAL				
FROM SUR	FACE	BORE - HOLE	T	YPE	(4)				7 - 1.	FROM SURFACE			TYPE			
FL to	Ft.	DIA, (Inches)	BLANK	SCREEN	CON- DUCTOR FILL PIPE	MATERIAL / GRADE	INTERNAL DIAMETER (Inches)	GAUGE OR WALL THICKNESS	SLOT SIZE IF ANY (Inches)	Ft. to	Ft.	ME (±	NT T	BEN- ONITE	FILL	FILTER PACK (TYPE/SIZE)
0;	310	12 1/4"	1			PVC	5"	SCH 40		0	28	5	/			10.2 SACK
310	350	12 1/4"		1	1	PVC	5"	SCH 40	.030	285	29	0	1			
					-			331,113		290	3	0			V	6 X 20 GRAVE
1																
										- 4			14.5	-3		

	ATTACHMENTS (<)
	Geologic Log
-	Well Construction Diagram
	Geophysical Log(s)
	Spil/Water Chemical Analysis
	Other

ATTACH ADDITIONAL INFORMATION, IF IT EXISTS.

	CERTIFICATION STATI			
I, the undersigned, certify that this report is comp	olete and accurate to the best of m	y knowledge and belief.		
(PERSON, FIRM, OR CORPORATION)		666	4.1	44414
3625 S. HIGHLAND	// DEL	REY	CA	93616
Signed Danie	1 Odie	CITY 02/25/15		ZIP 1178
WELL DOLL FRAUTUODIZED DEDDE	ECENTATIVE	DATE SIGNED	C-57	LICENSE NUMBE

TRIPLIC	ATE
Owner's	Сору

Page 1 of 1

STATE OF CALIFORNIA

WELL COMPLETION REPORT

o Instruction	Pamphlet
No EO	252670

Owner's Well No. C1-D , Ended 2/23/2015 Date Work Began 2/5/2015

- DWR USE ONLY - DO NOT FILL IN STATE WELL NO STATION NO. LONGITUDE LATITUDE APN/TRS/OTHER

Local Permi	it Age	ency KERN CTY PUBLIC HEALTH	APN/TRS/OTHER
Permit No	o. WF	Permit Date 12/30/2014	WELL OWNER -
ORIENTATION	(⊻)	GEOLOGIC LOG ✓ VERTICAL HORIZONTAL ANGLE (SPECIFY) DRILLING ROTARY FLUID WATER	Name VALLEY WATER MANAGEMENT Mailing Address 7500 MEANY AVENUE
DEPTH FROM SURFACE	VI	DESCRIPTION Describe material, grain, size, color, etc.	BAKERSFIELD CA 93300 CITY STATE ZIP
Ft. lo F	20	LARGE ROCK, TOPSOIL, COARSE SAND	Address S. OF 178 ON COMMANCHE ROAD
0;	20	LARGE GRAVEL, COARSE SAND, RED CLAY	City BAKERSFIELD CA 93306
20	160	SOME GRAVEL, COARSE SAND, CLAY	County KERN
60;	100	SOME SMALL GRAVEL, COARSE/MEDIUM	APN Book 388 Page 050 Parcel 25
160	240	SAND, BROWN CLAY	Township 29 S Range 29 E Section 34
040	200	BROWN CLAY, MEDIUM/COARSE SAND	
240	300	GRAVEL, BROWN CLAY, MEDIUM SAND	Latitude DEG. MIN. SEC. DEG. MIN. SEC.
300	380	BROWN CLAY, MEDIUM/FINE SAND	LOCATION SKETCH——ACTIVITY (½) —
			Other (Specify) DESTROY (Describe Procedures and Material Under "SEOLOGIC LOC PLANNED USES (∠) WATER SUPPLY Domestic Public Industries MONITORING ✓ TEST WELL CATHODIC PROTECTION HEAT EXCHANGE DIRECT PUSH INJECTION VAPOR EXTRACTION SPARGING REMEDIATION
			- Illustrate or Describe Distance of Well from Roads, Buildings, Fences, Rivers, etc. and attach a map. Use additional paper if necessary. PLEASE BE ACCURATE & COMPLETE. OTHER (SPECIFY)
			WATER LEVEL & YIELD OF COMPLETED WELL DEPTH TO FIRST WATER (FL) BELOW SURFACE DEPTH OF STATIC WATER LEVEL (FL) & DATE MEASURED ESTIMATED YIELD (GPM) & TEST TYPE AIR LIFT
TOTAL DEP	TH OF	F BORING 455 (Feet) F COMPLETED WELL 455 (Feet)	TEST LENGTH 21 (Hrs.) TOTAL DRAWDOWN (FL) May not be representative of a well's long-term yield.

DEPT	i.i						C	ASING (S)				PTH			ANNU		MATERIAL
FROM SUR		BORE -	7		E	(1)				Total Carlo	FROM S	UR	FACE			TY	PE
		DIA. (Inches)	BLANK			MATERIAL / INTERNAL DIAMETER (Inches)	GAUGE OR WALL THICKNESS	SLOT SIZE IF ANY (Inches)	Ft.	to	Ft.	CE- MENT	1	FILL	FILTER PACK (TYPE/SIZE)		
0	395'	12 1/4"	~	1	+	C u	PVC	5"	SCH 80		0	6	375	1	-		10.5 SACK SA
395	435'	12 1/4"	-	1	/		PVC	5"	SCH 80	.030	375		380		V		
393	400	12 171			1		1.70		0011.00		380	i	455			1	GRAVEL
				-	1							+		-			
- :			-	+	+	-		-			-	å					
				T	1							8		-	L.		

	ATTACHMENTS (∠) Geologic Log
	Well Construction Diagram
	Geophysical Log(s)
-	Soil/Water Chemical Analysis
-	Other

I, the undersigned, certify that this report is complete and accurate to the t			
NAME BRADLEY & SONS (PERSON, FIRM), OR CORPORATION) (TYPED OR PRINTED)	,	Table 1	37410
3625 S. HIGHLAND	DEL REY	CA	93616 ZIP
ADDRESS Signed A Driven A Drive	02/25/15	414	4178 7 LICENSE NUMBER
WELL DRILLERIAUTHORIZED REPRESENTATIVE	DATE SIGNED	C-5	LICENSE NUMBER

ATTACHMENT E WELL SURVEY DATA

VALLEY WATER MANAGEMENT GROUNDWATER MONITORING WELLS RACETRACK HILL SECTION 24 29/29

WELL	ELEV	DESC	DATUM	NORTHING	EASTING
RTH 7D	1061.83	TOP PVC CASING	NAD83	2328450.5330	6316615.0770
	1059.62	TOP WELL PAD			
RTH 8D	874.69	TOP PVC CASING	NAD83	2331694.4730	6318145.7090
	872.94	TOP WELL PAD			
RTH 9D	1025.15	TOP PVC CASING	NAD83	2330628.4350	6316159.4270
	1022.51	TOP WELL PAD			
C PLANT 1D	635.53	TOP PVC CASING	NAD83	2316433.8390	6305097.6380
	634.03	TOP WELL PAD			

PREPARED BY: DEE JASPAR & ASSOCIATES, INC. DATE OF SURVEY: March 20, 2015

VALLEY WATER MANAGEMENT GROUNDWATER MONITORING WELLS RACETRACK HILL SECTION 24 29/29

BENCHMARK:

NGS MONUMENT BRASS CAP - PID "FU0159"

1991 ELEV = 785.40

HORIZONTAL DATUM NAD83, ZONE 5

ATTACHMENT F
FIELD MEASUREMENTS FOR WELL SAMPLING

VALLEY WATER MANAGEMENT CO. FIELD MEASUREMENTS FOR RTH-7D

Date: 3/16/15

Static Water Level: 206.8 feet below top of PVC 206.8-2.2 feet = 204.6 feet below land surface

Perforated Interval: 282-330 feet

One Well Volume: $(330-204.6 \text{ ft}) \times 1.02 \text{ gal/ft} = 127.9 \text{ gallons}$

Three Well Volumes: $127.9 \text{ gal } \times 3 = 384 \text{ gallons}$

Average Pumping Rate: 4.3 gpm

	Temp	Elec. Cond. (pmhos/			Diamen i man
Time	(°F)	cm @ 25°C)	DH	Appearance	Pumping Level (ft)
2:50PM	Began pumping	- Cm (g 25 C)	PH	Appearance	Hever (IC)
2:51	76	5,080	6.5	Clear w/H2S odor	
2:52	, ,	3,000	0.5	CIERL W/ 1125 CGCL	249.0
2:54	76	3,440	8.1	Clear	233.0
2:56	76	3,260	11.1	Milky white	267.8
3:00	76	3,220	10.3	Milky white with	207.0
	, ,	0,220	10.5	organic odor	
3:02				ordanic odor	314.0
	umping stopped				314.0
	Began pumping			Brown Turbid	
3:17	and a branch and			DEOWN INLEASE	280.7
3:18					282.5
3:19	78	5,130	6.4	Milky white	202.5
3:24	7.7	7/25			283.1
3:25	79	5,330	6.4	Milky white	
3:30	79	5,410	6.3	Milky white with	
4.4.4.4	1, 21	21.00	58. A.M.	H ₂ S odor	284.0
3:35	79	5,410	6.4	Milky white	121212
3:40	79	5,340	6.4	Milky white	285.1
3:45	79	5,330	6.4	Milky white	6.575.4.8
3:50	79	5,370	6.4	Milky white	286.2
3:55	79	5,370	6.4	Milky white	Carlo & J.
4:00	79	5,320	6.4	Milky white	288.7
4:09				•	291.0
4:10	79	5,310	6.4	Milky white	
4:20	79	5,310	6.4	Milky white	
4:21				•	297.9
4:28	79	5,210	6.5	Milky white	26 4 2 3 11

VALLEY WATER MANAGEMENT CO. FIELD MEASUREMENTS FOR RTH-8D

Date: 3/11/15

Static Water Level: 86.9 feet below top of PVC 86.9-1.8 feet = 85.1 feet below land surface

Perforated Interval: 191-210 feet

One Well Volume: $(210-85.1 \text{ ft}) \times 1.02 \text{ gal/ft} = 127.4 \text{ gallons}$

Three Well Volumes: $127.4 \text{ gal } \times 3 = 382 \text{ gallons}$

Average Pumping Rate: 9 gpm

Time	Temp (°F)	Elec. Cond. (µmhos/ cm @ 25°C)	m.W	Anna	Pumping
1:27PM	Began pumping	Cm e 25 C)	рн	Appearance	Level (ft)
1:28	71	6,340	6.6	Clear	
1:30					104.0
1:31	71	6,440	6.6	Clear	
1:32					109.6
1:33	71	6,450	6.6	Clear	
1:35	71	6,450	6.6	Clear	
1:39	71	6,470	6.7	Clear	
1:41	71	6,450	6.6	Clear	
1:42					113.2
1:46	71	6,420	6.7	Clear	
1:48					113.8
1:51	71	6,470	6.7	Clear	
1:53					114.0
1:56	71	6,430	6.6	Clear	
1:58					114.1
2:01	71	6,380	6.6	Clear	
2:03					114.3
2:07	71	6,460	6.6	Clear	

Sample collected at 2:09PM

VALLEY WATER MANAGEMENT CO. FIELD MEASUREMENTS FOR RTH-9D

Date: 3/17/15

Static Water Level: 225.3 feet below top of PVC 225.3-2.6 feet = 222.7 feet below land surface

Perforated Interval: 312-350 feet

One Well Volume: $(350-222.7 \text{ ft}) \times 1.02 \text{ gal/ft} = 129.9 \text{ gallons}$

Three Well Volumes: 129.9 gal x 3 = 390 gallons

Average Pumping Rate: 3.2 gpm

Time	Temp	Elec. Cond. (µmhos/ cm @ 25°C)	рН	Appearance	Pumping Level (ft)
_	M Began pumping		2		20102 (20)
9:12	5, 2 5, 2 5			Brown muddy	239.4
9:14	76	3,180	11.8	2.27/11/2005	200
9:15				Clear	270.9
9:17	76	3,460	11.7	Clear	
9:20	76	3,180	11.4	Clear w/air	
9:21					289.8
9:25	76	2,930	9.4	Clear w/air	
9:26		12.70			301.9
9:30	76	2,930	10.7	Slightly turbid	
9:31					305.9
9:35	76	2,980	9.8	Slightly turbid	. 200
9:40	77	3,480	8.1	Slightly turbid	
9:41					305.2
9:45	77	3,640	7.6	Slightly turbid	
9:50	Pumping stopped			3,000,000	
10:20	Began pumping				
10:26	76	3,760	7.3	Slightly turbid w/ai	ir
10:30	77	3,750	7.3	Slightly turbid w/ai	ir
10:31					250.5
10:40	77	3,910	7.1	Clear w/air	
10:42					255.3
10:50	77	3,910	7.1	Clear w/air	
11:00	77	3,870	7.0	Clear w/air	
11:01					257.9
11:10	77	3,920	7.0	Clear w/air	
11:20	77	3,920	7.0	Clear w/air	
11:21					258.3
11:30	77	3,960	7.0	Clear w/air	
11:40					258.8
11:43	77	3,940	6.9	Clear w/air	

Samples collected at 11:46AM

VALLEY WATER MANAGEMENT CO. FIELD MEASUREMENTS FOR C-1D

Date: 3/17/15

Static Water Level: 298.4 feet below top of PVC 298.4-1.8 feet = 296.6 feet below land surface

Perforated Interval: 395-435 feet

One Well Volume: $(435-296.6 \text{ ft}) \times 1.02 \text{ gal/ft} = 141.2 \text{ gallons}$

Three Well Volumes: $141.2 \text{ gal } \times 3 = 424 \text{ gallons}$

Average Pumping Rate: 5.7 gpm

	Temp	Elec. Cond. (umhos/			Pumping
Time	(°F)	cm @ 25°C)	PH	Appearance	Level (ft)
7:15AM	Began pumping		-		
7:16					307.0
7:17	78	893	6.7	Clear with air and H ₂ S odor	
7:18					309.1
7:20	79	1,096	6.8	Milky white with H2S odor	
7:24 P	umping stopped				
7:30	Began pumping				
7:32					304.5
7:35	79	1,267	6.9	Milky white with H2S odor	
7:38					304.9
7:40	80	1,268	7.0	Milky white with H2S odor	
7:46	80	1,268	7.0	Milky white with H2S odor	304.8
7:50	80	1,272	7.0	Milky white with H2S odor	305.0
7:55	79	1,299	7.0	Milky white with H2S odor	303.0
8:00	80	1,300	7.1	Milky white with H2S odor	
8:03					305.1
8:05	79	1,316	7.1	Clear with air and H ₂ S odor	
8:10	79	1,307	7.1	Clear with air and H2S odor	
8:12					305.1
8:15	79	1,321	7.1	Clear with air and H ₂ S odor	

Continued:

VALLEY WATER MANAGEMENT CO. FIELD MEASUREMENTS FOR C-1D (Continued:)

Date: 3/17/15

Static Water Level: 298.4 feet below top of PVC 298.4-1.8 feet = 296.6 feet below land surface

Perforated Interval: 395-435 feet

One Well Volume: $(435-296.6 \text{ ft}) \times 1.02 \text{ gal/ft} = 141.2 \text{ gallons}$

Three Well Volumes: $141.2 \text{ gal } \times 3 = 424 \text{ gallons}$

Average Pumping Rate: 5.7 gpm

	Elec. Cond.				
	Temp	(µmhos/			Pumping
Time	(°F)	cm @ 25°C)	PH	Appearance	Level (ft)
8:20AM	79	1,318	7.1	Clear with air and	d
				H ₂ S odor	
8:25	80	1,333	7.1	Clear with air and	d
				H ₂ S odor	
8:26					305.1
8:30	80	1,318	7.1	Clear with air and	d
				H ₂ S odor	
8:34	80	1,319	7.1	Clear with air and	d
				Hog odor	

Samples collected at 8:35AM

ATTACHMENT G LABORATORY ANALYTICAL SHEETS



March 20, 2015

: VI 1540850-001 Lab ID

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 16, 2015-16:30

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

: Ag Water Matrix

: RTH-7D Description

: Race Track Hill Project

Sample Result - Inorganic

2.7740.5	D 1	DOL	Units	Note	Sample	Preparation	Sample Analysis	
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}								
Total Hardness as CaCO3	1760		mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Calcium	534	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Magnesium	104	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Potassium	35	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Sodium	411	1	mg/L		200.7	03/19/15:203223	200,7	03/19/15:204278
Total Cations	54.0		meg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Boron	0.3	0.1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Copper	ND	10	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Iron	540	30	ug/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Manganese	1130	10	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Zinc	60	20	ug/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Gypsum Requirement	0.0		Tons/AF		200.7	03/19/15:203223	200.7	03/19/15:204278
SAR	4.3	***			200.7	03/19/15:203223	200.7	03/19/15:204278
Total Alkalinity	260	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Hydroxide	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Carbonate	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Bicarbonate	320	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Sulfate	910	40*	mg/L		300.0	03/18/15:203226	300.0	03/18/15:204217
Chloride	1250	20*	mg/L		300.0	03/18/15;203226	300.0	03/18/15:204217
Nitrate	0.4	0.4	mg/L		4500NO3F	03/19/15:203243	4500NO3F	03/19/15:204261
Nitrate Nitrogen	ND	0.1	mg/L		4500NO3F	03/19/15:203243	4500NO3F	03/19/15:204261
Fluoride	ND	0.1	mg/L		300.0	03/18/15:203226	300.0	03/18/15:204217
Total Anions	59.5	200	meq/L		2320B	03/18/15:203166	2320B	03/18/15:204307
pH	6.6	**	units		4500-H B	03/19/15;203242	4500HB	03/19/15:20422:
E. C.	5420	1	umhos/cm		2510B	03/19/15:203224	2510B	03/19/15:204200
TDS by Summation	3560	4-	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Wet Chemistry ^{P;1} Solids, Total Dissolved (TDS)	3900	20*	mg/L		2540CE	03/18/15:203197	2540C	03/19/15:204208

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 ‡Surrogate. * PQL adjusted for dilution.



March 20, 2015

: VI 1540850-001 Lab ID

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 16, 2015-16:30

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

Matrix

: Ag Water

Description

: RTH-7D

Project

: Race Track Hill

Sample Result - Organic

0 0	Deside	DOL	Linite	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
TOC ^{AVT:14} TOC	0.5	0.5	mg/L	10.5	5310C	03/18/15:203198	5310C	03/18/15:204236

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 \$\pm\$Surrogate. * PQL adjusted for dilution.



March 19, 2015

: VI 1540793-001 Lab ID

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 11, 2015-14:09

Sampled By : James Angell

Received On : March 12, 2015-11:00

: Water Matrix

: RTH-8D Description

: Race Track Hill Project

Sample Result - Inorganic

800450	D le	DOL	Theirn	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P;1}			0.71	1				
Total Hardness as CaCO3	1940	146	mg/L	1	200.7	03/13/15:202987	200.7	03/13/15:203997
Calcium	514	1	mg/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Magnesium	161	1	mg/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Potassium	14	1	mg/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Sodium	376	(1)	mg/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Total Cations	55.6	991	meq/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Boron	9.1	0.1	mg/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Copper	10	10	ug/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Iron	ND	30	ug/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Manganese	110	10	ug/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Zinc	ND	20	ug/L		200.7	03/13/15:202987	200.7	03/13/15:203997
Gypsum Requirement	0.0		Tons/AF	1	200.7	03/13/15:202987	200.7	03/13/15:203997
SAR	3.7		-		200.7	03/13/15:202987	200.7	03/13/15:203997
Total Alkalinity	250	10	mg/L		2320B	03/13/15:203002	2320B	03/13/15:204019
Hydroxide	ND	10	mg/L		2320B	03/13/15:203002	2320B	03/13/15:204019
Carbonate	ND	10	mg/L		2320B	03/13/15:203002	2320B	03/13/15:204019
Bicarbonate	310	10	mg/L		2320B	03/13/15:203002	2320B	03/13/15:204019
Sulfate	23	2	mg/L		300.0	03/12/15:202962	300.0	03/13/15:204028
Chloride	2060	20*	mg/L		300.0	03/12/15:202962	300.0	03/13/15:204028
Nitrate	2.7	0.5	mg/L		300.0	03/12/15:202962	300.0	03/13/15:20402
Nitrate Nitrogen	0.6	0.1	mg/L		300.0	03/12/15:202962	300.0	03/13/15:204028
Fluoride	ND	0.1	mg/L		300.0	03/12/15:202962	300.0	03/13/15:20402
Total Anions	63.7	2.7	meq/L		2320B	03/13/15:203002	2320B	03/13/15:204019
pH	6.6	100	units		4500-H B	03/17/15:203104	4500HB	03/17/15:20406
E. C.	6490	1	umhos/cm		2510B	03/13/15:202985	2510B	03/13/15:20390
TDS by Summation	3460	1 2 2	mg/L		200.7	03/13/15:202987	200.7	03/13/15:20399
Wet Chemistry ^{P:1} Solids, Total Dissolved (TDS)	4180	20*	mg/L		2540CE	03/13/15:202959	2540C	03/16/15:20400

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 \$Surrogate. * PQL adjusted for dilution.



March 19, 2015 : VI 1540793-001 Lab ID

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

Sampled On : March 11, 2015-14:09 3701 Pegasus Dr., Suite #112 Sampled By : James Angell

Bakersfield, CA 93308 Received On : March 12, 2015-11:00

> : Water Matrix

Description : RTH-8D

Project : Race Track Hill

Sample Result - Organic

C	Discoult	DOL	Linita	Note	Sample Preparation		Sample Analysis	
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
TOCAVT: 1'4	1 73 1				100		1	
TOC	0.8	0.5	mg/L	J. T.	5310C	03/18/15:203198	5310C	03/18/15:204236

ND=Non-Detected, PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 \$Surrogate. * PQL adjusted for dilution.



March 20, 2015

: VI 1540850-003 Lab ID

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 17, 2015-11:46

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

: Ag Water Matrix

: RTH-9D Description

Project : Race Track Hill

Sample Result - Inorganic

The state of the s	Describe	DOL	Units	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
rrigation Suit ^{P:1}								
Total Hardness as CaCO3	1260	144	mg/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Calcium	464	1	mg/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Magnesium	26	1	mg/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Potassium	17	1	mg/L		200.7	03/19/15;203223	200.7	03/19/15:204278
Sodium	321	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Total Cations	39.7	**	meq/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Boron	0.2	0.1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Copper	ND	10	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
ron	ND	30	ug/L		200,7	03/19/15:203223	200.7	03/19/15:204278
Manganese	790	10	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Zinc	30	20	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Gypsum Requirement	0.0		Tons/AF		200.7	03/19/15:203223	200.7	03/19/15:204278
SAR	3.9				200.7	03/19/15:203223	200.7	03/19/15:204278
Total Alkalinity	170	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Hydroxide	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Carbonate	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Bicarbonate	210	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Sulfate	860	20*	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Chloride	820	10*	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Nitrate	1.0	0.5	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Nitrate Nitrogen	0.2	0.1	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Fluoride	ND	0.1	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Total Anions	44.5	42	meq/L		2320B	03/18/15:203166	2320B	03/18/15:204307
pH	7.0		units		4500-H B	03/19/15:203242	4500HB	03/19/15:204225
Б. С .	4000	1	umhos/em		2510B	03/19/15:203224	2510B	03/19/15:204206
TDS by Summation	2720		mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Wet Chemistry ^{P:1} Solids, Total Dissolved (TDS)	2960	20*	mg/L		2540CE	03/18/15:203197	2540C	03/19/15:204208

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 ‡Surrogate, * PQL adjusted for dilution.



March 20, 2015

Lab ID : VI 1540850-003

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 17, 2015-11:46

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

Matrix

: Ag Water

Description

: RTH-9D

Project

: Race Track Hill

Sample Result - Organic

n in the contract of	Damilé	DOL	Linita	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
TOC ^{AVT:14} TOC	0.5	0.5	mg/L		5310C	03/18/15:203198	5310C	03/19/15:204236

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 ‡Surrogate. * PQL adjusted for dilution.



March 20, 2015

Lab ID : VI 1540850-002

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 17, 2015-08:35

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

: Ag Water Matrix

Description : C-12

Project : Race Track Hill

Sample Result - Inorganic

	Donale	DOL	Units	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	PQL	Units	Note	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}				15.3				
Total Hardness as CaCO3	326	-64	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Calcium	101	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Magnesium	18	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Potassium	4	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Sodium	130	1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Total Cations	12.3		meq/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Boron	0.2	0.1	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Copper	ND	10	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Iron	40	30	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Manganese	880	10	ug/L	1	200.7	03/19/15:203223	200.7	03/19/15:204278
Zinc	ND	20	ug/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Gypsum Requirement	0.4		Tons/AF		200.7	03/19/15:203223	200.7	03/19/15:204278
SAR	3.1		77	1 3	200.7	03/19/15:203223	200.7	03/19/15;204278
Total Alkalinity	230	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Hydroxide	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Carbonate	ND	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Bicarbonate	280	10	mg/L		2320B	03/18/15:203166	2320B	03/18/15:204307
Sulfate	110	2	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Chloride	229	5*	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Nitrate	ND	0.5	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Nitrate Nitrogen	ND	0.1	mg/L		300.0	03/18/15:203225	300.0	03/18/15:204247
Fluoride	ND	0.1	mg/L	1	300.0	03/18/15:203225	300.0	03/18/15:204247
Total Anions	13.3	74.0	meq/L	1	2320B	03/18/15:203166	2320B	03/18/15:204307
pH	7.2		units		4500-H B	03/19/15:203242	4500HB	03/19/15:204225
E. C.	1400	1	umhos/em		2510B	03/19/15:203224	2510B	03/19/15:204206
TDS by Summation	872	75	mg/L		200.7	03/19/15:203223	200.7	03/19/15:204278
Wet Chemistry ^{P:1} Solids, Total Dissolved (TDS)	800	20	mg/L		2540CE	03/18/15:203197	2540C	03/19/15:204208

ND=Non-Detected, PQL=Practical Quantitation Limit, Containers; (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives; H2SO4 pH < 2 \$Surrogate. * PQL adjusted for dilution.



March 20, 2015

Lab ID

: VI 1540850-002

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112

Bakersfield, CA 93308

Sampled On : March 17, 2015-08:35

Sampled By : Jim Angell

Received On : March 18, 2015-11:45

Matrix

: Ag Water

Description

: C-1 D

Project

: Race Track Hill

Sample Result - Organic

Constituent	Result	PQL	Units	Note	Sample	Preparation	Samp	le Analysis
Constituent	Result	rQL	Onits	Note	Method	Date/ID	Method	Date/ID
TOC ^{AVT:14} TOC	0.9	0.5	mg/L		5310C	03/18/15:203198	5310C	03/18/15:204236

ND=Non-Detected, PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 ‡Surrogate. * PQL adjusted for dilution.

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112

Bakersfield, CA 93308

APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell

Project: Racetrack Hill

Sample Collection Date: 3/16/2015

Sample ID: RTH-7D

ARF: 75860

APPL ID: AZ12740

QCG: #TPHD-150319A-195115

Method	Analyte	Result	PQL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL	Not detected	50.0	ug/L	3/19/2015	3/23/2015
EPA 8015B-	SURROGATE: OCTACOSANE (S)	94.5	28-142	%	3/19/2015	3/23/2015
	SURROGATE: ORTHO-TERPHENYL (S)	66.7	49-128	%	3/19/2015	3/23/2015

Quant Method: TPHD121.M

Run #: 323011 Instrument: Apollo Sequence: 150323

Dilution Factor: 1 Initials: LA

Printed: 3/24/2015 8:57:10 AM Form 1 - APPL Standard GC - No MC

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112

Bakersfield, CA 93308

APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell

Project: RACETRACK HILL

Sample ID: RTH-8D

Sample Collection Date: 3/11/2015

ARF: 75797

APPL ID: AZ12300

QCG: #TPHD-150312A-194885

Method	Analyte	Result	PQL	Units	Extraction Date	Analysis Date
EPA 8015R-	DIESEL FUEL	280 T3M	50.0	ug/L	3/12/2015	3/12/2015
	SURROGATE: OCTACOSANE (S)	93.9	28-142	%	3/12/2015	3/12/2015
	SURROGATE: ORTHO-TERPHENYL (S)	81.3	49-128	%	3/12/2015	3/12/2015

++(T3M) The analyst has noted that the chromatogram of this sample is mainly higher boiling hydrocarbons.

Quant Method: TPHD121.M

Run #: 311053 Instrument: Apollo Sequence: 150311

Dilution Factor: 1 Initials: LA

Printed: 3/18/2015 8:37:31 AM Form 1 - APPL Standard GC - No MC

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112

Bakersfield, CA 93308

APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell Project: Racetrack Hill

Sample ID: RTH-9D

Sample Collection Date: 3/17/2015

ARF: 75860

APPL ID: AZ12742

QCG: #TPHD-150319A-195115

Method	Analyte	Result	PQL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL	Not detected	50.0	ug/L	3/19/2015	3/23/2015
EPA 8015B-	SURROGATE: OCTACOSANE (S)	94.9	28-142	%	3/19/2015	3/23/2015
	SURROGATE: ORTHO-TERPHENYL (S)	69.3	49-128	%	3/19/2015	3/23/2015

Quant Method: TPHD121.M

Run #: 323013 Instrument: Apollo Sequence: 150323

Dilution Factor: 1 Initials: LA

Printed: 3/24/2015 8:57:11 AM Form 1 - APPL Standard GC - No MC

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112

Bakersfield, CA 93308

Attn: James Angell Project: Racetrack Hill Sample ID: C-1 []

Sample Collection Date: 3/17/2015

APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

ARF: 75860

APPL ID: AZ12741

QCG: #TPHD-150319A-195115

Method	Analyte	Result	PQL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL	Not detected	50.0	ug/L	3/19/2015	3/23/2015
	SURROGATE: OCTACOSANE (S)	95.1	28-142	%	3/19/2015	3/23/2015
	SURROGATE: ORTHO-TERPHENYL (S)	69.8	49-128	%	3/19/2015	3/23/2015

Quant Method: TPHD121.M

Run #: 323012 Instrument: Apollo

Sequence: 150323 Dilution Factor: 1

Initials: LA

Printed: 3/24/2015 8:57:11 AM Form 1 - APPL Standard GC - No MC David L. Dettman. Research Scientist 520-621-4618 (office) 520-621-2672 (fax) dettman@email.arizona.edu



Environmental Isotope Laboratory Department of Geosciences Gould-Simpson Building 1040 E. 4th Street, Building No. 0077 Tucson, Arizona 85721-0077, USA

Kenneth D. Schmidt and Associates Attn: Jim Angell 3701 Pegasus Drive, Suite 112 Bakersfield CA 93308 March 17, 2015

REPORT OF ANALYSES

1 water samples for 5180 and 5D

W number	Sample	δ18Ο ‰	δD ‰
61739	RTH 8D	-7.4	-60

Analytical Precision

0.08

0.9

David Dettman Research Scientist David L. Dettman. Research Scientist 520-621-4618 (office) 520-621-2672 (fax) dettman@email.arizona.edu



Environmental Isotope Laboratory Department of Geosciences Gould-Simpson Building 1040 E. 4th Street, Building No. 0077 Tucson, Arizona 85721-0077, USA

Kenneth D. Schmidt and Associates Attn: Jim Angell 3701 Pegasus Drive, Suite 112 Bakersfield CA 93308 March 20, 2015

REPORT OF ANALYSES

3 water samples for δ18O and δD

W number	Sample	δ18Ο ‰	δD ‰	
61762	RTH-7D	-6.2	-60	
61763	C-1	-8.4	-68	
61764	RTH-9D	-7.4	-65	

Analytical Precision

0.08

0.9

David Dettman Research Scientist

Appendix D

Laboratory Reports



Produced Water Quality Lab Reports

J. J. EGLIN

Submitted By

D. A. GRIESEL

BC LABORATORIES DIL - CORES - SOIL - WATER 3016 UNIDN AVE. + FAIRVIEW 3-0077

BAKERSFIELD, GALIFORNIA Giumarra Vineyards Corp.

P.O. Box 1653

Bakersfield, California

Date Reported: 1/21/60

Date Received: 1/20/60

Laboratory No: 40543

Marked:

"Seepage Pits at Santa Margarita Outcrop" - Sec. 24, T. 29 S., R. 29 E.

IRRIGATION WATER ANALYSIS

Key to Qualitative Classification	l			Kx10 ^s @ 25°C	Boron pp		Sodium Percent	Chloride epm
Class I Excellent to Good Class II Good to Injurious		Les	s unan:	100 100-30	0.		50 50-70	б 5-10
Class III Injurious to Unsatisfactory		Mor	e Than:	800	0.0	2.0	70	10
Sample Description								
Boron, ppm	17.1	III						
Sodium Percentage								
"hloride, epm _x10° at 25°C (Salinity)	55.79 655	III	(1975	ppm)				
Gypsum Application for treating "Residual Sodium Carbonate"								
Lbs. 100% Gyp./Hr *								
*100 Gallons per min. flow rate					مد سم	1.5	50 unhesi	loen
100 dations per main 12011 1000					EC	المدرج	ر استان ساری در سر	
	•				: C1	1,9	75 mg/L	-
Constituents, P. P. M.					B	,	50 mmhes, 75 mg/L 17.1 mg	14
Calcium, (Ca)								i
Magnesium, (Mg)	•				4			1
Sodium, (Na)	1200							
Potassium, (K)					•			
Carbonates, (CO ₃)								
Bicarbonates, (HCO ₃)	3000							
Chlorides, (CL)	1975	•		•				
Sulphates (SO ₄) Nitrate, (NO ₅)								
Fluoride, (F)								
Total Iron, (Fe)								
Total Hardness as CaCos							•	
Total Dissolved Solids, 105°C Total Dissolved Solids Red Heat	3700							

pH or Hydrogen-ion activity

B C LABORATORIES

HORNKOHL LABORATORIES, INC.

CHEMICAL AND TESTING ENGINEERS

714 TRUXTUN AVENUE BAKERSFIELD, CALIFORNIA

Laboratory No. 126,669

January 16, 1961 Marked

Filtered Water XX 1-3-61

Sample

Water

Received

January 3, 1961

Submitted by

Valley Waste Disposal Company

3624 Pierce Road

Bakersfield, California

STATE WATER ANALYSIS

Constituents	Parts Per Million	Grains Per Gallon
Carbonates	0.0	0.00
Bicarbonates	123.2	7.20
Chlorides	1631.2	95•39
Sulphates	96.0	5.61
Sulphides	0.0	0.00
Calcium	476.0	27.84
Magnesium	73.2	4.28
Sodium	465.1	27.20
Potassium	19.6	1.15
Boron	2.0	0.12
Fluorides	0.8	0.05
рН	7.7	
Conductivity - Mhos/cm ³ x 10 ⁶ @ 25 ^o c.	4,906	
Total Solids @ 105°C.	2,826	165.26

Respectfully submitted,

HORNKOHL LABORATORIES, INC.

FF:dh

ALL REPORTS ARE SUBMITTED AS THE CONFIDENTIAL PROPERTY OF CLIENTS. AUTHORIZATION FOR PUBLICATION OF OUR REPORTS, CONCLUSIONS OR EXTRACTS FROM OR REGARDING THEM IS RESERVED PENDING OUR WRITTEN APPROVAL AS A MUTUAL PROTECTION TO CLIENTS, THE PUBLIC AND OURSELVES,

HORNKOHL LABORATORIES, Inc.

CHEMICAL AND TESTING ENGINEERS
714 TRUXTUN AVENUE
BAKERSFIELD, CALIFORNIA

January 22, 1963

Laboratory No. 141,119

Marked Race Track A Sec. Sump $\frac{\#1}{4}$

Sample

Water

Received

January 18, 1963

Submitted by

Valley Waste Disposal Company

3624 Pierce Road

Bakersfield, California

PARTIAL WATER ANALYSIS

CONSTITUENTS	PARTS PER MILLION	GRAINS PER GALLON
CHLORIDES	2709.1	158.43
BORON	17.0	0.99
TOTAL DISSOLVED SOLIDS	5094.8	297.94

Respectfully submitted, HORNKOHL LABORATORIES, INC.

FF:es

HORNKOHL LABORATORIES, Inc.

CHEMICAL AND TESTING ENGINEERS
714 TRUXTUN AVENUE

BAKERSFIELD, CALIFORNIA

December 23, 1964

Laboratory No. 159,375

Marked

Racetrack Filtered Water

Sample

Water

Received

December 18, 1964

Submitted by

Valley Waste Disposal Company

3624 Pierce Road

Bakersfield, California

Constituents	Parts per Million	Grains per Gallon
Boron	11.03	0.65
Chlorides	2553.0	149.30
Total Dissolved Solids	4399.0	257.25

Respectfully submitted,

HORNKOHL LABORATORIES, INC.,

FOR -- Technical Director

eg

OILWELL RESEARCH, INC. HORNKOHL LABORATORIES DIVISION

CHEMICAL AND TESTING ENGINEERS 714 TRUXTUN AVENUE BAKERSFIELD, CALIFORNIA 93302

November 2, 1979

Laboratory No

 $2\Lambda - 785 - 2$

Marked Race Track C

Sample

Water

Received

October 23, 1979

Submitted by

VALLEY WASTE DISPOSAL COMPANY

1804 Oak Street

Bakersfield, CA 93301

Attention: Mr. Dick Burdick

* * * *

SPECIAL STATE WATER ANALYSIS-OILFIELD

Constituents		Milligrams/Liter
Carbonates, CO ₃ Bicarbonates, HCO ₃ Chlorides, Cl Sulfates, SO ₄ Sulfides, S Nitrates, NO ₃ Calcium, Ca Magnesium, Mg Sodium, Na Potassium, K Boron, B Fluorides, F Hardness as CaCO ₃ Total Dissolved Solids Oil & Grease	•	0 · 153 2410 < 5 4 · 6 58 201 10 1395 4 · 9 6 5 · 1 544 4250 35
pH Value	7.6	
Conductivity: Micromhos/cm @ 25°C. Resistivity:	6050	
Ohm Meters @ 25°C.	165	

Respectfully submitted,

Victor P. Hoff

m

4100 PIERCE ROAD, 93308

BAKERSFIELD, CALIFORNIA 93308

PHONE 327-4911

Valley Waste Disposal Company 1400 Easton Drive, Suite 139B Bakersfield, California 93309

Date Reported: 10/19/84 Date Received: 9/28/84 Laboratory No.: 12364

Marked:

V.W.D.

East Side Race Track

Irrigation WATER ANALYSIS

Salinity, EC × 103 (Mmhos/cm) @ 250 C

Below 0.5 Very low salt content, may cause permeability problems.

Below 0.75 Low salinity hazard - sat. for most crops.

0.75 - 1.5 Medium salinity hazard - sat, for moderately salt tolerant crops.

1.5 - 3.0 High salinity hazard - sat. for highly salt tolerant crops.

Very high salinity hazard - generally unsuitable for continual use Over 3.0 except under favorable conditions of soil, climate, tolerance of crop and necessary leaching.

NOTE: This interpretation of EC assumes that 10-20% of the total water applied passes through and below the root zone. In most cases deep percolation losses will satisfy this leaching requirement for the usual crops of the area.

Salinity

EC Mmhos/cm = 5.60

Boron, ppm

Below 0.5 Satisfactory for all crops.

Boron, (B) = 20.

0.5 - 1.0Satisfactory for most crops; sensitive crops may show injury - leaf injury, but yields may not be affected.

Satisfactory for semi-tolerant crops. Sensitive crops usually re-1.0 - 2.0duced in yield and vigor.

2.0 - 4.0 Only talerant crops produce satisfactory yields. Chloride, expressed as epm. Fruit crops in general and many wood arnamentals are chloride sensitive.

Below 2 Satisfactory for all crops.

2 - 10Range associated with leaf burn on chloride sensitive crops.

Generally unsatisfactory for chloride sensitive crops. Above 10

CAUTION: Under high rates of evaporation water with 3 epm chloride has

caused leaf burn on sensitive tree crops.

CHLORIDE (CI) = 52, 4 epm.

SAR Sadium Adsorption Ratio. A calculated valve used to estimate the exchangeable sodium percentage (ESP) of a soil after long term use of the water.

SAR ESP (Water) (lio2)

Below 6 Below 10 No soil permeability problem due to sodium.

10 - 15

Possible permeability problems with fine textured soils

(saturation percentage above 50).

Above 15

Permeability problems likely on all mineral soils with possible exception of very coarse textured soils (satu-

ration percentage below 20).

NOTE: Permeability problems are more probable at a given SAR with waters of low solinity than at high salinity.

*SAR of Water = 54.61

ESP of Soil = 27.76 pHc** = 7.37

Gypsum Requirement = none Lbs. 100% Gyp./Hr./100 Gal./min. (for treating "Residual Sodium Carbonate")

Constituents PPM (parts per million)

Calcium, (Ca) 125. Magnesium, (Mg) 8. Sodium, (Na) 1150.

Nitrate, (NO₃) Nitrate, (N)

(-) 0.4(-) 0.1

7.7

Carbonates, (CO₃) Bicarbonates, (HCO₃) Chlorides, (CI)

0. 230. 1855.

Total Hardness as CaCO₃ 346. pН

Sulphates, (SO₄) : Total Dissolved Solids

(-) 5. 3399.

Adjusted SAR.

(-) refers to "less than".

20.2 gr/gal

** Values of pHc above 8.4 indicate tendency to dissolve lime from soil through which the water moves; values below 8.4 indicate tendency to

B C LABORATORIES





VALLEY WASTE DISPOSAL CO

1400 EASTON DR

SUITE 139B

BAKERSFIELD, CA 93309

Attn.: Larry Miller

Date Reported: 05/04/92 Date Received: 04/22/92

Laboratory No.: 3607-1

Sample Description: RACETRACK - A, SAMPLED 4-22-92

322-5004

WATER ANALYSIS (GENERAL CHEMISTRY)

<u>Constituents</u>	Results	Units	D.L.R.	<u> Method</u>
Calcium	188.	mg/L	0.1	CW 7740
Magnesium	9.0	mg/L	0.01	SW-7140
Sodium	1290.	mg/L	0.01	SW-7450
Potassium	16.5	mg/L		SW-7770
Total Cations	66.7	meq/L	0.1	SW-7610
Hydroxide	None Detected		0.01	Calculated
Carbonate	None Detected	mg/L	0.8	SM-403
Bicarbonate	465.	mg/L	2.6	SM-403
Chloride		mg/L	2.6	SM-403
Sulfate	2010.	mg/L	1.8	EPA-300.0
Nitrate as NO3	None Detected	mg/L	5.	EPA-300.0
Nitrate as N	None Detected	mg/L	0.4	EPA-300.0
	None Detected	mg/L	0.1	EPA-300.0
Total Anions	64.3	meq/L	0.01	Calculated
pH	7.6	pH Units	0.1	SW-9040
Electrical Conductivity				
@ 25 C	7100.	umhos/cm	1.	SW-9050
Total Dissolved Solids				
by summation	3750.	mg/l	10.	Calculated
Hardness as CaCO3	506.	mg/L	0.3	Calculated
SAR	24.9	-	0.01	Calculated
Adjusted SAR	61.6	_	0.01	Calculated
ESP	26.2	-	0.01	Calculated
рНс	6.93	_	0.01	Calculated
Gypsum Requirement			0.01	carcarated
# 100% Gyp/Hr/100 Gal/Min	NONE	#100% gyp./	0.01	Calculated

D.L.R. = Detection Limit for Reporting purposes.

REFERENCES:

EPA = "Methods for Chemical Analysis of Water and Wastes", EPA-600, 14-79-020.

SM = "Standard Methods for Examination of Water and Wastewater", 16th Edition 1986.

SW = "Test Methods for Evaluating Solid Wastes Physical/Chemical Methods",

SW 846, September, 1986.

Department Supervisor

Lab Sheet 8 ZALCO LABORATORIES, INC.



Analytical & Consulting Services_

Valley Waste Disposal 1400 Easton Drive, #139B Bakersfield, CA 93309

Laboratory No: 36035 Date Received: 5-28-93 Date Reported: 6-8-93

Attention: Larry Bright

Sample: Water

Sample Description: Produced Water, Valley Waste Edison Field Section 34, Incoming Water Monitoring Program #92-110

Sampled by Larry Miller on 5-28-93 at 1600 hours

Method/ <u>Reference</u>	Constituent	<u>Results</u>	MRL
407A/2	Chloride, Cl, mg/l	2250	5.0
200.7/1	Boron, B, mg/l	16	0.1
120.1/1	Specific Conductance, $\mu { m mhos/cm}$ at 25 °C	7400	10

MRL = Minimum Reporting Level

References:

1. EPA 600/4-79-020, March 1983.

2. APHA Standard Methods, 16th Edition, 1985.

Jim Etherton

Lab Operations Manager

JE/ccw .

4309 Armour Avenue

Bakersfield, California 93308_

[805] 395-0539

FAX (805) 395-3069



ZALCO LABORATORIES, INC.

Analytical & Consulting Services_

Valley Waste Disposal 1400 Easton Drive, #139-B Bakersfield, CA 93309

Laboratory No: Laboratory No: Date Received: 36408-2 7-2-93 Date Reported: 7-15-93

Attention:

Larry Bright

Sample Identification: Rt,A Incoming Water

Sampled by Larry Miller on 7-1-93

IRRIGATION WATER ANALYSIS

рΗ Specific Conductance, 8.0

(micromhos/cm @ 25 C)

6190

Constituents	mg/1	meg/1
Calcium, Ca	160	7.98
Magnesium, Mg	8.4	0.69
Sodium, Na (calculated)	1180	51.27
Potassium, K	14	0.36
Alkalinity as:		
Hydroxide, OH	0	0
Carbonate, CO3	0	0
Bicarbonate, HCO3	530	8.66
Chloride, Cl	1830	51.53
Sulfate, SO4	5.3	0.11
Nitrate, NO3	< 1.0	0
Totals (Sum)	3450	120.61
Boron, B	14	
Total Dissolved Solids, (Grav)	3570	
Calculated Hardness, CaCO3	430	
Sodium Adsorption Ratio, SAR	24.6	
Exchangeable Sodium Percentage, ESP	25.9	
Cation/Anion Balance, %	-1.47	
Sodium, Na (determined), mg/l	1100	
Langelier Scale Index	1.11	

Jim'Etherton

Laboratory Director

4309 Armour Avenue Bakersfield, California 93308_

(805) 395-0539

FAX (805) 395-3069



ZALCG_ABORATORIES, INC.

Analytical & Consulting Services

4309 Armour Avenue Bakersfield, California 93308

(805) 395-0539 FAX (805) 395-3069

Valley Waste Disposal 1400 Easton Drive, Suite 139B Bakersdield, CA 93389

Laboratory No: Date Received: Date Reported: 60008-3 10-2-95 10-10-95

Attention:

Larry Bright

Sample Identification: Racetrack A Section

Sampled by Larry Bright on 10-2-95

IRRIGATION WATER ANALYSIS

Нq

8.2

Electrical Conductivity, EC

(millimhos/cm @ 25 C)

6.87

Constituents	mg/l	meq/l
Calcium, Ca	170	8.48
Magnesium, Mg	13	1.07
Sodium, Na (calculated)	1300	55.77
Potassium, K	16	0.41
Alkalinity as:		
Hydroxide, OH	0	0
Carbonate, CO3	0	0
Bicarbonate, HCO3	480	7.94
Chloride, Cl	2000	57.79
Sulfate, SO4	< 5.0	0
Nitrate, NO3	< 1.0	0
Totals (Sum)	3800	131.46
Boron, B	13	
Total Dissolved Solids, (Grav)	3900	
Calculated Hardness, CaCO3	430	
Sodium Adsorption Ratio, SAR	25.5	
Exchangeable Sodium Percentage, I	ESP 26.7	
Cation/Anion Balance, %	0.29	
Sodium, Na (determined), mg/l	1300	
Langelier Scale Index	1.70	
Gypsum Requirement, lbs/ac-ft	0	

Jim Etherton

Laboratory Director



ZALCO ABORATORIES, IN Analytical & Consulting Services

Lab Sheet 11

4309 Armour Avenue Bakersfield, California 93308

(805) 395-0539 FAX (805) 395-3069

Valley Waste Disposal

1400 Easton Drive, Suite 139B

Bakersfield, CA 93309

Laboratory No:

69325-1

Date Received:

7-14-97

Date Reported:

7-22-97

Attention:

Larry Miller

Sample Identification:

R.T.A.

Sampled by Client on 7-13-97 at 1000 hours

IRRIGATION WATER ANALYSIS

рH

7.9

6.64

Electrical Conductivity, EC (millimhos/cm @ 25 C)

Constituents	mg/l	meg/1
Calcium, Ca	180	8.98
Magnesium, Mg	11	0.91
Sodium, Na (calculated)	1200	53.29
Potassium, K	14	0.36
Alkalinity as:		
Hydroxide, OH	0	0
Carbonate, CO3	0	0
Bicarbonate, HCO3	430	7.02
Chloride, Cl	2000	56.38
Sulfate, SO4	6	0.13
Nitrate, NO3	< 1.0	0
Totals (Sum)	3600	127.07
Boron, B	15	
Total Dissolved Solids, (Grav)	3800	
Calculated Hardness, CaCO3	490	
Sodium Adsorption Ratio, SAR	24	
Exchangeable Sodium Percentage, ESP	25.5	
Cation/Anion Balance, %	1.24	
Sodium, Na (determined), mg/l	1300	
Langelier Scale Index		
penderier poere minex	1.37	
Gypsum Requirement, lbs/ac-ft	0	

Jim Etherton

Laboratory Director



ZALCO LABORATORIES, INC.

Analytical & Consulting Services

4309 Armour Avenue Bakersfield, California 93308

(661) 395-0539 FAX (661) 395-3069

Valley Water Management Company

Project: Master

Work Order No.: 1307211

7500 Meany Avenue

Project #:

Reported: 07/23/2013

Bakersfield, CA 93308

Attention: Russell Emerson

Received: 07/18/2013 12:30

Lab Sample ID: 1307211-01

Collected By:

Client Sample ID: Produced Water RTC-Plant

Date Collected: 7/18/2013 10:25:00AM

							Date	Date	
Analyte	Results	PQL		Units	Flag	Method	Prepared	Analyzed	Init.
General Chemistry			MCL Limits						
Electrical Conductivity	5.7	0.010		mmhos/cm		SM 25108	7/18/13	7/23/13	MSS
Chloride	1800	200		mg/L		EPA 300.0	7/22/13	7/22/13	LME
Metals									
Boron	14	0.10		mg/L		EPA 200.7	7/23/13	7/23/13	ss



ZALCO LABORATORIES, INC.

Analytical & Consulting Services

4309 Armour Avenue Bakersfield, California 93308 (661) 395-0539 FAX (661) 395-3069

Valley Water Management Company

Lab Sample ID: 1410322-01

Project: Master

Work Order No.: 1410322

7500 Meany Avenue

Project #:

Reported: 11/07/2014

Bakersfield, CA 93308

rioject #.

Received: 10/24/2014 10:50

Attention: Russell Emerson

Collected By: Russell Emerson

Client Sample ID: RTC Discharge Water

Date Collected: 10/24/2014 12:00:00AN

							Date	Date	
Analyte	Results	PQL		Units	Flag	Method	Prepared	Analyzed	Init.
Alkalinity									
Total Alkalinity	290	10		mg/L		SM 2320B	10/24/14	10/24/14	SAM
Bicarbonate (HCO3)	290	10		mg/L		SM 2320B	10/24/14	10/24/14	SAM
Carbonate (CO3)	<10	10		mg/L		SM 2320B	10/24/14	10/24/14	SAM
Hydroxide (OH)	<10	10		mg/L		SM 2320B	10/24/14	10/24/14	SAM
General Chemistry			MCL Limits						
Electrical Conductivity	5.7	0.010		mmhos/cm		SM 2510B	10/24/14	10/24/14	MSS
Chloride	1500	100		mg/L		EPA 300.0	10/24/14	10/24/14	MSS
MBAS (calculated as LAS, mol wt)	<0.050	0.050	0.5	mg/L		SM 5540C	10/27/14	10/27/14	HG
pΗ	7.49			pH Units		EPA 150.1	10/24/14	10/24/14	SAM
Specific Conductance	5700	10		umhos/cm		SM 2510B	10/24/14	10/24/14	MSS
Sulfate as SO4	18	0.50		mg/L		EPA 300.0	10/24/14	10/24/14	MSS
Total Dissolved Solids	3000	10		mg/L		SM 2540C	10/27/14	10/27/14	MSS
Hardness									
Hardness (as CaCO3)	290	2.0		mg/L		SM 2340B	10/27/14	10/27/14	SS
Inorganic Chemical			MCL Limits						
Copper	<50	50	1000	ug/L		EPA 200.7	10/27/14	10/27/14	SS
Iron	130	100	300	ug/L		EPA 200.7	10/27/14	10/27/14	SS
Manganese	97	20	50	ug/L		EPA 200.7	10/27/14	10/27/14	SS
Silver	<10	10	100	ug/L		EPA 200.7	10/27/14	10/27/14	SS
Zinc	<50	50	5000	ug/L		EPA 200.7	10/27/14	10/27/14	SS
Metals									
Boron	13	0.10		mg/L		EPA 200.7	10/27/14	10/27/14	SS
Calcium	100	0.050		mg/L		EPA 200.7	10/27/14	10/27/14	SS
Magnesium	10	0.050		mg/L		EPA 200.7	10/27/14	10/27/14	SS
Potassium	12	0.50		mg/L		EPA 200.7	10/27/14	10/27/14	SS
Sodium	1300	7.0		mg/L		EPA 200.7	10/27/14	10/27/14	SS

NSS: Non Sufficient Sample H: Exceeds Analysis Hold Time truc: Total Threshold Limit Concentration STLC: Soluble Threshold Limit Concentration TCLP: Toxicity Characteristic Leaching Procedure MCL: Maximum Contaminant Level *: See Case Narrative *: See Case Narrative *: See Case Narrative *: MCL: Maximum Contaminant Level *: See Case Narrative *: See Case Narrative *: See Case Narrative *: MCL: Maximum Contaminant Level *: See Case Narrative *: See Case Narra

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Note: Samples analyzed for regulatory purposes should be put on ice immediately after sampling and received by the laboratory at temperatures between 0-6°C. Microbiological analysis requires samples to be at least 4-10°C when received at the laboratory. For additional information regarding the limitations of the method(s) referred to, please call us at 661-395-0539.



ZALCO LABORATORIES, INC.

Analytical & Consulting Services

4309 Armour Avenue Bakersfield, California 93308 (661) 395-0539 FAX (661) 395-3069

Valley Water Management Company

Project: Master

Work Order No.: 1501060

7500 Meany Avenue

Project #:

Reported: 01/14/2015

Bakersfield, CA 93308

Attention: Russell Emerson

Received: 01/07/2015 10:30

Lab Sample ID: 1501060-01

Collected By: Russell Emerson

Client Sample ID: Pond Effluent

Date Collected: 1/6/2015 10:00:00AM

							Date	Date	
Analyte	Results	PQL		Units	Flag	Method	Prepared	Analyzed	Init.
Alkalinity									
Total Alkalinity	280	10		mg/L		SM 2320B	1/7/15	1/7/15	SAM
Bicarbonate (HCO3)	280	10		mg/L		SM 2320B	1/7/15	1/7/15	SAM
Carbonate (CO3)	<10	10		mg/L		SM 2320B	1/7/15	1/7/15	SAM
Hydroxide (OH)	<10	10		mg/L		SM 2320B	1/7/15	1/7/15	SAM
General Chemistry			MCL Limits						
Hexavalent Chromium	<5.0	5.0		ug/L	I-02	E218.6	1/12/15	1/12/15	SAM
Nitrate as NO3	<2.00	2.00	45	mg/L		EPA 300.0	1/8/15	1/8/15	MSS
Electrical Conductivity	5.6	0.010		mmhos/cm		SM 2510B	1/7/15	1/7/15	SAM
Bromide	<0.10	0.10		mg/L		EPA 300.0	1/8/15	1/12/15	MSS
Chloride	1700	200		mg/L		EPA 300.0	1/8/15	1/8/15	MSS
рН	7.33			pH Units		EPA 150.1	1/7/15	1/7/15	SAM
Sulfate as SO4	<0.50	0.50		mg/L		EPA 300.0	1/8/15	1/12/15	MSS
Total Dissolved Solids	3100	10		mg/L		SM 2540C	1/7/15	1/7/15	MSS
Hardness									
Hardness (as CaCO3)	290	2.0		mg/L		SM 2340B	1/12/15	1/12/15	SS
Metals									
Boron	14	0.10		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Chromium	<0.050	0.050		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Arsenic	0.086	0.020		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Calcium	100	0.050		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Iron	0.28	0.10		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Magnesium	9.6	0.050		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Manganese	0.092	0.030		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Sodium	1600	7.0		mg/L		EPA 200.7	1/12/15	1/12/15	SS
Oil & Grease Testing									
Oil & Grease	13.0	5.00		mg/L		EPA 1664	1/8/15	1/8/15	JMM
Radiological Testing									
Uranium (pCi/L)	<0.67	0.67		pCi/L		EPA 200.8	1/12/15	1/13/15	MSS
Uranium (ug/L)	<1.0	1.0		ug/L		EPA 200.8	1/12/15	1/13/15	MSS

NSS: Non Sufficient Sample H: Exceeds Analysis Hold Time TTLC: Total Threshold Limit Concentration STLC: Soluble Threshold Limit Concentration TCLP: Toxicity Characteristic Leaching Procedure MCL: Maximum Contaminant Level *: See Case Narrative

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Note: Samples analyzed for regulatory purposes should be put on ice immediately after sampling and received by the laboratory at temperatures between 0-6°C. Microbiological analysis requires samples to be at least 4-10°C when received at the laboratory. For additional information regarding the limitations of the method(s) referred to, please call us at 661-395-0539.

Lab Sheet 15A



May 21, 2015 Lab ID : VI 1541268-002

Customer ID : 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112 Sampled On : April 20, 2015-15:10

Bakersfield, CA 93308 Sampled By : James Angell

Received On : April 22, 2015-11:30 : Drinking Water Matrix

Description : Racetrack Hill Influent

Project : Race Track Hill

Sample Result - Inorganic

Constituent	Result	PQL	Units	MCL/AL	Sample	Preparation	Samp	le Analysis
	Result	1 QL	Onits	WICL/AL	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}								
Total Hardness as CaCO3	265		mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Calcium	88	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Magnesium	11	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Potassium	17	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Sodium	923	5*	mg/L		200.7	04/25/15:204816	200.7	04/27/15:206270
Total Cations	45.9		meq/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Boron	12.6	0.1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Copper	ND	10	ug/L	1000^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Iron	370	30	ug/L	300^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Manganese	120	10	ug/L	50^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Zinc	30	20	ug/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Gypsum Requirement	4.9		Tons/AF		200.7	04/25/15:204816	200.7	04/25/15:206184
SAR	24.7				200.7	04/25/15:204816	200.7	04/25/15:206184
Total Alkalinity	330	10	mg/L		2320B	04/27/15:204887	2320B	04/27/15:206268
Hydroxide	ND	10	mg/L		2320B	04/27/15:204887	2320B	04/27/15:206268
Carbonate	ND	10	mg/L		2320B	04/27/15:204887	2320B	04/27/15:206268
Bicarbonate	410	10	mg/L		2320B	04/27/15:204887	2320B	04/27/15:206268
Sulfate	3	2	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Chloride	1370	20*	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Nitrate	ND	0.4	mg/L	45	4500NO3F	04/29/15:204972	4500NO3F	04/29/15:206391
Nitrate Nitrogen	ND	0.1	mg/L	10	4500NO3F	04/29/15:204972	4500NO3F	04/29/15:206391
Fluoride	3.3	0.1	mg/L	2	300.0	04/22/15:204880	300.0	04/23/15:206326
Total Anions	45.6		meq/L		2320B	04/27/15:204887	2320B	04/27/15:206268
pН	7.4		units		4500-H B	04/23/15:204734	4500HB	04/23/15:206085
E. C.	4630	1	umhos/cm	1600^{2}	2510B	04/23/15:204719	2510B	04/23/15:206051
TDS by Summation	2830		mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Wet Chemistry ^{P:1}		-						
Solids, Total Dissolved (TDS)	2560	20	mg/L	1000^{2}	2540CE	04/23/15:204727	2540C	04/24/15:206120

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (P) Plastic Preservatives: N/A \$Surrogate. * PQL adjusted for dilution. MCL = Maximum Contamination Level. 2 - Secondary Standard. 3 - CDPH Notification Level. AL = Regulatory Action Level.

Lab Sheet 15B

EPA 8015B TPH Diesel Water

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112

Bakersfield, CA 93308

APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell Project: Racetrack Hill

ARF: 76199

Sample ID: Racetrack Hill Influent Sample Collection Date: 4/20/2015 APPL ID: AZ14953

QCG: #TPHD-150423A-196288

Method	Analyte	Result	PQL	MDL	Units	Extraction Date	Analysis Date
FPA 8015B-	DIESEL FUEL	5000 ++	50.0	40.40	ug/L	04/23/15	04/24/15
그 그렇게 하게 없어가죠 하게 됐네다.	SURROGATE: OCTACOSANE (S)	156 #	28-142		%	04/23/15	04/24/15
	SURROGATE: ORTHO-TERPHENYL (97.9	49-128		%	04/23/15	04/24/15

Quant Method: TPHD121.M

Run #: 424019 Instrument: Apollo Sequence: 150424

Dilution Factor: 1 Initials: LA

> Printed: 5/7/2015 11:06:53 AM APPL-F1-SC-NoMC-REG MDLs

^{# =} Recovery (or RPD) is outside QC limits.

⁺⁺⁽T6) The analyst has noted that the chromatogram of this sample is mainly a match to hydrocarbons within the range of diesel fuel.

Appendix D2

Off-Site Well Lab Reports



Analytical Chemists

May 21, 2015 Lab ID : VI 1541268-001

Customer ID : 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112 Sampled On : April 20, 2015-14:06

Bakersfield, CA 93308 Sampled By : James Angell

Received On : April 22, 2015-11:30 : Drinking Water Matrix

Description : Well 26B

Project : Race Track Hill

Sample Result - Inorganic

Constituent	Result	PQL	Units	MCL/AL	Sample	Preparation	Samp	le Analysis
	Result	1 QL	Omts	WICL/AL	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}								
Total Hardness as CaCO3	72.4		mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Calcium	29	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Magnesium	ND	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Potassium	4	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Sodium	114	1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Total Cations	6.5		meq/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Boron	0.1	0.1	mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Copper	ND	10	ug/L	1000^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Iron	ND	30	ug/L	300^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Manganese	20	10	ug/L	50^{2}	200.7	04/25/15:204816	200.7	04/25/15:206184
Zinc	ND	20	ug/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Gypsum Requirement	0.7		Tons/AF		200.7	04/25/15:204816	200.7	04/25/15:206184
SAR	5.8				200.7	04/25/15:204816	200.7	04/25/15:206184
Total Alkalinity	110	10	mg/L		2320B	04/23/15:204721	2320B	04/23/15:206104
Hydroxide	ND	10	mg/L		2320B	04/23/15:204721	2320B	04/23/15:206104
Carbonate	ND	10	mg/L		2320B	04/23/15:204721	2320B	04/23/15:206104
Bicarbonate	130	10	mg/L		2320B	04/23/15:204721	2320B	04/23/15:206104
Sulfate	191	2	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Chloride	35	1	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Nitrate	ND	0.5	mg/L	45	300.0	04/22/15:204880	300.0	04/23/15:206326
Nitrate Nitrogen	ND	0.1	mg/L	10	300.0	04/22/15:204880	300.0	04/23/15:206326
Fluoride	0.2	0.1	mg/L	2	300.0	04/22/15:204880	300.0	04/23/15:206326
Total Anions	7.1		meq/L		2320B	04/23/15:204721	2320B	04/23/15:206104
рН	7.7		units		4500-H B	04/23/15:204734	4500HB	04/23/15:206085
E. C.	750	1	umhos/cm	1600^{2}	2510B	04/23/15:204719	2510B	04/23/15:206051
TDS by Summation	503		mg/L		200.7	04/25/15:204816	200.7	04/25/15:206184
Wet Chemistry ^{P:1}								
Solids, Total Dissolved (TDS)	490	20	mg/L	1000^{2}	2540CE	04/23/15:204727	2540C	04/24/15:206120

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (P) Plastic Preservatives: N/A ‡Surrogate. * PQL adjusted for dilution. MCL = Maximum Contamination Level. 2 - Secondary Standard. 3 - CDPH Notification Level. AL = Regulatory Action Level.

EPA 8015B TPH Diesel Water

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112 Bakersfield, CA 93308

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell Project: Racetrack Hill

ARF: 76199

APPL Inc.

Sample ID: Well 26B

APPL ID: AZ14952

Sample Collection Date: 4/20/2015

QCG: #TPHD-150423A-196288

Method	Analyte	Result	PQL	MDL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL	100 ++	50.0	40.40	ug/L	04/23/15	04/24/15
EPA 8015B-	SURROGATE: OCTACOSANE (S) SURROGATE: ORTHO-TERPHENYL (82.9 67.6	28-142 49-128		% %	04/23/15 04/23/15	04/24/15 04/24/15

++(T3M) The analyst has noted that the chromatogram of this sample is mainly higher boiling hydrocarbons.

Quant Method: TPHD121.M

Run #: 424018

Instrument: Apollo Sequence: 150424

Dilution Factor: 1 Initials: LA

> Printed: 5/7/2015 11:06:53 AM APPL-F1-SC-NoMC-REG MDLs



May 21, 2015 Lab ID : VI 1541268-004

Customer ID : 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112 Sampled On : April 21, 2015-08:45

Bakersfield, CA 93308 Sampled By : James Angell

Received On : April 22, 2015-11:30 : Drinking Water Matrix

Description : Well 24J

Project : Race Track Hill

Sample Result - Inorganic

Constituent	Result	PQL	Units	MCL/AL	Sample	Preparation	Samp	le Analysis
	Result	1 QL	Omts	WICL/AL	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}								
Total Hardness as CaCO3	276		mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Calcium	71	1	mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Magnesium	24	1	mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Potassium	5	1	mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Sodium	35	1	mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Total Cations	7.2		meq/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Boron	ND	0.1	mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Copper	ND	10	ug/L	1000^{2}	200.7	05/18/15:205769	200.7	05/18/15:207384
Iron	ND	30	ug/L	300^{2}	200.7	05/18/15:205769	200.7	05/18/15:207384
Manganese	ND	10	ug/L	50^{2}	200.7	05/18/15:205769	200.7	05/18/15:207384
Zinc	ND	20	ug/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Gypsum Requirement	0.05		Tons/AF		200.7	05/18/15:205769	200.7	05/18/15:207384
SAR	0.9				200.7	05/18/15:205769	200.7	05/18/15:207384
Total Alkalinity	210	10	mg/L		2320B	04/28/15:204904	2320B	04/28/15:206334
Hydroxide	ND	10	mg/L		2320B	04/28/15:204904	2320B	04/28/15:206334
Carbonate	ND	10	mg/L		2320B	04/28/15:204904	2320B	04/28/15:206334
Bicarbonate	260	10	mg/L		2320B	04/28/15:204904	2320B	04/28/15:206334
Sulfate	95	2	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Chloride	20	1	mg/L	500^{2}	300.0	04/22/15:204880	300.0	04/23/15:206326
Nitrate	15.6	0.5	mg/L	45	300.0	04/22/15:204880	300.0	04/23/15:206326
Nitrate Nitrogen	3.5	0.1	mg/L	10	300.0	04/22/15:204880	300.0	04/23/15:206326
Fluoride	0.3	0.1	mg/L	2	300.0	04/22/15:204880	300.0	04/23/15:206326
Total Anions	7.1		meq/L		2320B	04/28/15:204904	2320B	04/28/15:206334
рН	7.4		units		4500-H B	04/23/15:204734	4500HB	04/23/15:206085
E. C.	667	1	umhos/cm	1600^{2}	2510B	04/23/15:204719	2510B	04/23/15:206051
TDS by Summation	526		mg/L		200.7	05/18/15:205769	200.7	05/18/15:207384
Wet Chemistry ^{P:1}								
Solids, Total Dissolved (TDS)	440	20	mg/L	1000^{2}	2540CE	04/23/15:204727	2540C	04/24/15:206120

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (P) Plastic Preservatives: N/A ‡Surrogate. * PQL adjusted for dilution. MCL = Maximum Contamination Level. 2 - Secondary Standard. 3 - CDPH Notification Level. AL = Regulatory Action Level.

EPA 8015B TPH Diesel Water

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112 Bakersfield, CA 93308

908 North Temperance Avenue

Clovis, CA 93611

APPL Inc.

Attn: James Angell Project: Racetrack Hill

ARF: 76199

Sample ID: Well 24J

APPL ID: AZ14955

Sample Collection Date: 4/21/2015

QCG: #TPHD-150423A-196288

Method	Analyte	Result	PQL	MDL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL SURROGATE: OCTACOSANE (S) SURROGATE: ORTHO-TERPHENYL (Not detected 82.9 64.0	50.0 28-142 49-128	40.40	ug/L % %	04/23/15 04/23/15 04/23/15	04/24/15 04/24/15 04/24/15

Quant Method: TPHD121.M

Run #: 424021 Instrument: Apollo Sequence: 150424

APPL-F1-SC-NoMC-REG MDLs

Dilution Factor: 1

Initials: LA Printed: 5/7/2015 11:06:53 AM



Analytical Chemists

April 22, 2015 Lab ID : VI 1541145-001

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112 Sampled On : April 9, 2015-16:10

Bakersfield, CA 93308 Sampled By : Dee Jaspar

Received On : April 11, 2015-14:11

: Ag Water Matrix

Description : T29S/R29E-16H Project : Race Track Hill

Sample Result - Inorganic

Constituent	Result	PQL	Units	Note	Sample	Preparation	Samp	le Analysis
Constituent	Kesuit	1 QL	Onits	Note	Method	Date/ID	Method	Date/ID
Irrigation Suit ^{P:1}								
Total Hardness as CaCO3	66.5		mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Calcium	25	1	mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Magnesium	1	1	mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Potassium	2	1	mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Sodium	99	1	mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Total Cations	5.7		meq/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Boron	0.2	0.1	mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Copper	ND	10	ug/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Iron	190	30	ug/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Manganese	290	10	ug/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Zinc	90	20	ug/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Gypsum Requirement	0.7		Tons/AF		200.7	04/14/15:204307	200.7	04/14/15:205660
SAR	5.3				200.7	04/14/15:204307	200.7	04/14/15:205660
Total Alkalinity	140	10	mg/L		2320B	04/14/15:204293	2320B	04/14/15:205530
Hydroxide	ND	10	mg/L		2320B	04/14/15:204293	2320B	04/14/15:205530
Carbonate	ND	10	mg/L		2320B	04/14/15:204293	2320B	04/14/15:205530
Bicarbonate	170	10	mg/L		2320B	04/14/15:204293	2320B	04/14/15:205530
Sulfate	18	2	mg/L		300.0	04/17/15:204570	300.0	04/17/15:206004
Chloride	75	1	mg/L		300.0	04/17/15:204570	300.0	04/17/15:206004
Nitrate	ND	0.5	mg/L		300.0	04/17/15:204570	300.0	04/17/15:206004
Nitrate Nitrogen	ND	0.1	mg/L		300.0	04/17/15:204570	300.0	04/17/15:206004
Fluoride	0.2	0.1	mg/L		300.0	04/17/15:204570	300.0	04/17/15:206004
Total Anions	5.3		meq/L		2320B	04/14/15:204293	2320B	04/14/15:205530
pН	7.5		units		4500-H B	04/14/15:204321	4500HB	04/14/15:205559
E. C.	570	1	umhos/cm		2510B	04/13/15:204272	2510B	04/13/15:205507
TDS by Summation	390		mg/L		200.7	04/14/15:204307	200.7	04/14/15:205660
Metals, Diss ^{P:1}		-						
Arsenic	4	2	ug/L		200.8	04/14/15:204303	200.8	04/14/15:205578
Wet Chemistry ^{P:1}								
Solids, Total Dissolved (TDS)	310	20	mg/L		2540CE	04/14/15:204320	2540C	04/15/15:205579

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 \$Surrogate. * PQL adjusted for dilution.

Analytical Chemists

April 22, 2015 Lab ID : VI 1541145-001

Customer ID: 4-17878

Kenneth D. Schmidt & Assoc.

3701 Pegasus Dr., Suite #112 Sampled On : April 9, 2015-16:10

Sampled By Bakersfield, CA 93308 : Dee Jaspar

Received On : April 11, 2015-14:11

Matrix : Ag Water

Description : T29S/R29E-16H Project : Race Track Hill

Sample Result - Organic

Constituent	Result	PQL	Units	Note	Sample	Sample Preparation		le Analysis
Constituent	Result	1 QL	Omts	Note	Method	Date/ID	Method	Date/ID
TOC ^{AVT:1'4}								
TOC	0.8	0.5	mg/L		5310C	04/14/15:204285	5310C	04/14/15:205596

ND=Non-Detected. PQL=Practical Quantitation Limit. Containers: (AVT) Amber VOA TFE-Cap, (P) Plastic Preservatives: H2SO4 pH < 2 ‡Surrogate. * PQL adjusted for dilution.

EPA 8015B TPH Diesel Water

Kenneth D. Schmidt & Assoc. 3701 Pegasus Dr., Ste 112 Bakersfield, CA 93308 APPL Inc.

908 North Temperance Avenue

Clovis, CA 93611

Attn: James Angell

Project: RACETRACK HILL

ARF: 76093

Sample ID: T29S/R29E-16H

APPL ID: AZ14417

Sample Collection Date: 4/9/2015

QCG: #TPHD-150413A-195915

Method	Analyte	Result	PQL	Units	Extraction Date	Analysis Date
EPA 8015B-	DIESEL FUEL	Not detected	50.0	ug/L	4/13/2015	4/14/2015
	SURROGATE: OCTACOSANE (S)	69.0	28-142	%	4/13/2015	4/14/2015
	SURROGATE: ORTHO-TERPHENYL (S)	65.6	49-128	%	4/13/2015	4/14/2015

Quant Method: TPHD121.M

Run #: 413090 Instrument: Apollo Sequence: 150413

Dilution Factor: 1

Initials: LA

Printed: 4/24/2015 2:04:45 PM Form 1 - APPL Standard GC - No MC Kennedy/Jenks Consultants 303 Second Street, Suite 300 San Francisco, CA 94107 Reported: 06/19/2015 14:56
Project: Race Track Hill
Project Number: 1365027*00

Project Number: 1365027*00 Project Manager: Stuart Childs

Water Analysis (General Chemistry)

BCL Sample ID:	1514100-01	Client Samp	le Name:	Nickels U	nused Wel	I, 6/9/2015 6:30):00AM, R. Prir	nce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Calcium		110	mg/L	0.10	0.016	EPA-200.7	0.016	40.0.0	1
Total Recoverable Ca	lcium	120	mg/L	0.10	0.014	EPA-200.7	ND		2
Dissolved Magnesium	1	32	mg/L	0.050	0.019	EPA-200.7	ND		1
Total Recoverable Ma	gnesium	33	mg/L	0.050	0.019	EPA-200.7	ND		2
Dissolved Sodium		67	mg/L	0.50	0.051	EPA-200.7	ND		1
Total Recoverable So	dium	68	mg/L	0.50	0.051	EPA-200.7	0.052		2
Dissolved Potassium		8.8	mg/L	1.0	0.10	EPA-200.7	ND		1
Total Recoverable Po	tassium	9.2	mg/L	1.0	0.10	EPA-200.7	ND		2
Bicarbonate Alkalinity	as CaCO3	290	mg/L	4.1	4.1	EPA-310.1	ND		3
Carbonate Alkalinity as	CaCO3	ND	mg/L	4.1	4.1	EPA-310.1	ND		3
Alkalinity as CaCO3		290	mg/L	4.1	4.1	Calc	ND		4
Chloride		42	mg/L	0.50	0.061	EPA-300.0	ND		5
Nitrate as N		0.51	mg/L	0.10	0.018	EPA-300.0	ND		6
Sulfate		200	mg/L	1.0	0.10	EPA-300.0	ND		5
pH		7.47	pH Units	0.05	0.05	EPA-150.1		S05	7
Electrical Conductivit	y @ 25 C	977	umhos/c m	1.00	1.00	EPA-120.1			8
Total Dissolved Solids	s @ 180 C	680	mg/L	33	33	SM-2540C	ND		9
Non-Volatile Organic	Carbon	0.77	mg/L	1.0	0.30	EPA-415.1	ND	J	10

·			Run	·	·	·	QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-200.7	06/10/15	06/18/15 16:45	JRG	PE-OP2	1	BYF1638
2	EPA-200.7	06/11/15	06/15/15 17:21	JRG	PE-OP2	1	BYF1127
3	EPA-310.1	06/11/15	06/11/15 15:46	RML	MET-1	1	BYF1110
4	Calc	06/10/15	06/16/15 14:23	MSA	Calc	1	BYF1029
5	EPA-300.0	06/09/15	06/10/15 11:34	OLH	IC1	1	BYF0917
6	EPA-300.0	06/09/15	06/10/15 04:16	OLH	IC1	1	BYF0917
7	EPA-150.1	06/11/15	06/11/15 15:46	RML	MET-1	1	BYF1110
8	EPA-120.1	06/11/15	06/11/15 15:46	RML	MET-1	1	BYF1110
9	SM-2540C	06/12/15	06/12/15 09:30	CAD	MANUAL	3.333	BYF1047
10	EPA-415.1	06/10/15	06/10/15 22:19	ALW	TOC2	1	BYF0923

Report ID: 1000366083 4100 Atlas Court Bakersfield, CA 93308 (661) 327-4911 FAX (661) 327-1918 www.bclabs.com Page 7 of 19



Kennedy/Jenks Consultants 303 Second Street, Suite 300 San Francisco, CA 94107

Reported: 06/19/2015 14:56 Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Metals Analysis

BCL Sample ID:	1514100-01	Client Sampl	Client Sample Name: Nickels Unused Well, 6/9/2015 6:30:00AM, R. Prince					nce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run#
Dissolved Arsenic		ND	ug/L	50	9.2	EPA-200.7	ND		1
Dissolved Boron		140	ug/L	100	10	EPA-200.7	ND		1
Total Recoverable Ar	senic	8.7	ug/L	50	7.8	EPA-200.7	ND	J	2
Total Recoverable Bo	oron	130	ug/L	100	10	EPA-200.7	ND		2

			Run		QC			
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID	
1	EPA-200.7	06/10/15	06/16/15 17:15	JRG	PE-OP2	1	BYF0991	
2	EPA-200.7	06/11/15	06/15/15 17:21	JRG	PE-OP2	1	BYF1127	

Report ID: 1000366083 Page 8 of 19 Kennedy/Jenks Consultants 303 Second Street, Suite 300 San Francisco, CA 94107

06/19/2015 14:56 Reported: Project: Race Track Hill

Project Number: 1365027*00 Project Manager: Stuart Childs

Total Petroleum Hydrocarbons

BCL Sample ID:	1514100-01	Client Sampl	e Name:	Nickels U	nused Wel	l, 6/9/2015 6:30:0	00AM, R. Prir	nce	
Constituent		Result	Units	PQL	MDL	Method	MB Bias	Lab Quals	Run #
TPH - Crude Oil		ND	ug/L	500	140	EPA-8015B/FFP	ND		1
Tetracosane (Surrogate	e)	48.1	%	37 - 134 (LC	L - UCL)	EPA-8015B/FFP			1

			Run				QC
Run#	Method	Prep Date	Date/Time	Analyst	Instrument	Dilution	Batch ID
1	EPA-8015B/FFP	06/11/15	06/13/15 07:05	MWB	GC-13	1	BYF1189

Page 6 of 19 Report ID: 1000366083



Monthly Produced Water Flows for 2010 Through 2014

Appendix E: Monthly Produced Water Flows for 2010-2014

		Produced W	ater Discharg	e (Barrels)		Monthly
Month	2010	2011	2012	2013	2014	Average
January	211,574	208,592	235,406	355,300	342,775	270,729
February	229,028	214,623	250,248	287,241	281,083	252,445
March	226,744	266,462	323,768	278,204	261,989	271,433
April	267,417	192,062	259,062	278,629	269,642	253,362
May	234,459	192,770	317,935	370,099	343,851	291,823
June	222,473	196,193	241,982	329,681	272,890	252,644
July	274,625	259,834	262,594	283,982	329,612	282,129
August	215,496	192,332	312,376	356,806	258,407	267,083
September	268,847	266,065	264,141	296,558	260,492	271,221
October	212,438	224,264	271,794	364,651	316,547	277,939
November	194,035	249,071	317,012	283,582	241,668	257,074
December	250,108	309,864	280,357	266,827	277,157	276,863
Annual Total	2,807,244	2,772,132	3,336,675	3,751,560	3,456,113	

Appendix F

Report on Runoff Conditions at the Race Track Hill Facility, Kern County, CA



DEE JASPAR & ASSOCIATES, INC.

CONSULTING CIVIL ENGINEERS 2730 UNICORN ROAD, BUILDING A BAKERSFIELD, CA 93308 PHONE (661) 393-4796 FAX (661) 393-4799

June 29, 2015

Report on Storm Runoff Conditions at the Racetrack Hill Facility Kern County, CA

- The Racetrack Hill facility is located on 240 acres in Section 24, T.29S. R.29E. M.D.B.&M. This report estimates the runoff from the hills surrounding the facility to determine if water can be contained by the ponds within the facility.
- The facility is depicted on the attached map. Ponds are superimposed on an aerial photo of the facility. USGS Quadrangle sheets, and contours on the Kern County GIS website were used to delineate the drainage areas. The size of the drainage areas and ponds were developed using the tools on the County website.
- Drainage volumes were estimated from the Kern County Hydrology Manual and the SCS (now NRCS) Bulletin SCS-TP-149. Parameters selected for the site were from the Kern County Hydrology Manual and were as follows:
- 100 Year 24 Hour Precipitation: P = 3.00 inches
- SCS Curve Number: 75
- Total soil capacity: S = 3.33
- Initial abstract: Ia = 0.67"
- Net runoff volumes were estimated from the formula: $Y = (P-Ia)^2/(P-Ia+S) = 0.96$ " (0.08')
- The attached calculation sheet develops the storm yield by area.

It is noted that the maximum 1-day rainfall event in Bakersfield was 2.29". The 24-hour 100 year precipitation amount calculated by the Hydrology Manual of 3.00" was used for this study. The effects of a long-term rainfall were not considered in this report.

The calculation that follows shows that the ponds in each drainage area are capable of containing the maximum 24 hour 100 year event runoff if they are operated with the minimum freeboard that is calculated. This assumes that the interconnections of the ponds (pond overflow piping and connective channels) are capable of transporting the drainage flows. Although it was not addressed by this study, it appears that the connective piping, channels, etc., have been adequate for the past 50 or so years that the facility has been operated as evidenced by the absence of runoff from the site (by inspection of historical photos), and no pond levee failures. Additional flows from longer term rainfall events can be managed by adjusting pond freeboard amounts, and by dewatering certain ponds prior to the rainy season to provide storage space for runoff.

Area #1 (105.5 acres) drains to the east. It is the northern-most area. Area #1 has a significant number of ponds in the central drainage valley and in the small canyons on the north side of the

valley. The contributing area is steep and runoff occurs quite rapidly. Soils are moderately permeable. The Map Unit is 185- Brecken-Cuyama-Pleito complex. This soil type is common to all the drainage areas in the 240- acre facility.

Area #2 (43.9 acres) also drains to the east into Area #3 (23.6 acres). Slopes are steep and soils moderately permeable. The soils support salt-tolerant grasses, trees and shrubs. Soil series is partly 185 (above) and 192 Chanac-Pleito complex in Area #2, and 185 in Area #3.

Area #4 (36.5 acres) drains towards the south but pond capacity is adequate to keep all waters within the boundaries of the facility. Soils slopes are steep. Soils are 185 – Breken-Cuyama-Pleito, moderately permeable.

Area #5 (52.2 acres) on the east side of the facility has minimal storage, amounting to less than an acre-foot. Soil classification is 185. Moderately permeable. Slopes are steep on the west side of the area, steep to moderately sloping on the east portion of the area. Area #5 is also subject to runoff from the lands east of Breckenridge Road (Area #6). Area #6 (30.8 acres) discharges into a drainage channel located on the west side of the road in Area #5 via an 18-inch culvert pipe. Facility operators have stated that during heavy runoff events booster pumps are used to intercept water travelling along the west side of Breckenridge Road. This water is then pumped to vacant uphill ponds, thereby utilizing unused storage space and freeboard.

Therefore it appears that no water leaves the site during rainfall events. It is my opinion that this is due to provision of storage space in the ponds and utilizing pumping when necessary during the rainy season.

Dee Jaspar P E

Runoff Estimate for the Racetrack Hill Facility

<u>Information from the Kern County Hydrology Manual</u>

100 year 24 Hour Precipitation = 3.00"

SCS Curve Number 75

S = (1000/CN)-10 = 3.33

Ia = 0.2 S = 0.67"

 $Y = (P - Ia)^2/(P-Ia+S) = 0.96" = 0.08'$

Runoff Calculations by Area

Area #13.5+1.9

Total Area = 103.5 acres

West & Middle Areas

Area = 76.0 acres

Runoff Yield = 6.1 acre-feet

Pond Area = 6.1 acres

Required freeboard in all ponds = 12" (assuming adequate connectivity)

East Area

Area = 27.5 acres

Runoff Yield = 2.2 acre-feet

Pond Area = 2.0 acres

Required freeboard in all ponds = 14"

Area #2

Area = 43.9 acres

Runoff Yield = 3.5 acre-feet

Pond Area = 3.6 acres

Required freeboard in all ponds = 12"

<u> Area #3</u>

Area = 23.6 acre

Runoff Yield = 1.9 acre-feet

Pond Area = 5.0 acres

Required freeboard in all ponds = 5"

<u>Area #4</u>

This area drains to the south

Area = 36.5 acres

Runoff Yield = 2.9 acre-feet

Pond Area = 3.8 acres

Required freeboard in all ponds = 9"

Area #5

Area = 52.2 acres

Runoff Yield = 4.2 acre-feet


Pond Area = 0.36 acres

Area #6

This area is east of Breckenridge Road

Area = 30.8 acres contributing to Area #5

Runoff Yield = 2.5 acre-feet



DRAWN
DJA

CHECKED
DJA

DATE
DATE
SCALE
AS SHOWN
FILE

JOB NO.

SHEET

RACETRACK HILL FLOOD STUDY

VALLEY WATER MANAGEMENT KERN COUNTY, CALIFORNIA



				REVISION
				ВҮ